

#### Five-Year Review Report

First Five-Year Review Report For Normandy Park Apartments Site 11110 North 56<sup>th</sup> Street Temple Terrace, Florida

September 2006

PREPARED BY:

QORE Property Sciences 1211 Tech Blvd., Suite 200 Tampa, FL 33619

FOR:

United States Environmental Protection Agency
Region 4
Atlanta, Georgia

Approved by:

Reverly 🗗 Banister

Acting Director, Waste Management Division

U.S. EPA, Region 4

Date:

9-28-06



# U.S. EPA REGION IV

# SDMS

# POOR LEGIBILITY

PORTIONS OF THIS DOCUMENT MAY BE DIFFICULT TO VIEW DUE TO THE QUALITY OF THE ORIGINAL.

# TO MAKE THE DOCUMENT READABLE, TRY ONE OR MORE OF THE FOLLOWING:

#### From the Displays Settings in Windows Control Panel:

- 1. Set the Color Quality to the highest available: 24 bit or 36 bit.
- 2. Increase or decrease the Screen resolution.

#### From the Monitor/Display Controls:

- 1. For dark image page, increase the brightness and decrease the contrast.
- 2. For light image page, decrease the brightness and increase the contrast.

\*\* PLEASE CONTACT THE APPROPRIATE RECORDS CENTER TO VIEW THE MATERIAL\*\*

#### FIRST FIVE-YEAR REVIEW REPORT FOR NORMANDY PARK APARTMENTS SITE 11110 NORTH 56<sup>th</sup> STREET TEMPLE TERRACE, FLORIDA QORE Project No. 2148M

#### TABLE OF CONTENTS

	OF ACRONYMS CUTIVE SUMMARY	iv v
	YEAR REVIEW SUMMARY FORM	vi
I.	INTRODUCTION	1
II.	SITE CHRONOLOGY	2
III.	BACKGROUND Physical Characteristics Land and Resource Use History of Contamination Initial Response Basis for Taking Action	3 3 3 3 4
IV.	REMEDIAL ACTIONS Remedy Selection Remedy Implementation Operation and Maintenance	4 4 5 6
V.	PROGRESS SINCE LAST 5-YEAR REVIEW	8
VI.	FIVE-YEAR REVIEW PROCESS  Administrative Components Community Involvement Document Review Data Review Site Inspection Interviews	8 8 9 9 10
VII.	TECHNICAL ASSESSMENT  Question A: Is the remedy functioning as intended by the decision documents?  Question B. Are the exposure assumption, toxicity data, cleanup target levels, and remedial action objectives (RAQs) used at the time of the remedy selection still valid?  Question C: Has any other information come to light that could call into question the protectiveness of the remedy?	11 11 12 12
VIII	ISSUES	12

IX. RECO	MMENDATIONS AND FOLLOW-UP ACTIONS	13
X. PROT	ECTIVENESS STATEMENT	14
XI. NEXT	REVIEW	14
	TABLES	
Table 2- Annu Table 3 - List Table 4- Issue	onology of Site Events nal System Operations/O&M Costs of Interviewees s ommendations and Follow-Up Actions	2 8 10 12 13
	PLATES	
Location Map Apartment Co Areas Excava Monitor Well	mplex Layout ted	Plate 1 Plate 2 Plate 3 Plate 4
	APPENDICES	
Public Notice Listing of Rep Site Inspectio Interview For Restrictive Co	m	Appendix A Appendix B Appendix C Appendix D Appendix E Appendix F Appendix G
Lead and Anti Site Photograp	Appendix H Appendix I	

#### LIST OF ACRONYMS

AOC Administrative Order of Consent

ARAR Applicable or Relevant and Appropriate Requirement

CD Consent Decree

CERCLA Comprehensive Environmental Response, Compensation, and Liability Act

CFR Code of Federal Regulations

EPA United States Environmental Protection Agency FDEP Florida Department of Environmental Protection

FFS Focused Feasibility Study GCR Gulf Coast Recycling, Inc.

HCEPC Hillsborough County Environmental Commission

MCL Maximum Contaminant Level NCP National Contingency Plan NPL National Priorities List O&M Operation and Maintenance

OHM Remediation Services Corporation

PQL Practical Quantitation Level

QORE QORE, Inc.

RCRA Resource Conservation and Recovery Act

RD Remedial Design ROD Record of Decision

SRI Streamlined Remedial Investigation

SDWA Safe Drinking Water Act

WRS WRS Infrastructure & Environment, Inc.

#### **EXECUTIVE SUMMARY**

The remedy for the Normandy Park Apartments Site in Temple Terrace, Florida included removal of at least the top two feet of contaminated soil every where the ground surface was exposed, excluding a specified distance around the existing trees, and filling the excavations with clean fill. Tree plazas were constructed of wood, pavers or mulch within the drip line of the existing, mature trees on site to prevent exposure to contaminated soil. Monitored natural attenuation was selected for contaminated ground water and institutional controls were implemented to prevent the use of ground water at the site and to notify future owners of the apartment complex of the contaminated soil remaining under the site structures (including paved areas and sidewalks). Construction activities were completed and described in the Remedial Action Construction Report dated January 25, 2002. The trigger for this five-year review was the actual start of remedial activities on March 19, 2001.

The assessment of this five-year review found that the remedy was constructed in accordance with the requirements of the Record of Decision (ROD) and the remedy is functioning as designed. The immediate threat of exposure to contaminated soil has been addressed and the remedy is expected to be protective when ground water cleanup goals are achieved through monitored natural attenuation.

# Five-Year Review Summary Form

+ .	-		SITE IDENTIFICATION			
Site name (from WasteLAN): Normandy Park Apartments Site						
EPA ID (from WasteLAN): FLD984229773						
Region: IV	State:	Florida	orida City/County: Temple Terrace/Hillsborough County			
i			SITE STATUS			
NPL status: ΓF	inal ΓDe	leted Γ C	Other (specify) Proposed but deferred in exchange for cooperation			
Remediation sta	tus (cho	ose all tha	nat apply): Γ Under Construction Γ Operating Γ Complete			
Multiple OUs?*	Г YES Г	NO NO	Construction completion date: 11 / 2001			
Has site been pu	ut into re	use? [	TYES F NO			
			REVIEW STATUS			
Lead agency: Г	<u>ΕΡΑ</u> Γ S	State IT	Tribe Γ Other Federal Agency			
Author name: L	awrence	Maron 8	& William Denman			
Author title: LM: WD: Remedial Pr		•	Consultant Author affiliation: LM: QORE Property Sciences WD: U.S. EPA			
Review period:"	07/15/2	005 to	03 / 19 / 2006			
Date(s) of site in	spection	n: 12 / 1	13 / 2005			
Type of review:  Γ Post-SARA Γ Pre-SARA Γ NPL-Removal only Γ <u>Non-NPL Remedial Action Site</u> Γ NPL State/Tribe-lead Γ Regional Discretion						
Review number: Γ 1 (first) Γ 2 (second) Γ 3 (third) Γ Other (specify)						
Triggering action:         Γ Actual RA On-site Construction at Site X       Γ Actual RA Start at OU#         Γ Construction Completion       Γ Previous Five-Year Review Report         Γ Other (specify)						
Triggering action date (from WasteLAN): 03 / 19 / 2001						
Due date (five years after triggering action date): 03 / 19 / 2006						
* ["OU" refers to operable unit.]						

<sup>\* [&</sup>quot;OU" refers to operable unit.]

\*\* [Review period should correspond to the actual start and end dates of the Five-Year Review in WasteLAN.]

#### Five-Year Review Summary Form, cont'd

#### **Issues:**

Maintenance and management personnel at the facility were unaware of the presence of contaminated soil under the tree plazas, sidewalks, pavement, tennis courts and buildings. As a result, they were unaware of the need to maintain the tree plazas and of procedures to follow in the event contaminated soil is exposed. New tenants are also not being informed of the past remedial actions at the site and the presence of contaminated soil on site, even though the risk of exposure is very low.

#### **Recommendations and Follow-up Actions:**

Maintenance and management personnel were informed of the presence of contaminated soil remaining on site and the procedures to follow in the event the soils are exposed. A written description as to the presence and location of contaminated soils should be prepared to provide instruction in the event the current maintenance and management personnel are replaced. The written description should include the steps to follow and people to notify in the event contaminated soil will be exposed. A one-page handout should also be prepared to provide to new and prospective tenants to inform them of the site conditions and history.

#### **Protectiveness Statement(s):**

The remedy is expected to be protective of human health and the environment after the ground water cleanup goals are achieved through monitored natural attenuation.

#### **Other Comments:**

The issue of the management and maintenance personnel not being aware of the presence of contaminated soil was caused by recent personnel changes. These personnel were notified of the presence of contaminated soil and restrictions on exposing the contaminated soil during the on-site interviews. No disturbance to the tree plazas or other structures had occurred since the remedial action was completed.

#### FIRST FIVE YEAR REVIEW REPORT

### Normandy Park Apartments Site 11110 North 56<sup>th</sup> Street Temple Terrace, FL

#### I. INTRODUCTION

The purpose of Five-Year reviews is to determine whether the remedy at a site is protective of human health and the environment. The methods, findings, and conclusions of reviews are documented in Five-Year Review reports. In addition, Five-Year Review reports identify issues found during the review, if any, and recommendations to address them.

The U.S. Environmental Protection Agency (EPA) is preparing this Five-Year review pursuant to CERCLA § 121 and the National Contingency Plan (NCP). CERCLA § 121 states:

If the President selects a remedial action that results in any hazardous substances, pollutants, or contaminants remaining at the site, the President shall review such remedial action no less often than each five years after the initiation of such remedial action to assure that human health and the environment are being protected by the remedial action being implemented. In addition, if upon such review it is the judgment of the President that action is appropriate at such site in accordance with section [104] or [106], the President shall take or require such action. The President shall report to the Congress a list of facilities for which such review is required, the results of all such reviews, and any actions taken as a result of such reviews.

The EPA interpreted this requirement further in the NCP; 40 CFR § 300.430(f)(4)(ii) states:

If a remedial action is selected that results in hazardous substances, pollutants, or contaminants remaining at the site above levels that allow for unlimited use and unrestricted exposure, the lead agency shall review such action no less often than every five years after the initiation of the selected remedial action.

The EPA Region 4 has conducted a Five-Year review of the remedial actions implemented at the Normandy Park Apartments Site in Temple Terrace, Florida. The time period covered by this review was July 15, 2001 through March 19, 2006. The Normandy Park Apartments Site Five-Year Review was led by Mr. William Denman of the EPA, Remedial Project Manager for the Normandy Park Apartments Site, and included employees from QORE, Inc. (QORE), under the direction of Mr. Lawrence J. Maron, P. E. QORE is the environmental consulting firm that prepared the Streamlined Remedial Investigation, and developed and oversaw the remedial action. This report documents the results of the review.

This is the first Five-Year review for the Normandy Park Apartments Site. The triggering action for this review is the initiation of the remedial action on March 19, 2001. There are no operable units at the site. The Five-Year review is required due to the fact that hazardous substances, pollutants, or contaminants remain at the site above levels that allow for unlimited use and unrestricted exposure.

## II. SITE CHRONOLOGY

**Table 1 - Chronology of Site Events** 

Event	Date
Hillsborough County Environmental Protection Commission requests Gulf Coast Recycling (GCR) to conduct subsurface environmental testing	8/1991
The Florida Department of Environmental Regulation, now known as the Florida Department of Environmental Protection (FDEP), referred the site to the EPA	2/1992
The EPA performed surface and subsurface sampling	2/25- 2/26/92
GCR entered an Administrative Order of Consent (AOC) with EPA to abate the immediate threat of exposure to apartment residents	6/1992
OHM Remediation Services Corporation (OHM) submitted a Removal Action Plan	8/1992
The Site was proposed for inclusion in the National Priority List (NPL)	2/13/1995
Interim abatement actions were constructed - Concrete caps were put in place, a fence was erected and a wooden decking system was constructed	10/1995
EPA issued a special notice letter to GCR to conduct a Streamlined Remedial Investigation (SRI), Focused Feasibility Study (FFS) and Risk Assessment at the site	5/12/1998
GCR entered into an AOC to conduct the SRI/FFS	9/30/1998
GCR completed the SRI/FFS	1999
Remedial design start	4/1999
Remedial design complete	6/30/1999
The SRI/FFS were made available to the public and the proposed plan identifying EPA's preferred remedy released to the public for comment	2/17/2000
Record of Decision (ROD) selecting the remedy is signed	5/11/2000
Remedial Design(RD)/Remedial Action (RA) Work Plan submitted to EPA	2/13/2001
Remedial Action construction started	3/19/2001
Remedial Design/Remedial Action Work Plan approved by EPA	5/10/2001
Consent Degree (CD) and Statement of Work filed	6/22/2001
Remedial Action construction completed	11/2001
Remedial Action Construction Report completed	1/25/2002

#### III. BACKGROUND

#### **Physical Characteristics**

The Normandy Park Apartments Site occupies approximately 8.25 acres approximately ½ mile south of Fowler Avenue between 56<sup>th</sup> Street and 53<sup>rd</sup> Street in the City of Temple Terrace, Hillsborough County, Florida (Plate 1). The street address is 11110 North 56<sup>th</sup> Street. The Site is currently developed with a 144 residential unit apartment complex. All portions of the site not covered with apartment structures, swimming pools, tennis court, paved parking and roadways, are either grassed, mulched or covered with tree plazas. The layout of the apartment complex is shown on Plate 2.

#### Land and Resource Use

From 1953 until 1963, GCR operated a battery recycling and secondary lead smelting facility at the site. In 1970, GCR built the Normandy Park Apartments on the property, which remain to date.

The current and the future expected use of the Site is residential. The surrounding area is a mixture of commercial and residential properties, and it is anticipated that this will continue into the future.

Private water-supply wells that are used as a drinking water source are not known to be present in the immediate area of the site. The area has been developed for many years and municipal water is supplied. Future use of ground water in the area is anticipated to remain the same.

#### **History of Contamination**

GCR owned the Site from 1953 until June 2001. During the battery recycling and secondary lead smelting operational period, GCR followed standard industry practices. At the facility, tops of spent lead batteries were chopped off by a hydraulic guillotine or cracked open by some other means. The lead plates were separated and processed for recycling, and the battery casings were disposed. The lead plates were smelted on-site. The process resulted in the release of sulfuric acid and lead into the environment.

The contamination was discovered in August 1991. In response to a citizen's complaint, the Hillsborough County Environmental Protection Commission (HCEPC) investigated the Site. The analysis of samples collected by the HCEPC revealed the presence of lead in on-site soils at concentrations of up to 35,000 milligrams per kilogram (mg/kg) and in the ground water at concentrations at up to 16.7 milligrams per liter (mg/l). In January 1992, private blood test results for three children living at the apartments were publicized. The blood lead concentrations were reportedly 9, 10, and 12 micrograms per deciliter ( $\mu$ g/dl) per unit of whole blood. Two of the three children's blood level results were slightly above or equal to the Center for Disease Control's recommended level of 10  $\mu$ g/dl lead per unit of whole blood. In February 1992, the FDEP referred the Site to the EPA. Sampling conducted by the EPA confirmed widespread lead contamination throughout the Site in levels that threatened human health and the environment.

#### **Initial Response**

Under the direction of EPA's Emergency Response and Removal program, GCR placed concrete caps over two areas significantly affected by battery recycling operations in the northern courtyard

of the apartment complex. In the southern courtyard, a fence was erected around the entire courtyard. Eventually, a wooden decking system was constructed over the entire southern courtyard to prevent direct contact with affected soil. The wood decking system was completed in October 1995.

The Site was proposed for inclusion on the NPL in February 1995. The EPA, however, used its enforcement discretion to defer placing the Site on the NPL in exchange for GCR's cooperation. GCR and EPA entered into an Administrative Order on Consent on September 30, 1998. The consent order required the preparation of a site specific Health and Safety Plan, a Quality Assurance Project Plan, and a Streamlined Remedial Investigation (SRI)/Focused Feasibility Study (FFS) Work Plan. QORE submitted a Health and Safety Plan and Quality Assurance Project Plan to EPA on September 23, 1998. QORE and Environmental Consulting & Technology, Inc. submitted an SRI Work Plan to the EPA in September 1998. The Work Plan was approved by the EPA and incorporated into the Consent Order. The SRI and FFS reports and proposed plan for the Normandy Park Apartments Site were made available to the public in February 2000.

#### **Basis for Taking Action**

#### **Contaminants**

Hazardous substances that have been released at the site in each media include:

Soil Ground Water - Surficial Aquifer
Antimony Antimony
Arsenic Lead

Lead

Based on results of the risk assessment and on comparison of the detected contaminant concentrations to enforceable, health based standards, site related contaminants were present in the surface soil and ground water at the Normandy Park Apartments Site in concentrations which did pose significant noncarcinogenic risks to human health. At many locations throughout the Site, the on-site surface soil contained concentrations of lead above the acceptable level, as determined by the risk assessment, of 420 mg/kg. In addition, antimony and lead were present in the on-site surficial ground water at levels exceeding their respective drinking water standards of 0.015 mg/l for lead and 0.006 mg/l for antimony.

#### IV. REMEDIAL ACTIONS

#### **Remedy Selection**

The ROD for the Normandy Park Apartments Site was signed on May 11, 2000. The remedial action objective for soil contaminants at the Normandy Park Apartments Site was to remove and treat, if necessary, the top two feet of soil throughout the apartment complex and replace with clean fill, thereby eliminating the potential for exposure to surface soil contaminants. The existing concrete caps installed pursuant to the EPA emergency response action, the existing buildings, and the asphalt parking lots would remain in place to act as caps, preventing exposure to the soil underneath. Institutional controls would be used to ensure the soil underneath these structures will be properly treated if the land use changes.

The remedial action objective for ground water was to remove the highly contaminated soil in the southern courtyard, which was a contributing source of ground water contamination. Since removal of this significant source, monitoring of the ground water has taken place to ensure it naturally attenuates to below the cleanup levels.

The EPA selected a preferred remedy consisting of Excavation, On-Site Screening, Ex-Situ Stabilization, Off-Site Disposal, Monitored Natural Attenuation, and Institutional Controls. The preferred remedy required the following:

- Excavation of all exposed soil to a depth of two feet, with the exception of a twenty foot radius around the existing trees
- Removal of the deck in the southern complex and the soil excavated to the water table or as
  deep as possible without jeopardizing the structural stability of the adjacent swimming pool
  and apartment buildings
- Placement of a permeable liner at the base of the excavated areas
- Filling of all excavated areas with clean soil to pre-excavation grade and sodding
- Temporary storage of excavated soil in the open field south of the apartments to allow screening of the soils for compliance with Landfill Disposal Regulations under the Resource Conservation and Recovery Act (RCRA)
- On-site treatment of the soil stored in the open field via ex-situ stabilization if the screening indicates that the soil does not meet the Landfill Disposal Regulations
- Off-site disposal of treated and untreated soil in a regulated landfill
- Monitored natural attenuation of the ground water contaminants
- Institutional controls to limit future use of soil and ground water

#### **Remedy Implementation**

The Remedial Action (RA) work was awarded to WRS Infrastructure & Environment, Inc. (WRS), located in Tampa, Florida. WRS began mobilizing to the site on March 19, 2001. The following are the major components of the RA that were implemented:

- WRS removed the wood deck present in the southern complex and excavated soil up to seven feet below ground surface (bgs)
- The excavated soil from this area was treated with Portland cement and tri-sodium phosphate for disposal.
- WRS excavated soil in the central and northern apartment complexes to a depth of two feet bgs.
- All soil excavated was transported to a Class I Industrial Landfill in Okeechobee, Florida.
- A non-woven polypropylene fabric was placed over the bottom and sides of all of the soil excavations and the excavations filled with a clean fill obtained from an off-site location
- A landscaping contractor installed an irrigation system and sodded the excavated areas once the area was backfilled and graded.
- An independent contractor constructed tree plazas consisting of concrete pavers, wood decking or mulch over the areas being preserved around the existing trees.

The remedial action required by the ROD allowed that soil within a 20-foot radius or the drip-line of the mature oak trees, whichever was greater, should not be excavated. Instead, these areas would be covered with a tree plaza to prevent contact with the soil. During the implementation of the

remedial action, the EPA agreed that the preservation areas could remain in their existing state without the construction of a tree plaza if the total lead concentration in the soil was less than the concentration established by the residential exposure scenario in the site-specific risk assessment approved by the EPA (420 mg/kg). By using this standard, potential damage to the root systems of the trees, especially the mature oaks could be avoided. In areas where the soil lead concentration was less than 420 mg/kg, no tree plaza was constructed, although the area under the large oak tree in the west end of the central complex courtyard and the area at the east end of the northern complex courtyard, adjacent to the playground area, were covered with 6 inches of mulch. WRS completed the construction activities and demobilized August 25, 2001.

The areas that were excavated and the areas in which tree plazas were constructed are shown on Plate 3.

After completion of the remedial action, ground water sampling began to monitor the effect of natural attenuation on the ground water quality (see following Operation and Maintenance section). In addition, an easement was obtained that requires EPA and FDEP approval prior to removing or modifying existing structures that would pose possible exposure to contaminated soil underneath

#### **Operation and Maintenance**

Operation and Maintenance (O&M) at the site consists of the collection of ground water samples on a quarterly basis and maintaining the tree plazas to prevent exposure in areas of elevated lead concentrations. Ground water sampling requirements were initially identified in the "Revised Sampling and Analysis Plan, Remedial Design Ground Water Sampling, Normandy Park Apartments, Tampa, Florida, for Gulf Coast Recycling" dated February 13, 2001. This sampling and analysis plan (SAP) was approved by the EPA in a letter dated May 10, 2001.

No specific O&M manual exists with respect to maintenance of the tree plazas; however, quarterly inspections of the tree plazas will be conducted to assure their integrity and effectiveness. These inspections will coincide with the scheduled quarterly sampling events.

#### **O&M** Operational Summary

The approved SAP required the sampling of eighteen (18) monitor wells at the Normandy Park Apartments Site. Thirteen (13) of these wells are screened within the upper portion of the surficial aquifer (MW-1 through MW-6, MW-7A, and MW-8 through MW-13), two (2) are screened at the base of the surficial aquifer (MW-DSA-1 and MW-DSA-2), and three (3) are screened into the uppermost portion of the Floridan aquifer. The locations of the monitor wells are shown on Plate 4.

Sampling of the required wells began in August 2001, after installation of six new monitor wells required under the SAP. Starting in October 2001, ground water samples were collected quarterly (January, April, July and October) from monitor wells MW-7A, MW-10, MW-11, MW-12, MW-DSA-1 and MW-DSA-2. These samples were analyzed for lead, arsenic, and antimony. Semi-annually (April and October), samples were also collected from existing surficial monitor wells MW-1, MW-2, and MW-8, and from the existing Floridan aquifer monitor well PZ-1, and analyzed for the same parameters.

Changes to the ground water monitoring plan were proposed and subsequently approved by the EPA in a March 27, 2003 letter. The changes that were approved were:

- 1. Sampling of all of the monitoring program wells on a semi-annual basis, except for wells MW-7A and MW-11. These two wells are sampled quarterly.
- 2. Analysis of the samples for arsenic concentrations only once per year, during the October sampling event.
- 3. Addition of sampling of monitor well MW-5 semi-annually. The sample from this well is analyzed only for antimony.

In addition to these changes, the installation of a surficial aquifer monitor well was recommended along the western property boundary, approximately midway between wells MW-2 and MW-5 in the report (dated October 23, 2003) that presented the results of the July and April 2003 sampling events. This well (identified as well MW-13) was recommended to provide a point for the measurement of ground water elevation that was needed to better define the direction of ground water flow along the western property line and to identify and evaluate the extent of elevated antimony concentrations in the ground water. A ground water flow map for the site is provided in Appendix A, Plate 2. The installation of this well was approved by the EPA and subsequently installed on June 17, 2004. Sampling of this well occurs semi-annually.

Reports of the ground water sampling results are submitted to the EPA after completion of each of the ground water sampling events. The most recent of the sampling events is described in the report prepared by QORE entitled "April 2006 Sampling Event, Remedial Action Ground Water Sampling, Normandy Park Apartments, Tampa, Florida, For Gulf Coast Recycling, QORE Project No. 2148M", dated June 26, 2006. A copy of this report is provided in Appendix A and the results of the ground water monitoring are presented in Table 2 of the report.

O&M activities with respect to maintaining the tree plazas have been minimal. Mulch was added to the large tree plaza in the central courtyard of the middle apartment complex in December 2005. Minor paving block repairs were made at the same time to a tree plaza on the north side and adjacent to the parking lot between the northern and central complexes. Since completion of the remedy, no other O&M activities have been recorded with respect to the tree plazas.

#### Costs of O&M Operations

Costs of the O&M operations to maintain the tree plazas have been minimal to-date. The ground water sampling activities vary depending on the number of wells being sampled and the analyses being performed. In general, with GCR personnel assisting in the sampling, sampling costs typically range from \$1500 (January and July) to \$3000 (March and September) per sampling event. Actual yearly invoiced costs associated with the ground water sampling, since October 2001, are as follows:

**Table 2 - Annual O&M Costs** 

<u>Year</u>	<b>Invoiced Costs</b>
2001	\$1,870
2002	\$9,600
2003	\$8,425
2004	\$9,590
2005	\$8,280
Total	\$37,765

#### O&M Effectiveness

To date, the ground water monitoring has occurred as required and, as illustrated by the reductions in the sampling requirements, has effectively tracked ground water quality at the site. Similarly, the tree plazas have required essentially no maintenance to date and they are, therefore, effective in maintaining the remedy .

During a site inspection by GCR representatives in December 2005, it was discovered that a few concrete pavers making up one of the tree plazas had been disturbed. The pavers had been removed but replaced within the area from which they were removed. An adjacent resident of the apartment complex reported to GCR personnel that this activity had recently occurred and was done by teenagers that resided at the facility. GCR repaired the tree plaza and also renewed the mulch placed in the tree plaza located within the courtyard area of the middle apartment complex.

#### V. PROGRESS SINCE LAST 5-YEAR REVIEW

This review is the first 5-year review for the project.

#### VI. FIVE-YEAR REVIEW PROCESS

#### **Administrative Components**

GCR was notified of the initiation of the five-year review process in a telephone conversation and a follow-up email from Mr. William Denman of the EPA on July 15, 2005. The Normandy Park Apartments Site Five-Year Review was led by Mr. Denman of the EPA, Remedial Project Manager for the Normandy Park Apartments Site, and included employees from QORE, Inc. (QORE), under the direction of Mr. Lawrence J. Maron, P. E. QORE is the environmental consulting firm that prepared the Streamlined Remedial Investigation and Focused Feasibility Study, and developed and over saw the remedial action.

#### **Community Involvement**

A notice was sent on December 15, 2005 to the Temple Terrace Beacon, a local newspaper focused in the area of Temple Terrace, that announced that the EPA was conducting the Five-Year Review for the Normandy site and inviting public comments. Mr. William Denman of the EPA was identified as the contact. This notice was published in the December 21, 2005 newspaper. No comments were received from any parties. A copy of the notice is provided in Appendix B.

Mr. Denman also visited the Temple Terrace Library, the designated repository for documents pertaining to the site, on December 13, 2005, to verify that the documents submitted to the repository in the past were available. The documents were readily available.

#### **Document Review**

This five-year review included a review of relevant documents including the ROD and the ground water monitoring data. A listing of the documents reviewed is provided in Appendix C.

#### **Data Review**

Ground water monitoring has been conducted at the site since February 1996 on an irregular basis until October 2001. At that time, ground water monitoring began on a quarterly basis as part of the approved ROD. A copy of the historical monitoring data collected at the site is provided in Table 2 in Appendix A.

Since the start of quarterly monitoring in October 2001, lead has been detected at concentrations above the laboratory's Practical Quantitation Limit (PQL) of 0.0050 mg/l essentially only in monitoring wells MW-1 and MW-7A with the most recent concentrations (October 2005 sampling event) being .026 mg/l and .26 mg/l, respectively. Both these concentrations exceed the cleanup standard of 0.015 mg/l established in the ROD.

Arsenic concentrations have remained below the laboratory's PQL of 0.010 mg/l in all of the wells since October 2001.

Antimony concentrations exceed the cleanup standard of 0.006 mg/l in all of the monitor wells except wells MW-12, MW-DSA-1, MW-DSA-2 and PZ-1. Well MW-5 has the highest concentrations, ranging from 0.10 to 0.14 mg/l. The antimony concentrations in wells MW-1 and MW-7A have generally decreased over the long term; however, the concentrations in the remaining wells have generally fluctuated within narrow (0.010 mg/l) ranges.

Ground water elevations are all similar in pattern since implementation of the SAP. From October to January a decrease in water level on the order of two feet is generally seen and then a smaller decrease of less than ½ foot from January to April. This decrease is a reflection of Florida's "dry" season. Water levels then typically increase on the order of 1 to 1.5 feet from April to the sampling conducted in July reflecting the beginning of the typical "wet" season in Florida. Water levels typically continue to increase, slightly, from the July to October sampling events, depending primarily on the amount of rainfall that is received.

The elevated concentrations of antimony have been attributed, at least in part, to a potential offsite source. Monitoring well MW-5, in which the highest concentrations have been recorded, is located along the western property boundary in the southwestern corner of the site. Monitoring wells MW-2 and MW-13 are located along the western property boundary and both wells have elevated concentrations of antimony. Ground water elevations are highest at these latter two wells and the ground water contour maps indicate that ground water flows beneath the site from the western property boundary over the approximate middle of the site. Well MW-2 is also located up-gradient (west) of the area of the historical lead recycling activities. The concentrations of lead and arsenic in well MW-2 have been below the laboratory's PQL in all of the prior sampling events, indicating

a possible source other than battery recycling activities for the antimony concentrations observed. The lead concentration in well MW-13 was also below the laboratory's PQL (as noted in Section IV. REMEDIAL ACTIONS, Operation and Maintenance, the installation of well MW-13 was recommended by GCR to better evaluate the direction of ground water flow along the western property boundary and the source of the antimony).

#### **Site Inspection**

A site inspection was conducted on December 13, 2005 by Mr. William Denman of the EPA, Mr. Lawrence Maron of QORE and Ms. Joyce Morales-Caramella of GCR. The purpose of the inspection was to assess the protectiveness of the remedy by walking most areas of the site and observing the conditions of the tree plazas and the overall site.

No issues were identified during the inspection. All tree plazas appeared to be unaltered since their construction (the tree plaza identified in "O& M Effectiveness" having been repaired by GCR prior to the site inspection). New mulch had been placed in the tree plaza within the courtyard of the central apartment complex and the asphalt was maintained within the pavement areas. No evidence was observed that would indicate that digging within the grassed areas or within the paved areas had occurred since the remedy. A copy of the site inspection checklist is provided in Appendix D.

Restrictive covenants have been filed on the property deed which include prohibitions on the use of ground water at the site until clean up levels are achieved and notifications that the soils under the structures, paved areas and sidewalks are contaminated and that, if any of these structures are removed, then appropriate measures must be taken to address the underlying contaminated soils. A copy of the restrictive covenants is included in Appendix F of this report. Notifications are also required to notify future owners of the property of the site conditions and restrictions.

#### **Interviews**

Interviews were conducted with various parties connected to the site on December 13 and 14, 2005. The following people were interviewed:

Table 3 - List of Interviewees

Name	Position	Affiliation
Diane Lee	President	DLG Management Systems (DLG)
Amy Flanagan	Property Manager	DLG, and resident
Diana Colon	Leasing Agent	DLG, and resident
Franky Acuna	Maintenance Man	DLG
Victor Claudio	Maintenance Man	DLG
Apartment Resident #1	Apartment Resident	Resident
Apartment Resident #2	Apartment Resident	Resident
Joyce Morales-Caramella	Environmental and Health Manager	GCR

DLG Management Systems is the entity managing the complex for the current owner.

All but Apartment Resident #2 were interviewed on December 13, 2006 by Messrs. Denman and Maron and Ms. Morales-Caramella. Apartment Resident #2 was interviewed by Mr. Denman on December 14, 2006. Both interviewees were residents of the apartment complex before the remedial action was performed. Copies of the completed interview forms are provided in Appendix E.

The interviews with the DLG personnel revealed that most, including the site leasing and maintenance personnel, were unaware that contaminated soils remained on site and that restrictions existed with respect to disturbance of soils under the site structures (including sidewalks and paved areas). Ms. Lee and Flanagan reported that notices were provided to new tenants after the remedial action was completed to make them aware of the contamination that remained on site; however, this practice had been dropped over the past couple of years.

Ms. Morales-Caramella indicated that she had recently observed that several pavers that comprise one of the tree plazas had been pulled up, reportedly by teenagers that resided at the complex. Ms. Morales-Caramella made arrangements for GCR personnel to repair the plaza and alerted the apartment management personnel during the interview that the apartment personnel needed to be alert for these activities.

No issues were identified by the long-term residents of the site.

#### VII. TECHNICAL ASSESSMENT

Question A: Is the remedy functioning as intended by the decision documents?

The information reviewed and work performed during this review indicate that the remedy is functioning as intended by the ROD. The removal of the soil from all areas that would afford exposure of humans and animals has achieved the remedial objectives to minimize ingestion of contaminants in the soil. All of the structures under which contaminated soil remains are still intact.

The remedial action has been effective in preventing exposure to or use of contaminated ground water at the site. During the past 5 years, the monitoring system has been optimized to delete the collection of extraneous data and to add one monitor well to better define that off site sources may be contributing to elevated antimony concentrations in the ground water under the western portion of the site.

The institutional controls (restrictive covenants) that are in place provide notification that the soil underneath the structures, paved areas and sidewalks are contaminated. The restrictive covenants also require that if any of these structures are removed, then appropriate measures must be taken to address the underlying contaminated soils. With one minor exception near the end of the five-year review period (the recent disturbance of pavers at one tree plaza), the cap (existing structures and tree plazas) has been undisturbed. A copy of the restrictive covenants has been included in Appendix F.

After the interviews of the on-site personnel, EPA was notified by the apartment manager that the soil under the first floor of one of the townhouses would be exposed and disturbed during the repair of plumbing under the floor. The apartment personnel had advised the plumbing contractor that the

soil was contaminated and required special care in removal and disposal. The plumbing work was performed on December 26, 2005 and was attended by representatives of QORE and GCR who verified that proper protective clothing was worn by the plumbing contractors and that soil removed from the excavation was properly handled. Excess soil was drummed and taken to OCR's Tampa facility for processing.

**Question B:** Are the exposure assumption, toxicity data, cleanup target levels, and remedial action objectives (RAQs) used at the time of the remedy selection still valid?

The Federal drinking water standard and the ground water standard (Maximum Contaminant Level (MCL)) for Class G-II Ground Water within the State of Florida for arsenic was lowered from 0.050 mg/l to 0.010 mg/l (Rule 62-550, Florida Administrative Code). This change has had no effect on the remedy selection because the concentration of arsenic at the site has been below the revised MCL of 0.010 since the April 2002 sampling event.

The Soil Cleanup Target Level (SCTL) for lead, as established by the State of Florida in Rule 62-777, Florida Administrative Code, is 400 mg/kg for the residential exposure scenario. This concentration was initially established for certain State cleanup programs in May 1999 and re-affirmed in April 2005; however, the SCTL can be modified if a site-specific risk assessment is performed. Even if one utilizes the SCTL of 400 mg/kg, it has no effect on the remedial action performed at the site because the only place soil was not excavated is within the drip-line of select trees. The concentrations of lead in the soil samples collected from the tree areas that tree plazas were not constructed over, were all less than 400 mg/kg. Copies of the plates that transmitted the soil sampling results within the tree preservation areas to the EPA are provided in Appendix G.

Overall, the remedy is progressing as expected. As previously discussed, all monitor wells have seen an overall decrease in the concentration of contaminants. The lead concentration in all the monitor wells except MW-1 and MW-7A are below the cleanup standard of 0.015 mg/l. Chart 1 is provided in appendix H showing the decreasing trend of lead concentration in MW-1 and MW-7A.

The arsenic concentration has remained below the laboratory's PQL of 0.010 mg/l in all of the wells since October 2001. Overall, the antimony concentrations have fluctuated, however they do show a decreasing trend in concentration levels. Chart 2 is provided in appendix H showing the antimony concentrations in MW-7A and MW-11.

Piezometer PZ-1 has been sampled semi-annually for antimony, arsenic and lead to insure that the Floridan Aquifer remains uncontaminated. No detections of these parameters above the laboratory's reporting limit have occurred since the start of sampling in February 1996. Based on this and other contamination assessment work performed on site, the Floridan Aquifer remains unaffected by past site activities.

**Question C:** Has any other information come to light that could call into question the protectiveness of the remedy?

No information was identified during this five-year review that questions the protectiveness of the remedy.

#### **Technical Assessment Summary**

According to the data reviewed, the site inspection, and the interviews, the remedy is functioning as intended by the ROD. There have been no changes in the physical conditions of the site that would affect the protectiveness of the remedy. Most ARARs for soil contamination cited in the ROD have been met. There have been no changes in toxicity factors for the contaminants of concern that were used in the baseline risk assessment, and there have been no change to the standardized assessment methodology that could affect the protectiveness of the remedy. There is no other information that calls into question the protectiveness of the remedy.

#### VIII. ISSUES

**Table 4 - Issues** 

Issue	Currently Affects Protectiveness	Affects Future Protectiveness
Maintenance and management personnel unaware of need to maintain tree plaza areas	No	Yes
Maintenance and management personnel unaware of presence of contaminated soil on site	No	Yes
New tenants not informed of past remedial actions and presence of contaminated soil on site	No	No
Decrease of antimony concentrations in groundwater at certain locations not occurring as quickly as expected.	No	No
Resolve need for monitor well along eastern property boundary as requested by the FDEP.	No	No

#### IX. RECOMMENDATIONS AND FOLLOW-UP ACTIONS

**Table 5 - Recommendations and Follow-Up Actions** 


Issue	Recommendations/ Follow-Up Actions	Party Responsible	Oversight Agency	Milestone Date	Affects Protectiveness (Y/N)	
					Current	Future
Tree plaza maintenance	Prepare written description of inspection and maintenance activities for site personnel.	GCR	EPA	1/1/2007	N	Y
Written contaminated soil plan	Prepare written description of actions to be taken when contaminated soil exposed. Meet with maintenance and management personnel yearly to review soil contamination restrictions. Quarterly verify with management staff that new maintenance personnel have been educated on soil contamination restrictions.	GCR	EPA	1/1/2007	N	Y
Notification of new tenants	Prepare one-page information sheet to hand out to new tenants	DLG/GCR	EPA	1/1/2007	N	N
Decrease of antimony concentration	Evaluate the potential for an offsite source of antimony concentration	QORE	EPA	10/1/2007	N	N
Disseminating of ground water contamination to uncontaminated areas.	Prior to conducting the next 5-year review monitoring wells MW-6 and MW-9 will be sampled.	QORE	EPA	6/1/2011	N	N
Resolve need for monitor well with FDEP.	Discuss need for monitor well with EPA and FDEP.	EPA	EPA	10/1/2007	N	N


#### X. PROTECTIVENESS STATEMENT


The remedy is expected to be protective of human health and the environment upon attainment of ground water cleanup goals through natural attenuation. In the interim, institutional controls are preventing the exposure to and ingestion of contaminated ground water at the site. Similarly, institutional controls are preventing exposure to and ingestion of contaminated soil at the site. All threats at the site have been addressed through removal of contaminated soil in readily accessible areas, the construction of tree plazas in areas where the soil was not removed from existing tree root systems, and institutional controls to notify current and future owners of the site that soil under the existing structures (including paved areas and sidewalks) is contaminated and must be addressed appropriately if any structure is demolished or soil is excavated from beneath the structures.


#### XI. NEXT REVIEW

The next five-year review for the Normandy Park Apartment site is required within five years of the signature/approval date of this report. It should be noted that wells MW-6 and MW-9 must be sampled prior to the next five-year review.









# APPENDIX A APRIL 2006 SAMPLING REPORT



#### Prepared for:

#### U.S. Environmental Protection Agency 61 Forsyth Street Atlanta, Georgia 30303-8960

Prepared by:

QORE, Inc. 1211 Tech Blvd. Suite 200 Tampa, Florida 33619

April 2006 Sampling Event
Remedial Action Ground Water Sampling
Normandy Park Apartments
Tampa, Florida
For EnviroFocus Technologies, L.L.C.

June 26, 2006 QORE Project No. 2148M June 26, 2006

Mr. William C. Denman, P. E. U.S. Environmental Protection Agency 61 Forsyth Street Atlanta, Georgia 30303-8960

Re: April 2006 Sampling Event

Remedial Action Ground Water Sampling

Normandy Park Apartments

Tampa, Florida

For EnviroFocus Technologies, L. L. C.

QORE Project No. 2148M

Dear Mr. Denman,

QORE, Inc. (QORE) is pleased to submit this report presenting the results of the periodic ground water sampling conducted as part of the Remedial Action at the above-referenced site. The ground water sampling was initially described in QORE's document entitled "Revised Sampling and Analysis Plan, Remedial Design Ground Water Sampling, Normandy Park Apartments, Tampa, Florida, for Gulf Coast Recycling", dated February 13, 2001, and was modified by the U.S. Environmental Protection Agency (EPA) in a letter from Mr. Bill Denman to Ms. Joyce Morales-Caramella of Gulf Coast Recycling, Inc. (GCR) dated March 27, 2003. Please be advised that EnviroFocus Technologies, L. L. C. (EFT) purchased substantially all of the assets of GCR on May 31, 2006 and will be responsible for continuing the ground water monitoring at the site. QORE will continue to perform the ground water monitoring on behalf of EFT.

This report presents the results of the sampling conducted in April 2006.

#### **BACKGROUND**

The approved Sampling and Analysis Plan (SAP) required the installation of six monitor wells at the Normandy Park Apartment site after the remedial action was completed: four screened within the upper portion of the surficial aquifer (MW-7A, MW-10, MW-11 and MW-12) and two screened at the base of the surficial aquifer (MW-DSA-1 and MW-DSA-2). The installation of these monitor wells was completed on August 30, 2001.

The six monitor wells required by the SAP supplemented eight (8) surficial aquifer monitor wells (MW-1 through MW-6, MW-8 and MW-9) that existed at the site. Three monitor wells (MWFL-1, PZ-1 and PZ-2) also exist on site that are screened into the uppermost portion of the Floridan aquifer. The locations of all the monitor wells are shown on Plate 1.

Starting in October 2001, ground water samples were collected quarterly (January, April, July and October) from the six monitor wells installed in accordance with the SAP. These samples were analyzed for lead, arsenic, and antimony. Semi-annually (April and October), samples were also collected from existing surficial monitor wells MW-1, MW-2, and MW-8, and from the existing Floridan aquifer monitor well PZ-1, and analyzed for the same parameters.

Changes to the ground water monitoring plan were approved in EPA's March 27, 2003 letter to Ms. Joyce Morales-Caramella of OCR. The changes that were approved were:

- 1. All of the monitor wells in the ground water monitoring program are sampled semi-annually, except for wells MW-7A and MW-11. These two wells are sampled quarterly.
- 2. Arsenic concentrations are measured only once per year, during the October sampling event.
- 3. Semi-annual sampling of monitor well MW-5 was added to the monitoring program. The sample from this well is analyzed only for antimony.

In addition to these changes, the installation of a surficial aquifer monitor well (MW-13) was recommended along the western property boundary, approximately midway between wells MW-2 and MW-5 in the report (dated October 23, 2003) that presented the results of the July and April 2003 sampling events. This well was recommended to provide a point for the measurement of ground water elevation, needed to better define the direction of ground water flow along the western property line, and to identify and evaluate the extent of elevated antimony concentrations in the ground water. The installation of this well was approved by the EPA and it was subsequently installed on June 17, 2004. Sampling of this well occurs semi-annually along with the other shallow aquifer wells.

#### **GROUND WATER FLOW**

The depth to ground water was measured in all the wells on April 20, 2006. The ground water depths and the corresponding ground water elevations are presented in Table 1. Due to much lower than normal rainfall during the months preceding the April 20th measurements, the water level in two monitor wells (MW-3 and MW-4) had dropped below the bottom of their respective well screens.

The ground water elevations were plotted on a scaled map of the site and equal lines of ground water elevation were interpolated between the known points. The individual water elevations at each well and the ground. water contours for the surficial aquifer during the April event are shown on Plate 2. At the time of the ground water measurements, ground water flow at the site appears to be radially toward the north, east and south from a ground water "high" located west of the western property boundary. This flow pattern is similar to that reported during prior sampling events.

The potentiometric elevations measured in the Floridan monitor wells during the April sampling event are shown on Plate 3. Ground water flow in the Floridan aquifer during this event was toward the east-northeast. This flow direction is more northerly than the southeasterly-trending flows identified during the January 2006 sampling event; however flow in a northeasterly direction tends to be more consistent with previous events. In general, the slope of the potentiometric surface is very shallow at the site (less than 3 inches over 500 feet). As a result, small changes in measurements at the wells can dramatically affect the purported direction of ground water flow.

#### GROUND WATER MONITORING

Ground water samples were collected on April 20 and 21, 2006, from monitor wells MW-1, MW-2, MW-5, MW-7A, MW-8, MW-10, MW-11, MW-12, MW-13, MW-DSA-1, MW-DSA-2 and PZ-1, as designated in the SAP. All sampling was conducted in accordance with the procedures and protocols contained in the QORE Quality Assurance Project Plan (QAPP) most recently approved by the EPA. After purging the well, each ground water sample was analyzed in the field for temperature, pH, conductivity, turbidity and dissolved oxygen. The ground water samples were placed in laboratory-supplied sample containers and stored on ice in a laboratory-supplied cooler until delivery to the laboratory for analysis. The samples were submitted to STL Tampa West (STL) for analysis of total antimony and total lead using EPA Method 6010.

The results of the laboratory analyses are summarized in Table 2. With the exception of the samples from wells MW-1 and MW-2, the turbidities of the samples from all the wells were less than 10 Nephelometric turbidity units (NTUs). The turbidity values in wells MW-1 and MW-2 could not be lowered below 23 NTUs and 35 NTUs, respectively, during the sampling. As a result, filtered samples were also collected from these two wells for analysis. Despite filtering, the turbidities of the filtered samples were 15 NTUs for MW-1 and 13 NTUs for MW-2. This is the third consecutive sampling event that a filtered sample has been collected from well MW-1 and the first for well MW-2.

Table 2 also includes the results of prior water quality sampling conducted under the SAP and sampling results reported in the Streamlined Remedial Investigation, prepared by QORE, Inc., dated June 30, 1999. Copies of the laboratory reports and field sampling forms for the April 2006 sampling event are presented in Appendix A.

The results of the water quality sampling are very similar to past sampling events. Lead was reported at a concentration above the laboratory's Practical Quantitation Limit (PQL) of 0.0050 milligrams per liter (mg/l) only in the samples collected from wells MW-1, MW-2 and MW-7A. The unfiltered lead concentration in the sample from well MW-1 was 0.027 mg/l, which is virtually the same as that reported for the October 2005 sampling event (0.026 mg/l). The unfiltered lead concentration in the sample from well MW-2 was 0.012 mg/l, which represents the only value reported for this well above the PQL of 0.0050 mg/l. The concentration of lead in the filtered sample from well MW-2 was < 0.0050 mg/l, indicating that the unfiltered lead concentration is likely caused by sediment in the sample. The lead concentration in the filtered sample from well MW-1 was 0.015 mg/l, which indicates that at least some of the reported lead concentration can likely be attributed to sediment in the sample. The lead concentration in the sample from well MW-7A was 0.24 mg/l, virtually the same concentration of 0.23 mg/l reported during the October 2005 sampling event and well within the range of concentrations reported in the past. The concentrations of lead in wells MW-1 and MW-7A are greater than the Maximum Contaminant Level (MCL) of 0.015 mg/l, as established by the Primary Drinking Water Standards and Rule 62-520, Florida Administrative Code.

During the April 2006 sampling event, antimony was reported above the laboratory's PQL in the ground water samples collected from wells MW-1, MW-2, MW-5, MW-7A, MW-8, MW-10, MW-11 and MW-13. The antimony concentrations for these samples were all greater than the MCL

of 0.006 mg/l, with the maximum concentration occurring in well MW-10. In general, the concentrations of antimony in the wells were similar to concentrations that had been previously reported, with the exception of wells MW-7A and MW-10. The concentration of antimony in well MW-10 was almost four times the value reported in the last sampling event for this well (October 2005) while the concentration in well MW-7A was almost one-half the previous value (January 2006).

#### ANALYSIS OF ANTIMONY CONCENTRATIONS

In the past, the reports presenting the results of the semi-annual sampling events provided a discussion of the elevated antimony concentrations in relationship to any historic changes in ground water flow directions and/or water level fluctuations. The plots of antimony concentration versus water level previously presented were updated with the April 2006 sampling event data for wells MW-1, MW-2, MW-5, MW-7A, MW-8, MW-10, MW-11, MW-12 and MW-13 and are provided in Appendix B. Plots for the remaining wells in the monitoring program have not been developed because antimony concentrations have always been reported to be below the laboratory's PQL of 0.0060 mg/l.

The plots of the water elevations are all similar in pattern over the past year, as follows:

- Water levels increased slightly (on the order of 1 to 1.5 feet) from April 2005 to the sampling conducted in July 2005, reflecting the beginning of the seasonal increase in rainfall associated with the typical "wet" season in Florida.
- Water levels decreased slightly (less than ½ feet) from the July 2005 to the October 2005 sampling events, suggesting a decreased amount of rainfall for this period.
- Since the October 2005 sampling event, water levels decreased on the order of 1-½ feet at the time of the January 2006 sampling event and continued to decrease 1-¼ feet at the time of the April 2006 event. As noted previously, wells MW-3 and MW-4 were dry during the April 2006 event. The decreases in the water table reflect the smaller amounts of rainfall associated with Florida's "dry" season.

A review of the antimony versus water level plots indicates three general trends, as follows:

1. Antimony concentrations decrease as water levels increase and increase as water levels decrease. The antimony concentrations in wells MW-1 and MW-10 appear to follow this trend, especially over the last 2 years. Antimony concentrations in well MW-2 also followed this trend with the exception of the October 2005 sampling event, when the antimony concentration dropped below the PQL of 0.006 mg/l with a drop in water level. Antimony concentrations in MW-13 appeared to follow this trend; however, during this sampling event, the antimony concentration decreased as the water level decreased. The decrease in antimony concentrations as water levels increase can be associated with dilution due to the increased volume of water resulting from the percolation of rainwater. As water levels decrease, the volume of water decreases and the antimony concentration increases.

- 2. Antimony concentrations parallel the pattern of water levels, that is, concentrations increase as water levels increase and decrease as water levels decrease. This pattern generally occurs in well MW-7A. This type of pattern typically indicates that antimony is being dissolved as water level increases; however, the plot of antimony concentrations clearly shows that antimony concentrations are decreasing over the long term. Concentrations currently are about 1/5 the value observed during sampling events in 2002.
- 3. Antimony concentrations don't change in response to water levels. This trend occurs in wells MW-5, MW-8, and MW-11. Antimony concentrations in well MW-5 show a consistent decrease since monitoring of this well began, although, with the single exception of a slight increase for the October 2005 sampling event. Antimony concentrations in wells MW-8 and MW-11 are remaining relatively constant.

As noted previously, the antimony concentration in well MW-2 dropped below the MCL of 0.006 mg/l for the first time during the October 2005 sampling event. The antimony concentration only increased slightly to 0.0012 mg/l (filtered) this sampling event. The water level and antimony concentrations reported during the April 2006 event still support the contention that the area west of the site may be contributing to at least some of the elevated antimony concentrations, as follows:

- Ground water elevations are highest at wells MW-2 and MW-13 and ground water flow has been toward the east and south from these wells.
- The ground water contour maps indicate that ground water flows beneath the site from the western property boundary over the approximate middle of the site. Well MW-2 is also located up-gradient (west) of the area of historical lead recycling activities, indicating that water flowing beneath the site from the west may be contributing to at least some of the elevated antimony concentrations.
- The concentrations of lead and arsenic in well MW-2 have been below the laboratory's PQL in all of the prior sampling events, indicating a possible source other than battery recycling activities for the antimony concentrations observed in well MW-2. The lead concentration in well MW-13 was also below the laboratory's PQL.

Well MW-5, which has normally had the highest concentrations of antimony, is also located along the western property boundary in the southwestern corner of the site. Ground water flow at this location is typically toward the south or southeast, further indicating a possible source west of the site.

QORE is pleased to have this opportunity to submit this information for EFT. If you have any questions pertaining to this report, please do not hesitate to contact us.

\* \* \* \* \*

Yours very truly, **QORE, Inc.** 

Four (4) copies submitted

cc: Ms. Joyce Morales-Caramella - EFT (two copies)

#### TABLE 1 GROUND WATER ELEVATIONS APRIL 20, 2006 NORMANDY PARK APARTMENTS

Top-of-Casing Water Level						
Measuring Point  Designation	Elevation (feet	Depth to Water (feet btoc)	Elevation (feet			
	NGVD)	(reet bloc)	NGVD)			
Shallow Aquifer Mon	itor Wells					
MVV-1	76.14	8.37	67.77			
MW-2	78.03	8.04	69.99			
MW-3	78.57	DRY	DRY			
MW-4	78.42	DRY	DRY			
MW-5	74.19	6.95	67.24			
MW-6	76.54	10.01	66.53			
MW-7A	77.35	9.02	68.33			
MW-8	78.01	9.04	68.97			
MW-9	77.77	9.22	68.55			
MW-10	76.39	9.57	66.82			
MW-11	76.06	10.20	65.86			
MW-12	77.86	11.81	66.05			
MW-13	77.34	6.88	70.46			
Deep Shallow Aquifer Monitor Wells						
MW-DSA-1	76.44	9.72	66.72			
MW-DSA-2	75.78	10.20	65.58			
Floridan Aquifer Monitor Wells						
MWFL-1	78.81	59.70	19.11			
PZ-1	74.09	54.86	19.23			
PZ-2	76.31	57.28	19.03			

Note:

Feet NGVD = feet above National Geodetic Vertical Datum of 1929.

N.M. = Not Measured btoc = below top of casing

## TABLE 2 SUMMARY OF GROUND WATER QUALITY NORMANDY PARK APARTMENTS

WELL NO.	DATE	ANTIMONY,	ARSENIC,	LEAD,	-D		CONDUCTIVITY,	TURBIDITY
WELL NO.		mg/l	mg/l	mg/l	pH	<u>°c</u>	uS	NTUs
	THE MOUNT	上。201006过生	(a €0.05 the	01015				
	20-Feb-96		<0.010	0.013				
	17-Dec-98	0.042	<0.010	0.15 (0.10)	6.42	26.7	98	126.0
	10-Aug-01	ns 0.054	ns -0.010	ns 2.045	ns	ns	ns 040	ns
	25-Oct-01 14-Jan-02	0.054 ns	<0.010	0.015 ns	4.45 ns	28.4 ns	243 ns	5.6 ns
ì	16-Apr-02	0.065	<0.010	0,013	6.17	26.3	451	2.1
	31-Jul-02	ns	ns	ns	ns	ns	ns	ns
MW-1	30-Oct-02	0.057	<0.010	0.016	5.96	30.0	550	4.7
	17-Apr-03	0.038	na	0.026	6.95	26.5	210	10.0
	15-Oct-03	0.041 0.048	<0,010 na	0.013 0.012	6.06 6.75	29.5	323 172	6.1
	13-Apr-04 4-Oct-04	0.048	<0.010	0.012	6.17	25.8 31.6	375	7.0 9.5
	13-Apr-05	0.026 (0.025)	na	0.065 (0.052)	6.18	26.2	197	55 (40)
	20-Oct-05	0.033 (0.035)	<0.010	0.026 (0.0092)	5.80	31.1	322	16 (2.5)
	20-Apr-06	0.037 (0.037)	na	0.027 (0.015)	6.07	27.3	193	23 (15)
	20-Feb-96	0.04	<0.010 <0.010	<0.0050 <0.0050	6.40	20.0	240	45.2
	17-Dec-98 10-Aug-01	ns	ns	70.0050 ns	ns	26.0 ns	310 ns	15.3 ns
	21-Nov-01	0.025 (0.026)	<0,010	<0.0050	6.27	25.7	568	6.8
	14-Jan-02	ns	ns	ns	ns	ns	ns	ns
	16-Apr-02	0.034	<0.010	<0.0050	6.33	26.4	489	2.9
Ana: o	31-Jul-02	ns	ns	ns	ns	ns	ns	ns ns
MVV-2	30-Oct-02	0.017 0.0097	<0.010 na	<0.0050 <0.0050	6.08 6.75	29.1	3340 333	5.1 4.6
	18-Apr-03 15-Oct-03	0.0097	<0.010	<0.0050	6.28	25.5 29.2	359	6.4
	13-Apr-04	0.059	na	<0.0050	6.60	25.1	561	0.6
	5-Oct-04	0.021	<0.010	<0.0050	5.66	29.3	381	0.5
	13-Apr-05	0.034	na	<0.0050	5.45	25.2	221	8.7
	20-Oct-05	<0.0060	<0.010	<0.0050	4.97	30.3	149.7	7.4
	21-Apr-06 16-Dec-98	0.0097 (0.012) 0.093	na <0.010	0.012 (<0.0050) <0.0050	5.74 6.89	26.9 24.5	85.5 368	35 (13) 0.4
	17-Apr-03	0.14	na	na	6.92	24.0	294	3.8
	16-Oct-03	0.13	na	na	6.22	27.2	327	1.6
MW-5	13-Apr-04	0.12	na	na	6.72	23.2	567	0.6
	4-Oct-04	0.12	na	na	6.70	28.0	244	9.4
	13-Apr-05	0.10 0.12	na	na	6.16 5.89	22.8	249	5.5
	19-Oct-05 20-Apr-08	0.12	na na	na na	5,86	28.5 24.3	291 275	0.51 1.4
	20-Feb-96	<u> </u>			0,00	24.0		14
	17-Dec-98	0.11 (0.099)**	0.049**	0.24 (0.16)**	6.64**	23.3**	404**	54.8**
	13-Aug-01	0.081	<0.010	0.084	6.37	27.2	421	2.3
	26-Oct-01	0.29	<0.010 0.010	0.45 0.37	5.56 6.12	23.6	914 791	0.3
•	15-Jan-02 17-Apr-02	0.16 0.15	<0.010	0.66	6.29	21.8 24.1	820	0.3 2.2
	31-Jul-02	0.14	<0.010	0.30	6.20	26.5	810	4.6
	31-Oct-02	0.15	<0.010	0.51	6.18	26.4	630	1.7
	18-Apr-03	0.093	na	0.22	6.90	22.2	543	2.6
MANA/-7A	18-Jul-03	0.11	na <0.010	0.39	6.82 6.47	25.9	568	2.0
MW-7A	16-Oct-03 12-Jan-04	0.13 0.074	<0.010 na	0.24 0.29	6.47 6.92	26.6 22.7	424 698	1.3 4.6
	13-Apr-04	0.037	na	0.18	7.51	21.5	496	2.2
<u>'</u>	13-Jul-04	0.059	na	0.30	6.61	26.0	507	8.6
	5-Oct-04	0.086	<0.010	0,30	6.65	26.8	483	6.8
	20-Jan-05	0.049	na	0.22	7.20	24.8	457	1.4
	13-Apr-05 7-Jul-05	0.057 0.072	na na	0.21 0.30	6,41 6,73	21.9 26.8	503 505	5 5.1
	20-Oct-05	0.072	<0.010	0.36	6.18	28.5	439	0.05
	12-Jan-08	0.055	na	0.23	7.00	24.5	407	0.5
	21-Apr-06	0.03	na	0.24	6.42	23.9	494	0.4
	20-Feb-98							
	16-Dec-98	0.013	<0.010	<0.0050	6.18	24.8	445	4.5
	10-Aug-01 28-Oct-01	ns 0.018	ns <0.010	ns <0.0050	ns 5.90	ns 24.7	ns 198	ns 4.9
	14-Jan-02	0.016 ns	NS	ns	0.90 ns	24.1 ns	198 ns	4.9 ns
	17-Apr-02	0.033 (0.032)	0.015 (0.011)	0.0070 (<0.0050)	6.24	26.2	155	45 (21)
MW-8	31-Jul-02	ns	ns	ns	ns	ns	ns	ns
	31-Oct-02	0.034	<0.010	<0.0050	6.36	27.5	293	3.0
	26-Apr-03 15-Oct-03	0.027 0.026	na <0.010	<0.0050 <0.0050	6.89 6.01	24.3 27.3	323 226	3.3 7.4
	13-Apr-04	0.028	0.010	<0.0050	6.30	24.0	127	8.5
								9.9
	5-Oct-04	0.030	<0.010	0,0057	6.31	27.7	211	
		0.030 0.023 0.024	<0.010 na <0.010	<0.0057 <0.0050 <0.0050	5.88 5.59	24.2 29.1	115.6 119.3	7.9 5.8

## TABLE 2 SUMMARY OF GROUND WATER QUALITY NORMANDY PARK APARTMENTS

WELL NO.	DATE	ANTIMONY,	ARSENIC,	LEAD,	рН		CONDUCTIVITY,	TURBIDITY
		mg/l	mg/l	mg/l	F''	°c	uS	NTUs
				<b>建成00015</b> 元				<u> </u>
	20-Feb-96	ni	ni	ni 	ni	ni ni	ni	ni
	16-Dec-98	ni 0.021	ni <0.010	ni <0.0050	ni 5 04	ni 24.2	ni 440	ni
	10-Aug-01 25-Oct-01	0.021	<0.010	<0.0050	5.84 5.43	28.4	442	1.4 1.6
	14-Jan-02	0.028	<0.010	<0.0050	5.94	24.4	463	0.5
İ	17-Apr-02	0.030	<0.010	<0.0050	5.76	28.2	494	3.3
1	31-Jul-02	0.028	<0.010	<0.0050	5.70	29.4	586	1.5
MW-10	30-Oct-02	0.031	<0.010	<0.0050	5.74	30.5	355	4.7
	18-Apr-03	0.020	na	<0.0050	6.63	26.7	274	7.4
	16-Oct-03	0.028	<0.010	<0.0050	6.35	30.1	351	2.4
- 1	13-Apr-04 4-Oct-04	0.060 0.033	na <0.010	<0.0050 <0.0050	6.68 6.45	26.2 31.1	343 190.2	7.8 3.5
	13-Apr-05	0.013	na	<0.0050	6.15	26.1	348	8.2
	20-Oct-05	0.027	<0.010	<0.0050	5.93	31.1	320	2.8
	20-Apr-06	0.12	na	<0.0050	6.52	28.4	261	3.5
	20-Feb-96	ni	ni	ni	ni	ni	ni	ni
	16-Dec-98	ní	ni	ni ni	ni	ni	ni ni	<u>ni</u>
}	10-Aug-01	0.036	<0.010	<0.0050	6.64	23.2	492	0.5
	25-Oct-01 15-Jan-02	0.040 0.028	<0.010 <0.010	<0.0050 0.0088	6.28 6.47	26.3 21.0	458 43.3	0.8 0.7
ł	17-Apr-02	0.028	<0.010	0.0088	5.89	25.9	226	3.1
ŀ	31-Jul-02	(0.042)	(<0.010)	(0.0068)	5.84	27.8	325	14 (4.4)
į	31-Oct-02	0.052	<0.010	<0.0050	5.91	27.2	257	32 (23)
{	18-Apr-03	0.033	na	<0.0050	6.81	23.9	370	3.8
Lna.	18-Jul-03	0.038	na	0.0060	6.86	27.5	293	9.3
MVV-11	15-Oct-03	0.046 0.035	<0.010	<0.0050	6.53	27.3	321	7.4
	12-Jan-04 13-Apr-04	0.033	na na	<0.0050 <0.0050	6.75 6.70	22.7 23.3	441 300	5.2 7.4
	13-Jul-04	0.034	na	<0.0050	6.41	27.1	270	8.8
	4-Oct-04	0.031	<0.010	0.0074	6.48	27.3	105.8	31
	20-Jan-05	0.029	na	<0.0050	7.21	24.0	429	2.8
	13-Apr-05	0.031	na	<0.0050	6.24	23.8	377	6.40
	7-Jul-05	0.038	na	<0.0050	5.95	27.8	272	4.1
	19-Oct-05 12-Jan-06	0.037 0.038	<0.010	<0.0050 <0.0050	6.25 6.66	28.1 23.1	313 335	4.3 3.3
	20-Apr-06	0.031	na	<0.0050	6.29	25.3	236	1.6
	20-Feb-96	ni	ni	ni	ni	ni	ni	ni
	16-Dec-98	ni	ni	ni	ni	ni	ni	ni
	10-Aug-01	<0.0060	<0.010	<0.0050	6.09	22.6	319	0.3
	25-Oct-01	<0.0060	<0.010	<0.0050	5,91	25.9	336	0.0
	14-Jan-02	<0.0060	<0.010	<0.0050	5.72	22.0	350	0.0
	16-Apr-02 29-Jul-02	<0.0060 <0.0060	<0.010 <0.010	<0.0050 <0.0050	6.04	25.1 26.9	285 536	0.0
	30-Oct-02	<0.0060	<0.010	<0.0050	6.35	27.0	460	1.6
MW-12	17-Apr-03	<0.0060	na	<0.0050	6.88	24.2	553	0.6
	16-Oct-03	<0,0060	<0.010	<0.0050	6.13	26.3	492	0.8
	13-Apr-04	<0.0060	na	<0.0050	6.20	23.6	373	3.4
	4-Oct-04	0.014	<0.010	<0.0050	6.23	27.4	319	0.6
	14-Dec-04 13-Apr-05	<0.0060 <0.0060	na na	na <0.0050	6.38 6.35	25.1 23.2	642 463	3.0 5.2
MW-11  MW-12	20-Oct-05	<0.0060	<0.010	<0.0050	6.20	27.8	350	0.0
	21-Apr-06	<0.0060	na	<0.0050	5.49	25.2	489	0.0
	13-Jul-04	0.042	na	<0.0050	6.20	29.5	535	7.8
	5-Oct-04	0.062	<0.010	<0.0050	5.22	30.3	390	0.1
MW-13	13-Apr-05	0.023	na	<0.0050	6.1	26.2	409	4.7
	20-Oct-05	0.046	<0.010	<0.0050	5.99	31.2	389	0.0
	21-Apr-06 20-Feb-96	0.032 ni	na ni	<0.0050	6.0 ni	27.5 ni	308	5.4
	16-Dec-98	ni	<u>'"</u>	ni ni	ni ni	ni ni	ni ni	ni ni
	10-Aug-01	<0.0060	<0.010	<0.0050	4.06	23.9	454	2.3
	25-Oct-01	<0.0060	<0.010	<0.0050	3.77	27.3	427	0.3
	14-Jan-02	<0.0060	<0.010	<0.0050	3.71	24.8	468	0.2
	17-Apr-02	<0.0060	<0.010	<0.0050	3,62	26.5	445	1.1
MAL DOA 4	31-Jul-02	<0.0060	<0.010	<0.0050	3.47	27.3	500	0.1
MVV-DSA-1	30-Oct-02	<0.0060	<0.010	<0.0050	2.80	28.5	518	3.4
	18-Apr-03 16-Oct-03	<0.0060 <0.0060	na <0.010	<0.0050 <0.0050	3.49 3.81	26.9 27.9	625 542	0.9 1.4
	13-Apr-04	<0.0060	na	<0.0050	3.77	26.0	726	4.7
	5-Oct-04	<0.0060	<0.010	<0.0050	3.67	29.1	614	4.5
	13-Apr-05	<0.0060	na	<0.0050	3.06	25.5	580	4.5
	20-Oct-05	<0.0060	<0.010	<0.0050	3.56	29.6	474	0.13
	20-Apr-06	<0.0060	na	<0.0050	3.75	27.8	434	0.15

#### TABLE 2 SUMMARY OF GROUND WATER QUALITY NORMANDY PARK APARTMENTS

WELL NO.	DATE	ANTIMONY,	ARSENIC,	LEAD,	pН	TEMPERATURE,	CONDUCTIVITY,	TURBIDITY,
WELL NO.	DATE	mg/l	mg/l	mg/l	ÞΓ	°c	uS	NTUs
	L MCL. E	][20.006][][]	更是0.05"二"	Vii. 0.015				
	20-Feb-96	ni .	ni	ni	ni	กเ	ni	ni
	16-Dec-98	ni	ni	ni	ni	ni	ni	ni
i .	10-Aug-01	<0.0060	<0.010	<0.0050	4.56	21.8	85,3	0.5
	25-Oct-01	<0.0060	<0.010	<0.0050	5.25	26.1	183	0.3
	15-Jan-02	<0.0060	<0.010	<0.0050	4.54	22.8	144	0.0
	17-Apr-02	<0.0060	<0.010	<0.0050	4.02	24.9	145	2.9
[	29-Jul-02	<0.0060	<0.010	<0.0050	3.72	28.0	160	0.1
MW-DSA-2	30-Oct-02	<0.0060	<0.010	<0.0050	3.51	26.5	215	3.0
1	18-Apr-03	<0.0060	na	<0.0050	4.20	24.9	169	0.7
	15-Oct-03	<0.0060	<0.010	<0.0050	5.09	26.0	215	0.9
	13-Apr-04	<0.0060	na	<0.0050	4.18	23.9	202	3.6
i	4-Oct-04	<0.0060	<0.010	<0.0050	4.73	26.5	150.2	8.4
	13-Apr-05	<0.0060	na	<0.0050	3.73	26.5	273	5.1
	19-Oct-05	<0.0060	<0.010	<0.0050	3.82	26.7	215	0.0
	20-Apr-06	<0.0060	na	<0.0050	3.99	25.4	275	0.35
	20-Feb-96		<0.010	<0.0050				
	15-Dec-98	<0.0060	<0.010	0.035*	7.82	25.4	320	15.3
	10-Aug-01	ns	ns.	ns	ns	ns	ns	hs
	8-Nov-01	<0.0060	<0.010	<0.0050	6.96	20.1	118.9	2.2
	14-Jan-02	ns	ns	กร	ns	ns	ns	ns.
j	17-Apr-02	<0.0060	<0.010	<0.0050	7.46	24.7	220	10.0
١ ا	31-Jul-02	ns	ns	ns .	ns	វាន	ns	ns
PZ-1	31-Oct-02	<0.0060	<0.010	<0.0050	6.76	25.6	292	3,3
1	17-Apr-03	<0.0060	na	<0.0050	7.87	26.7	274	5.2
[	15-Oct-03	<0.0060	<0.010	<0.0050	6.70	25.5	291	9.4
i i	14-Apr-04	<0.0060	na	<0.0050	7.66	25.8	242	7.9
1 1	4-Oct-04	<0.0060	<0.010	<0.0050	7.26	26.2	222	8.9
	13-Apr-05	<0.0060	na	<0.0050	6.80	26.8	236	7.2
	19-Oct-05	<0.0060	<0.010	<0.0050	6.78	27.2	224	8.0
	20-Apr-06	<0.0060	na	<0.0050	7.38	26.9	183	7,9

ns = -not sampled - samples are collected semi-annually

ni = :not installed

na = `not analyzed - arsenic is now analyzed once per year in October

\* = concentration of sample collected on March 23, 1999 was <0.0050

= sample collected from monitor well MW-7

mg/l = milligrams per liter


μS = microSiemens per centimeter


NTU = Nephelometric turbidity unit


°C = degrees Centigrade

MCL = Maximum Contaminant Limit, Rule 62-550, FAC

Concentrations in parentheses ( ) are dissolved concentrations for samples having high turbidity







TEMPLE TERRACE, FLORIDA

1211 Tech Bvd. Suite 200 Tompo, Florido 33619 (813) 623-6646

04C-FA-042000

# APPENDIX A LABORATORY REPORTS & FIELD SAMPLING LOGS



## **ANALYTICAL REPORT**

Job Number: 660-8642-1

Job Description: Normandy Park

For:
QORE Property Science
1211 Tech Boulvard
Suite 200
Tampa, FL 33619

Attention: Mr. Larry Maron

Peggy Penner
Project Manager II

ppenner@stl-inc.com 04/28/2006

Project Manager: Peggy Penner DOH Certification #: E84282, E87052

These test results meet all the requirements of NELAC. All questions regarding this test report should be directed to the STL Project Manager who signed this test report. The estimated uncertainty associated with these reported results is available upon request.



## **METHOD SUMMARY**

Client: QORE Property Science

Job Number: 660-8642-1

Description		Lab Location	Method	Preparation Method
Matrix:	Water			
Inductive	ly Coupled Plasma - Atomic Emission Spectrometry	STL-TAM	SW846 6010	)B
	Acid Digestion of Waters for Total Recoverable or Sample Filtration performed in the Field	STL-TAM STL-TAM		SW846 3005A FIELD_FLTRD

#### LAB REFERENCES:

STL-TAM = STL-Tampa

#### **METHOD REFERENCES:**

SW846 - "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

## **SAMPLE SUMMARY**

Client: QORE Property Science

Lab Sample ID	Client Sample ID	Client Matrix	Date/Time Sampled	Date/Time Received
660-8642-1	PZ-1 042006	Water	04/20/2006 1017	04/24/2006 0815
660-8642-2	MW-11 042006	Water	04/20/2006 1156	04/24/2006 0815
660-8642-3	MW-DSA-2 042006	Water	04/20/2006 1254	04/24/2006 0815
660-8642-4	MW-10 042006	Water	04/20/2006 1417	04/24/2006 0815
660-8642-5	MW-DSA-1 042006	Water	04/20/2006 1458	04/24/2006 0815
660-8642-6	Dupe-1 042006	Water	04/20/2006 0000	04/24/2006 0815
660-8642-7	MW-8 042106	Water	04/21/2006 0812	04/24/2006 0815
660-8642-8	MW-13 042106	Water	04/21/2006 0910	04/24/2006 0815
660-8642-9	MW-12 042106	Water	04/21/2006 1021	04/24/2006 0815
660-8642-10	MVV-1 042106	Water	04/20/2006 1159	04/24/2006 0815
660-8642-11	MW-2 042106	Water	04/21/2006 1035	04/24/2006 0815
660-8642-12	MW-5 042006	Water	04/20/2006 1026	04/24/2006 0815
660-8642-13	MW-7A 042106	Water	04/21/2006 0845	04/24/2006 0815
660-8642-14	EB-1	Water	04/21/2006 0930	04/24/2006 0815

## **EXECUTIVE SUMMARY - Detections**

Client: QORE Property Science

Lab Sample ID Analyte	Client Sample ID	Result / Qualifier	Reporting Limit	Units	Method
660-8642-2	MW-11 042006				
Total Recoverable Lead Antimony		0.0017 I 0.031	0.0050 0.0060	mg/L mg/L	6010B 6010B
660-8642-4	MW-10 042006				
Total Recoverable Antimony		0.12	0.0060	mg/L	6010B
660-8642-7	MW-8 042106			erre	ne
Total Recoverable Antimony		0.021	0.0060	mg/L	6010B
660-8642-8	MW-13 042106				
Total Recoverable Antimony		0.032	0.0060	mg/L	6010B
660-8642-10	MW-1 042106				
<b>Dissolved</b> Lead, Dissolved Antimony, Dissolved		0.015 0.037	0.0050 0.0060	mg/L mg/L	6010B 6010B
Total Recoverable Lead Antimony		0.027 0.037	0.0050 0.0060	mg/L mg/L	6010B 6010B
660-8642-11	MW-2 042106				•
Dissolved Lead, Dissolved Antimony, Dissolved		0.0023 I 0.012	0.0050 0.0060	mg/L mg/L	6010B 6010B
Total Recoverable Lead Antimony		0.012 0.0097	0.0050 0.0060	mg/L mg/L	6010B 6010B

## **EXECUTIVE SUMMARY - Detections**

Client: QORE Property Science

Lab Sample ID Analyte	Client Sample ID	Result / Qualifier	Reporting Limit	Units	Method	
660-8642-12 Total Recoverable Antimony	MW-5 042006	0.090	0.0060	mg/L	6010B	
660-8642-13  Total Recoverable Lead Antimony	MW-7A 042106	0.24 0.030	0.0050 0.0060	mg/L mg/L	6010B 6010B	

## **SAMPLE RESULTS**

Client: QORE Property Science Job Number: 660-8642-1

Client Sample ID: MW-11 042006

 Lab Sample ID:
 660-8642-2
 Date Sampled:
 04/20/2006 1156

 Client Matrix:
 Water
 Date Received:
 04/24/2006 0815

6010B Inductively Coupled Plasma - Atomic Emission Spectrometry-Total Recoverable

Method:6010BAnalysis Batch: 660-24490Instrument ID:TJA ICPPreparation:3005APrep Batch: 660-24347Lab File ID:6D28BDilution:1.0Initial Weight/Volume:50 mL

 Dilution:
 1.0
 Initial Weight/Volume:
 50 mL

 Date Analyzed:
 04/28/2006 1232
 Final Weight/Volume:
 50 mL

 Date Prepared:
 04/26/2006 1312

 Analyte
 Result (mg/L)
 Qualifier
 MDL
 PQL

 Lead
 0.0017
 I
 0.0016
 0.0050

 Antimony
 0.031
 0.0036
 0.0060

Client: QORE Property Science Job Number: 660-8642-1

Client Sample ID: PZ-1 042006

Lab Sample ID: 660-8642-1 Date Sampled: 04/20/2006 1017

Client Matrix: Date Received: 04/24/2006 0815

6010B Inductively Coupled Plasma - Atomic Emission Spectrometry-Total Recoverable

Method: 6010B Analysis Batch: 660-24490 Instrument ID: TJA ICP

Preparation: 3005A Prep Batch: 660-24347 Lab File ID: 6D28B
Dilution: 1.0 Initial Weight/Volume: 50 mL

Date Analyzed: 04/28/2006 1216 Final Weight/Volume: 50 mL
Date Prepared: 04/26/2006 1312

Analyte Result (mg/L) Qualifier MDL PQL

Lead 0.0016 U 0.0016 0.0050

Antimony 0.0036 U 0.0036 0.0060

Client: QORE Property Science

Job Number: 660-8642-1

Client Sample ID: MW-DSA-2 042006

Lab Sample ID:

660-8642-3

Client Matrix:

Date Sampled:

04/20/2006 1254

Water

Date Received:

04/24/2006 0815

## 6010B Inductively Coupled Plasma - Atomic Emission Spectrometry-Total Recoverable

Method:

6010B

Analysis Batch: 660-24490

Instrument ID:

TJA ICP

Preparation:

3005A

Lab File ID:

Prep Batch: 660-24347

6D28B

Dilution:

1.0

Initial Weight/Volume:

Date Analyzed:

04/28/2006 1237

50 mL

Date Prepared:

04/26/2006 1312

Final Weight/Volume:

50 mL

Analyte

Qualifier

MDL

PQL

Lead Antimony 0.0016 0.0036

Result (mg/L)

U U 0.0016 0.0036 0.0050 0.0060

Client: QORE Property Science

Job Number: 660-8642-1

Client Sample ID: MW-10 042006

Lab Sample ID:

660-8642-4

Date Sampled:

04/20/2006 1417

Client Matrix:

Water

Date Received:

04/24/2006 0815

6010B Inductively Coupled Plasma - Atomic Emission Spectrometry-Total Recoverable analysis Plasma

Method:

6010B

Analysis Batch: 660-24490

Instrument ID:

TJA ICP

Preparation:

3005A

Lab File ID:

6D28B

Dilution:

1.0

Prep Batch: 660-24347

Initial Weight/Volume:

Date Analyzed: 04/28/2006 1242

50 mL

Date Prepared: 04/26/2006 1312

Final Weight/Volume:

50 mL

Analyte

Result (mg/L)

Qualifier

U

MDL

**PQL** 

Lead Antimony 0.0016 0.12

0.0016 0.0036

0.0050 0.0060

Client: QORE Property Science Job Number: 660-8642-1

Client Sample ID: MW-DSA-1 042006

660-8642-5 Date Sampled: 04/20/2006 1458 Lab Sample ID: Client Matrix: Water Date Received: 04/24/2006 0815

6010B Inductively Coupled Plasma - Atomic Emission Spectrometry-Total Recoverable

Method: 6010B Preparation: 3005A

Dilution: 1.0

04/28/2006 1247 Date Analyzed: Date Prepared: 04/26/2006 1312 Analysis Batch: 660-24490

Prep Batch: 660-24347

Instrument ID: Lab File ID:

TJA ICP 6D28B

Initial Weight/Volume:

50 mL

Final Weight/Volume:

50 mL

Analyte	Result (mg/L)	Qualifier	MDL	PQL
Lead	0.0016	บ	0.0016	0.0050
Antimony	0.0036	ป	0.0036	0.0060

Client: QORE Property Science

Job Number: 660-8642-1

Client Sample ID: Dupe-1 042006

Lab Sample ID:

660-8642-6

Client Matrix:

Water

Date Sampled:

04/20/2006 0000

Date Received: 04/24/2006 0815

6010B Inductively Coupled Plasma - Atomic Emission Spectrometry-Total Recoverable

Method:

6010B

Analysis Batch: 660-24490

Instrument ID:

TJA ICP

Preparation:

3005A

Lab File ID:

6D28B

Dilution:

Prep Batch: 660-24347

1.0

Initial Weight/Volume:

50 mL

Date Analyzed:

04/28/2006 1252

Final Weight/Volume:

50 mL

Date Prepared:

04/26/2006 1312

Analyte

Result (mg/L)

Qualifier

MDL

PQL

Lead **Antimony**  0.0016 0.0036 U U 0.0016 0.0036 0.0050 0.0060

Client: QORE Property Science

Job Number: 660-8642-1

Client Sample ID: MW-8 042106

Lab Sample ID:

660-8642-7

Client Matrix:

Water

Date Sampled:

04/21/2006 0812

Date Received:

04/24/2006 0815

6010B Inductively Coupled Plasma - Atomic Emission Spectrometry-Total Recoverable

Olegia.

Method:

6010B

Analysis Batch: 660-24490

Instrument ID:

TJA ICP

Preparation:

3005A

Prep Batch: 660-24347

Lab File ID:

6D28B

Dilution:

1.0

Initial Weight/Volume:

50 mL

Date Analyzed: Date Prepared:

04/28/2006 1258

Final Weight/Volume:

50 mL

Analyte

04/26/2006 1312

Qualifier Result (mg/L)

MDL

PQL

Lead Antimony

0.0016 0.021

U

0.0016 0.0036 0.0050 0.0060

Page 13 of 27

Client: QORE Property Science

Job Number: 660-8642-1

Client Sample ID: MW-13 042106

Lab Sample ID:

660-8642-8

Client Matrix:

Water

Date Sampled:

04/21/2006 0910

Date Received:

04/24/2006 0815

6010B Inductively Coupled Plasma - Atomic Emission Spectrometry-Total Recoverable

Method: Preparation: 6010B 3005A Analysis Batch: 660-24490

Instrument ID:

TJA ICP 6D28B

Dilution:

1.0

Prep Batch: 660-24347

Lab File ID:

Date Analyzed:

Initial Weight/Volume:

50 mL

Date Prepared:

04/28/2006 1313 04/26/2006 1312 Final Weight/Volume:

50 mL

Analyte

Result (mg/L)

Qualifier

U

MDL

PQL

Lead **Antimony**  0.0016 0.032

0.0016 0.0036 0.0050 0.0060

Client: QORE Property Science

Job Number: 660-8642-1

Client Sample ID: MW-12 042106

Lab Sample ID:

660-8642-9

Date Sampled:

04/21/2006 1021

Client Matrix:

Water

Date Received:

04/24/2006 0815

6010B Inductively Coupled Plasma - Atomic Emission Spectrometry-Total Recoverable

Method:

Analysis Batch: 660-24490

Instrument ID:

TJA ICP

Preparation:

6010B 3005A

Lab File ID:

Dilution:

1.0

Prep Batch: 660-24347

6D28B

Initial Weight/Volume:

Date Analyzed: 04/28/2006 1318

50 mL

Date Prepared:

Final Weight/Volume:

04/26/2006 1312

50 mL

Analyte	Result (mg/L)	Qualifier	MDL	PQL
Lead	0.0016	U	0.0016	0.0050
Antimony	0.0036	U	0.0036	0.0060

Client: QORE Property Science

Job Number: 660-8642-1

Client Sample ID: MW-1 042106

Lab Sample ID:

660-8642-10

Client Matrix:

Water

Date Sampled:

04/20/2006 1159

Date Received:

04/24/2006 0815

#### 6010B Inductively Coupled Plasma - Atomic Emission Spectrometry-Total Recoverable

Method:

Dilution:

Preparation:

6010B 3005A

1.0

Date Analyzed: Date Prepared:

04/28/2006 1323 04/26/2006 1312 Analysis Batch: 660-24490

Prep Batch: 660-24347

Instrument ID: Lab File ID:

TJA ICP 6D28B

Initial Weight/Volume:

50 mL

Final Weight/Volume:

50 mL

Result (mg/L) Qualifier MDL **PQL** Analyte 0.027 0.0016 0.0050 Lead 0.037 0.0036 0.0060 **Antimony** 

#### 6010B Inductively Coupled Plasma - Atomic Emission Spectrometry-Dissolved

romic &

Method: Preparation:

Analyte

6010B

3005A 1.0

Dilution: Date Analyzed: Date Prepared:

Lead, Dissolved

Antimony, Dissolved

04/28/2006 1328 04/26/2006 1312 Analysis Batch: 660-24490

Prep Batch: 660-24347

Instrument ID:

Lab File ID: Initial Weight/Volume:

6D28B 50 mL

Final Weight/Volume:

50 mL

TJA ICP

Qualifier MDL PQL Result (mg/L) 0.015 0.0016 0.0050 0.037 0.0036 0.0060

Client: QORE Property Science

Job Number: 660-8642-1

Client Sample ID: MW-2 042106

Lab Sample ID:

660-8642-11

Client Matrix:

Water

Date Sampled:

04/21/2006 1035

Date Received:

04/24/2006 0815

#### 6010B Inductively Coupled Plasma - Atomic Emission Spectrometry-Total Recoverable

Method: Preparation: 6010B

3005A

1.0

Dilution: Date Analyzed:

04/28/2006 1334 Date Prepared: 04/26/2006 1312 Analysis Batch: 660-24490

Prep Batch: 660-24347

Instrument ID:

TJA ICP

Lab File ID: Initial Weight/Volume: 6D28B

Final Weight/Volume:

50 mL

50 mL

Analyte	Result (mg/L)	Qualifier	MDL	PQL
Lead	0.012		0.0016	0.0050
Antimony	0.0097		0.0036	0.0060

#### 6010B Inductively Coupled Plasma - Atomic Emission Spectrometry-Dissolved

Method:

6010B

Preparation: 3005A Dilution: 1.0

Date Analyzed:

04/28/2006 1339

Date Prepared: 04/26/2006 1312 Analysis Batch: 660-24490

Prep Batch: 660-24347

Instrument ID:

Lab File ID:

TJA ICP 6D28B

Initial Weight/Volume:

50 mL 50 mL

Final Weight/Volume:

Analyte	Result (mg/L)	Qualifier	MDL	PQL
Lead, Dissolved	0.0023	l	0.0016	0.0050
Antimony, Dissolved	0.012		0.0036	0.0060

Client: QORE Property Science

Job Number: 660-8642-1

Client Sample ID: MW-5 042006

Lab Sample ID:

660-8642-12

Client Matrix:

Water

Date Sampled:

04/20/2006 1026

Date Received:

04/24/2006 0815

#### 6010B Inductively Coupled Plasma - Atomic Emission Spectrometry-Total Recoverable

in Garies

Method: Preparation: 6010B

3005A

1.0

Dilution:

04/28/2006 1344 Date Analyzed: Date Prepared:

04/26/2006 1312

Analysis Batch: 660-24490

Prep Batch: 660-24347

Instrument ID:

Lab File ID:

TJA ICP 6D28B

Initial Weight/Volume:

50 mL

Final Weight/Volume:

50 mL

Analyte

Result (mg/L)

Qualifier

MDL

**PQL** 

**Antimony** 

0.090

0.0036

0.0060

Client: QORE Property Science

Job Number: 660-8642-1

Client Sample ID: MW-7A 042106

Lab Sample ID:

660-8642-13

Client Matrix:

Water

Date Sampled:

04/21/2006 0845

Date Received:

04/24/2006 0815

#### 6010B Inductively Coupled Plasma - Atomic Emission Spectrometry-Total Recoverable

Method:

6010B

Analysis Batch: 660-24490

Instrument ID:

TJA ICP

Preparation:

3005A

Prep Batch: 660-24347

Lab File ID:

6D28B

Dilution:

1.0

Initial Weight/Volume:

50 mL

Date Analyzed:

04/28/2006 1349

Final WeightVolume:

50 mL

Date Prepared:

04/26/2006 1312

MDL

Analyte

Result (mg/L)

Qualifier

0.0016

PQL

Lead **Antimony**  0.24 0.030

0.0036

0.0050 0.0060

Client: QORE Property Science

Job Number: 660-8642-1

Client Sample ID: EB-1

Lab Sample ID:

660-8642-14

Client Matrix:

Water

Date Sampled:

04/21/2006 0930

Date Received:

04/24/2006 0815

## 6010B Inductively Coupled Plasma - Atomic Emission Spectrometry-Total Recoverable

nic Emiss

Method:

6010B

3005A

Analysis Batch: 660-24490

Instrument ID:

TJA ICP

Preparation:

1.0

Prep Batch: 660-24347

Lab File ID:

6D28B

Dilution:

Initial Weight/Volume:

50 mL

Date Analyzed:

04/28/2006 1354

Date Prepared:

04/26/2006 1312

Final Weight/Volume:

50 mL

Analyte	Result (mg/L)	Qualifier	MDL	PQL
Lead	0.0016	U	0.0016	0.0050
Antimony	0.0036	U	0.0036	0.0060

## DATA REPORTING QUALIFIERS

Client: QORE Property Science

Lab Section	Qualifier	Description
Metals		
	U	Indicates that the compound was analyzed for but not detected.
	1	The reported value is between the laboratory method detection limit and the laboratory practical quantitation limit.

# **QUALITY CONTROL RESULTS**

### **Quality Control Results**

Job Number: 660-8642-1

Client: QORE Property Science

Method Blank - Batch: 660-24347

Method: 6010B Preparation: 3005A **Total Recoverable** 

Lab Sample ID: MB 660-24347/1-A

Client Matrix:

Water 1.0

Dilution: Date Analyzed: 04/28/2006 1145 Date Prepared: 04/26/2006 1312 Analysis Batch: 660-24490 Prep Batch: 660-24347

Units: mg/L

Instrument ID: TJA ICP Lab File ID: 6D28B

Initial Weight/Volume: 50 mL Final Weight/Volume: 50 mL

Analyte	Result	Qual	MDL	PQL
Lead	0.0016	U	0.0016	0.0050
Lead, Dissolved	0.0016	U	0.0016	0.0050
Antimony	0.0036	U	0.0036	0.0060
Antimony, Dissolved	0.0036	U	0.0036	0.0060

Laboratory Control/

Laboratory Control Duplicate Recovery Report - Batch: 660-24347

Method: 6010B Preparation: 3005A

LCS Lab Sample ID: LCS 660-24347/2-A

Client Matrix:

Water

Dilution:

1.0

Date Analyzed: Date Prepared: 04/28/2006 1151 04/26/2006 1312 Analysis Batch: 660-24490

Prep Batch: 660-24347

Units: mg/L

**Total Recoverable** 

Instrument ID: TJA ICP Lab File ID: 6D28B

Initial Weight/Volume: 50 mL

Final Weight/Volume: 50 mL

LCSD Lab Sample ID: LCSD 660-24347/3-A

Client Matrix:

Water

Dilution:

1.0

Date Analyzed: Date Prepared:

04/26/2006 1312

04/28/2006 1156

Analysis Batch: 660-24490

Prep Batch: 660-24347

Units:mg/L

Instrument ID: TJA ICP Lab File ID: 6D28B

Initial Weight/Volume: 50 mL

Final Weight/Volume: 50 mL

	<u>9</u>	<u> 6 Rec.</u>					
Analyte	LCS	LCSD	Limit	RPD	RPD Limit	LCS Qual	LCSD Qual
Lead	104	102	75 - 125	3	20		
Lead, Dissolved	104	102	75 - 125	3	20		
Antimony	94	92	75 - 125	2	20		
Antimony, Dissolved	94	92	75 - 125	2	20		

## **Quality Control Results**

Client: QORE Property Science

Job Number: 660-8642-1

Matrix Spike/

Matrix Spike Duplicate Recovery Report - Batch: 660-24347

Method: 6010B Preparation: 3005A **Total Recoverable** 

MS Lab Sample ID: 660-8642-1

Analysis Batch: 660-24490

Instrument ID: TJA ICP

Client Matrix:

Water

Lab File ID:

Dilution:

Prep Batch: 660-24347

6D28B

1.0

Initial Weight/Volume: 50 mL

Date Analyzed: Date Prepared: 04/28/2006 1222 04/26/2006 1312 Final Weight/Volume: 50 mL

MSD Lab Sample ID: 660-8642-1

Analysis Batch: 660-24490

Instrument ID: TJA ICP

Client Matrix:

Water

Lab File ID: 6D28B

Dilution:

1.0

Prep Batch: 660-24347

Initial Weight/Volume: 50 mL

Date Analyzed:

04/28/2006 1227

Final Weight/Volume: 50 mL

Date Prepared:

04/26/2006 1312

% Rec.

Analyte	MS	MSD	Limit	RPD	RPD Limit	MS Qual MSD Qual
Lead	100	101	75 - 125	1	20	
Lead, Dissolved	100	101	75 - 125	1	20	
Antimony	92	91	75 - 125	1	20	
Antimony, Dissolved	92	91	75 - 125	1	20	

				<del> </del>							3331	L **		
SEVERN STL					STL Tampa Website: www.stl-inc.com 6712 Benjamin Road, Suite 100 Phone: (813) 885-7427 Tampa, FL 33634 Fax: (813) 885-7049							·		
TO TO SIGN					ernate L	aborato	ory Name	/Loca	tion					
											Phone: Fax:			
PROJECT REFERENCE PROJECT NO.  ROMANUM PARK 2148 MM	PROJECT LOCATION	MAT					REOL	JIRED /	ANALYSIS			PAGE	1	7F
No Mand Park 2148 MM SAMPLER'S SIGNATURE P.O. NUMBER	(STATE) FL	TY	тт.	<del>.  </del>	<del></del>	_ <u>ਨ</u> ਾ		-						<u> </u>
13. M Dunie	CONTRACT NO.	끧				150		- 1	1	1	1	DELI	Dard Report Ery	8: I
CLIENT (SITE) PM CLIENT PHONE	CLIENT FAX	INDICATE	. IN	<u>.</u>		10	1		\ \	1	1		ATE DUE	<b>7</b> F
Larry Maron 623-6646	623-3795	(0)	Ī	7	)			- 1	1			- 1		
CLIENT NAME CLIENT E-MAIL				<u> </u>	J i	Fi / f. r.			}			] DELIN		
QORE		GRAB C	عِ الْحِ	3		, <del>7</del>	į	- 1		Į		(SUR	CHARGE)	
CLIENT ADDRESS Tamper FL 33619						7						0	ATE DUE	
COMPANY CONTRACTING THIS WORK (if applicable)	<del></del>	S A S		3	3	2		-, T	1	1			ER OF COOLER	S SUBMITTED
The Politice of the Politice o		SSS		1403	Eort.	Hwo 3		· 1.	1			PER	SHIPMENT:	į
SAMPLE SAMPLE IDENTIFICATION		COMPOSITE (C) OR GR. AQUEOUS (WATER)	SOLID ON SEMISOLID AIR NONADI IFOLIS LIDIJD IDIL SOLVENT			NIIM	BER OF C	ONTAI	NERS SUE	MITTED	L		REMARK	
DATE TIME	•	SE	하 공   2	-	<del></del>	1,40,1	- I		7-10		<del>, , , , , , , , , , , , , , , , , , , </del>			· · · · · ·
4/20/06 1017 PZ-1 042006		X	$\bot \bot$	$\perp \perp$	<u> </u>								<del></del>	27
1156 mw-11 042004	<del></del>	X		$\perp L$										
1254 MW-DSA-2 042006		K		1										<u> </u>
1417 MW-10 042006		X		1										700
1458 MW-DSA-1 042006				1.										0
V - Dupe-1		8		1										
4/21/06 08/2 MW-8 042106		M	П	1										
1 0910 MW-13 642104		M		17										
V 1021 MW-12 042106		X	$\top$	1							1			
4/20/06 1159 MW-1 042006		X	71	1		1								
4/21/66 1035 MW-2 042/04		M		17		1								
			11	1		•								
	RELINQUISHED BY; (SIG	NATURE)			DATE	1.	TIME		RELINQUI	RED BY:	(SIGNATURE)		DATE	TIME
9/1/1/6	RECEIVED BY: (SIGNATURE)	<u>1 (</u>	206	E		lole		0	BALL	15	M		7-24-Co	0815
PRECEIVED BYNGSIGNATURE) DATE TIME	RECEIVED BY: (SIGNATU				DATE	. ]	TIME	,	RECEIVED	BY: (SIGN	(3RUTA		DATE	TIME
13. M Ken QORK 4/19/66	MULIN SI	<u>×                                      </u>	512		1-2	10G	07	30					<u></u>	
		LABORA						* Č = - :	· .			<u> </u>	- <del></del>	
	CUSTODY INTACT YES .	CUSTO SEAL N	NO.	LOG	Tampa No.		FARORA	I OKY I	KEMARKS	NO	ICE	<u>,</u>	•	
anvan xult 4-2400 0815	NO O				1004	V ·		·	· · · · · · · · · · · · · · · · · · ·					

Serial Number 33915

													<u> </u>	<u> 21:</u>	<u> </u>	
ANALYSIS REQUEST AND CHAIN OF CUSTODY RECORD  SEVERN						STL Tampa         Website: www.stl-inc.com           6712 Benjamin Road, Suite 100         Phone: (813) 885-7427           Tampa, FL 33634         Fax: (813) 885-7049								85-7427		
TRENT DIL				<	⊃ Alt	ernate	Laborat	ory Nar	ne/Loc	ation			hone: ax:			
PROJECT REFERENCE PROJECT NO. 2148M	PROJECT LOCATION (STATE)		ATRE					RE	QUIREC	ANALY	SIS				PAGE 2	OF 2
SAMPLER'S SIGNATURE P.O. NUMBER  CLIENT (SITE) PM CLIENT PHONE	CONTRACT NO.	1TE													STANDARD REPOR	₹ 🕉
CLIENT (SITE) PM CLIENT PHONE  COTAY MORON 623-6646	CLIENT FAX 623-3795	INDICATE		O VEN											DATE DUE	
CLIENT NAME CLIENT E-MAIL	<u> </u>	GRAB (G)		(C)		1									EXPEDITED REPOR	
QORE CLIENT ADDRESS		88	S S	2			7								(SURCHARGE)  DATE DUE	
COMPANY CONTRACTING THIS WORK (if applicable)		COMPOSITE (C) OR GRA AQUEOUS (WATER)	OR SEMI	AIR NONACHEONIS FROM SOLVENT	2 2	7 7	3		!	<del>                                     </del>	<del> </del> 	<del> </del>	 		NUMBER OF COOL PER SHIPMENT:	ERS SUBMITTED
SAMPLE SAMPLE IDENTIFICATION DATE TIME	DN .	AOUE	OTOS	NON AR				MBER O	CONT	AINERS	SUBMIT	ITED			REMAR	eks
4/2010/6 1026 MW-5 042006		X	1		4	1										7.0
4/21/06 0845 MW-74 042106.		1	11	- {	11	1	1									3
- 0930 EB-/		×			1											90
				_	<del>                                     </del>											
		-	$\vdash$	-	-		-		· .				 			
		- -	H	+	┼-	-										
		$\vdash \vdash$	H		┼-	+-										
		- -	$\dagger \dagger$	$\uparrow$	$\vdash$	1	1	-								
1																
RELINOUSHED BY: (SKSYATYRE) DATE TIME	DELINIOUSUED BY: 100	MATURE	ĻŢ	<u> </u>	<u> </u>	. DAT	<u> </u>	TIME	<u> </u>	DELIN	UIISHE	DANG (	SIGNATUR	DE)	DATE	TIME
Man / 1/1/11 4/6/06 173	RELINQUISHED BY: (SIG	in iune	,			14/0	Nole		30	1	)nd	1/2	X.	M	- 12-xp0	0818
B. M. Burns QORE 1/19/66	RECERTED BY: ISKNATU	(E)				DAT	4-de	TIME	130		VED BY	: SIGNA	TURE)		DATE	TIME
	- Company				JSE ON	LY "	•			•						
RECEIVED FOR LABORATORY BY DATE TIME (SIGNATURE)	CUSTODY INTACT YES O NO O	CUS	NO.	<i>(</i>	LOG	TAMPA NO.	$\chi \gamma$	LABO	RATORY	REMAR	rks A		<i>p</i> /o	FC	<u>E</u>	,

## LOGIN SAMPLE RECEIPT CHECK LIST

Client: QORE Property Science

Job Number: 660-8642-1

Login Number: 8642

Question	T/F/NA	Comment
Radioactivity either was not measured or, if measured, is at or below background	NA	
The cooler's custody seal, if present, is intact.	NA	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	False	metal samples
Cooler Temperature is acceptable.	NA	
Cooler Temperature is recorded.	NA	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
There are no discrepancies between the sample IDs on the containers and the COC.	True	
Samples are received within Holding Time.	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
VOA sample vials do not have headspace or bubble is <6mm (1/4") in diameter.	True	
If necessary, staff have been informed of any short hold time or quick TAT needs	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	



## WATER LEVEL DATA

CLIENT	UCK		DA1	TE 4/20/	o le
JOB NO.	2148 M		E	BY 13 TA	۷ .
	Normandy Pa	rk			
MEASURING DE	VICE Slope		DATL	J <b>M</b>	<del></del>
WELL NUMBER	TOP OF CASING ELEVATION ( )	DEPTH TO WATER	WATER ELEVATION ( )	TIME	REMARKS
Mw-1		8.37		0729	
MW-10		9.57		c732	<del> </del>
MW DSA-1		9.72		0733	
Mw-74		9.02		0738	
Mw-le PZ-Z		10.01		0743	
PZ-2		57.28		0745	
Mw-12		11.81		0748	
Mw-4		Dry		0751	<del></del>
Mu-3	······································	Dry		0757	· ·
Ft muft!		59.70		0757	
MW-9		9.22	- <del></del>	0801	· · · · · · · · · · · · · · · · · · ·
MW-2		8:04	· · · · · · · · · · · · · · · · · · ·	0805	
Mw-13 PZ-1		Dry		0809	
1-51		54.86	··· - · · · · · · · · · · ·	083-3	<del> </del>
MW 11		6.95		0835	<u></u>
		10,20		1/36	
ru DSA-2		16.20		1230	
COMMENTS		Or 10		1/	<del></del>
MW-8		9-04		1572	<u> </u>
				· · · · · ·	

## DEP-SOP-001/01 FT 1200 Field Measurement of Specific Conductance

## Form FD 9000-8: FIELD INSTRUMENT CALIBRATION RECORDS

INSTRUME	NT (MA	KER/MO[	DEL#)	moHe 20201	NSTRU	иent # <i>2<u>6</u>85</i>	54	
PARAMET	ER: [ch	eck only o	ne]					
☐ TEMP	ERATUR	E CON	OUCTIVITY	SALINITY[	] pH	ORP		•
X) TURB	YTIDI	☐ RESI	DUAL CI	□ DO [	OTHER			:
values, and th	e date the	e standards v	were prepa	dards used for cal red or purchased]		ne origin of the s	standards, the s	standard
Standar	rd A		Non	<del> </del>	<del></del>			
Standar	rd B	810			<del></del>			
	rd C							
DATE (yy/mm/dd)	TIME (hr:min)	STD (A, B, C)	STD VALUE	INSTRUMENT RESPONSE	% DEV	CALIBRATED (YES, NO)	TYPE (INIT, CONT)	SAMPLER INITIALS
060420	e859	A	<u> </u>	ලලව	NA	yes.	INT	BJM
• -		$\mathcal{B}$	800	800			cont	
W.	1036	A	41	_000				
1	1202	$\mathcal{B}$	80C	800	-	~		
-	1300	A	4	000	~			
	1425	B	800	800	1-	ب	٠.	-
1	1503	A	41	000	1		-	<i>j</i>
dio421	0738	$\mathcal{B}$	800	800			/-	
	0818	A	< j	000	1-		~	
11	0915	B	800	800		•	-	
11	1047	A	4	000		10	10	11
								1.
				<del></del>			· · · · · · · · · · · · · · · · · · ·	-
				·				

Revision Date: February 1, 2004

FORM FD 9000-8: FIELD INSTRUMENT CALIBRATION RECORDS

INSTRUMENT (MAKER/MODEL#) Degree INSTRUMENT # 6/7/

PARAMETER: [check only one]

TEMPERATURE | CONDUCTIVITY | SALINITY | ph | ORP
| TURBIDITY | RESIDUAL CI | DO | OTHER |

STANDARDS: [Specify the type(s) of standards used for calibration, the origin of the standards, the standard values, and the date the standards were prepared or purchased]

Standard A NTST Traceable

Standard C

DATE TIME | STD | STD | INSTRUMENT | CALIBRATED | TYPE | SAMPLE (SYMMIND) | (hr.min) | (A, B, C) | VALUE | RESPONSE | % DEV | (YES, NO) | (INIT, CONT) | INITIAL

Standar	a C					3		
DATE (yy/mm/dd)	TIME (hr.min)	STD (A, B, C)	STD VALUE	INSTRUMENT RESPONSE	% DEV	CALIBRATÉD (YES, NO)	TYPE (INIT, CONT)	SAMPLER A INITIALS
	0902	A	/	23.92		Les	エーナ	BJM
-	1038	A		26.8°C			Cont	/~
	12e3	A	/	30,7c	_/	~ر	~	
1-	1302	A		31.2°C		·	· ·	e" i. "
~-	1427	A		32.3c	/	/-	J	٠-
1	150h	A		34.0c		ν-	1	1
060421	0739	A		23.7c	/		``	1
	819	A		23.5c	1	i l	<i></i>	1
1-	09/7	À		25-2c		( ~	^	g
~_	1050	A		28-4°C			1-	
		·						

# Form FD 9000-8: FIELD INSTRUMENT CALIBRATION RECORDS INSTRUMENT (MAKER/MODEL#) \( \sumsetengger \) \( \su

(Nythmidd) (hr.min) (A, B, C) VALUE RESPONSE % DEV (YES, NO) (INIT CONT) CONTINITIALS  La 420 8703 A 7 cm 1 8 2 16 - Con 7 - Con 7 -   1203 A 7 cm 7 7-7-28c 1 -   1302 B 02 .14 .14 -   1427 A 5 cm 7-3-31c .1 -   1506 B 02 .05 .05 -   1506 B 02 .05 .05 -   1507 B 02 .05 .05 - Cm	Standar	U C							
1203 A 300 7.7-286 .1	DATE (yy/mm/dd)		STD (A, B, C)	VALUE	INSTRUMENT RESPONSE	% DEV	CALIBRATED . (YES, NO)	TYRE (INIT_CONT)	∴SAMPLER ∡∷INITIALS
B 02 16 - Cont  1703 A 3201 7.7-28C .1  1302 B 02 .14 .14  - 1127 A 500 7.3-31C .1  - 1506 B 200 .05 .05  - 819 B 250 .17 .17  - 819 B 250 .17 .17  - 1050 B 200 .10 .10  .10 .10 .10 .10 .10 .10 .10 .10 .	da 420	0903	A	Jev-1	8.7-75c	NA	Yes	INT	BJM
- 1302 B	1	~~	$\mathcal{B}$	(ウァ	16		ي ا	Cont	
- 1427 A Sevel 7.3-31°C .1		1203	A	15201	7.7-28°C	./		1	~
- 819 B 32 .17 .17	1-		В	1777	.14	.14	~~		~
- 819 B 32 .17 .17		1427	_A	Secol Texal	7-3-312				
- 819 B 32 .17 .17	/	150h	$\mathcal{B}$	02	,05		~		1
- 819 B 32 .17 .17	068471	6739	A	/cve/	8.4-23c		~	~	· · · ·
	1	0819	$\mathcal{B}$	02	.17	.17	+-	<b>,</b> _	~ _
		0918	A	12 Vel.	8.0-2C	.1	1/		
		1050	B	200		10			
	1		· · · · · · · · · · · · · · · · · · ·						
			   <u>.                                     </u>						
	-		 	<u> </u>					
							· · · · · · · · · · · · · · · · · · ·		
			L				·		
					-				

	RUMENT CALIBRATION RECORDS
INSTRUMENT (MAKER/MODEL# 10/c lave	instrument #37637
PARAMETER: [check only one]	
TEMPERATURE CONDUCTIVITY S	ALINITY DH DRP
☐ TURBIDITY ☐ RESIDUAL CI ☐ D	O OTHER
STANDARDS: [Specify the type(s) of standards usualues, and the date the standards were prepared or p	sed for calibration, the origin of the standards, the standard urchased]
Standard A 15-00 MS	
Standard B 84.0 us	
Standard C	

(yymm/dd) (hr.min) (A, B, C) VALUE RESPONSE % DEV (YES, NO) (INIT, CONT) WINIT	MPLER TIALS
060420 0918 A 15.00 15.00 15.00 14.87MS - CONT - 1205 B 84.0 85.5us	37M
1- 1041 A 15.00 14.87Ms 1- 1- 1205 B 84.0 85.5us 1- 1-	
1- 1041 A 15.00 14.87MS ~	-
1-1205 B 84.0 85.545	
	-
	-
- 1929 B 84.0 85./us	_
- 1508 A 15.00 14.90 MS	
060421 0741 B 84.0 85.845	
- 820 A 15.00 14.78MS	-
0920 B 84.0 85.3	
1052 A 15.00 14.52ms	_
	· ·

# Form FD 9000-8: FIELD INSTRUMENT CALIBRATION RECORDS INSTRUMENT (MAKER/MODEL#D/Con 2304 INSTRUMENT #01948 PARAMETER: [check only one] TEMPERATURE CONDUCTIVITY SALINITY PH ORP TURBIDITY RESIDUAL CI DO OTHER STANDARDS: [Specify the type(s) of standards used for calibration, the origin of the standards, the standard values, and the date the standards were prepared or purchased]

Standard A 7-06
Standard B 4-01
Standard C 10.00 D: 1.68

Stariuai	U U			<del></del>				
DATE (yy/mm/dd)	TIME (hr:min)	STD (A, B, C)	STD VALUE	INSTRUMENT RESPONSE	% DEV	CALIBRATED (YES, NO)	TYPE (INIT, CONT)	SAMPLER INITIALS
oboybo	ी।४	A	7.00	7.00		·		
	^	13	4-01	4.01 54	100.4	755	INT	BIM
(-·	« ~	C	10.00	9.81	,19	٧	Cont	
	1042	A	7.00	7.08	.08	~_		
/-	1205	B	4.01	4.19	-18		^	~
	1305	<u> </u>	1.68	1. 73	گه.			
	143°	<u>A</u>	7.00	7.08	.08		<i></i>	. سرب
	1509	D	1.68	1.75	,07			
060421	0744	A	7.00	6-94	.ole			
1-	0870	${\cal B}$	4-01	4.04	٤٥,	~		~
1-	0920	A	7.00	7.07	.07	/_	~	
	1053	B	4.01	4-18	./7	/-		
					· · · · · · · · ·			
			<u></u>	·				
<u> </u>								

Form FD 9000-8: FIELD INSTRUMENT CALIBRATION RECORDS
INSTRUMENT (MAKER/MODEL#) 45755 INSTRUMENT # 968 45391
PARAMETER: [check only one]
☐ TEMPERATURE ☐ CONDUCTIVITY ☐ SALINITY ☐ pH ☐ ORP
TURBIDITY RESIDUAL CI DO OTHER
<b>STANDARDS:</b> [Specify the type(s) of standards used for calibration, the origin of the standards, the standard values, and the date the standards were prepared or purchased]
Standard A SEAUFIEL
Standard B 7540 O2
Standard C

DATE	TIME	STD	STD	INSTRUMENT	~ pp.	CALIBRATED	TYPE	SAMPLER
(yy/mm/dd)	(hr.min)	(A, B, C)	STA UEVEL	RESPONSE	% DEV	(YES, NO)	(INIT, CONT)	* INITIALS
do \$4 2¢	ןייון		ZENOO,	-to:/_	10/1	75>	JAIL	
٦١.		<del></del>	STA	0.20	Ø.20	11	CONT	XIP.
-	TANT	_A_		2.02	$\psi \cdot \psi$	u	·,	ve)
	1218	_B	25,000 SBA! LEVEL	0.11	Ø.(7			be
068471	1846	A	Eru O	8.5	Φ	.u	11	be
	0903	<u>B</u>	Stra	$\varphi \cdot \mathcal{L} \varphi$	<b>9</b> .29	11	<u>ل</u> لا	Ke
17	1933	A	STA	6.29	\$.24	প	ч.	KR
		_					·	
ļ							, 	
			[ 					
ļ		<del></del>						
		 <del> </del>						
		<del></del>					<del></del>	
							, 	
		•	<u> </u>					
		· · · · · · · · · · · · · · · · · · ·						
		<del> </del>						
	<del>                                     </del>							
L	<u></u>	L	لـــــــــــــــــــــــــــــــــــــ					

# FORM FD 9000-8: FIELD INSTRUMENT CALIBRATION RECORDS INSTRUMENT (MAKER/MODEL#) DIGITAL INSTRUMENT # 191768 PARAMETER: [check only one] | TEMPERATURE | CONDUCTIVITY | SALINITY | ph | ORP | | TURBIDITY | RESIDUAL CI | DO | OTHER | STANDARDS: [Specify the type(s) of standards used for calibration, the origin of the standards values, and the date the standards were prepared or purchased] Standard A | NIST | TRACEABLE | Standard B |

Standa	rd C							••
ODATE (yy/mm/dd)	TIME (hr:min)	STD (A, B, C)	STD VALUE	INSTRUMENT RESPONSE	% DEV	CALIBRATED (YES, NO)	TYPE (INIT, CONT)	SAMPLER INITIALS
0640426	8418	A		27.1°C		YEZ	INIT	KIRS
w	1845	A		29.3°C		٦	CONT	ka
JU04420	1219	A		29.90		ч	(1	ke.
05/204/21	<b>9809</b>	A		23.2°()		٠,	U	KR
is '	20101	A	-	25.4°C		بر	7	6
W.	034	1		37.00%		h	1)	YP
						·		· ·
					-			
						·		
								<del></del>
							·	
<del> </del>	<del>                                     </del>							
	<del> </del>							
<b></b>								
	<del> </del>							
<del> </del>	<del> </del>							
L	<u> </u>	L	<u> </u>				l	

Page 8 of 8 Revision Date: February 1, 2004

### 

DATE (yy/mm/dd)	TIME (hcmin)	STD (A, B, C)	STD VALUE	INSTRUMENT RESPONSE	% DEV	CALIBRATED (YES, NO)	TYPE (INIT, CONT)	SAMPLER INITIALS
666426		_A	¥6.1	Ø, øø	BNA	YES	Dvr	WE)
(1	u	B	800	800	M	, 4	CONT	VR
٠,٠	844	A	461	Ø.øø	NA	Č (	cont	lae
ખ	(222	3	800	800	W	ч	cont	KR
060421	1080	A	< Ø. i	7 00	MA	(1	Ų	KR
φοι,	1915	B	800	800	NA	U	ધ	KR
N	034	À	201	ØØØ	NA	cl	Çį	KR
	, , ,					·		
			· .	 				
_								
				· · · · · · · · · · · · · · · · · · ·				
				<del></del>				
		-						
						·		
		<del></del>		<del></del>		<del></del>		··
		<del>_</del>						
						·		
				<del></del>				<del></del>
	-							<del></del>

	Form	FD 9000-	B: FIELD	INSTRUMEN	T CALIE	BRATION RE	ECORDS			
INSTRUME	NT (MA	KER/MOD	EL#)	1301A 11	NSTRUM	MENT# 0	7431			
PARAMET	ER: [ch	eck only o	ne]							
☐ TEMP	ERATUR	E CON	OUCTIVITY	SALINITY	ЪН	ORP				
☐ TURB	IDITY	RESI	DUAL CI	□ DO [	OTHER					
				dards used for cal red or purchased)		e origin of the s	standards, the s	standard		
Standar	d A _1	· 66 PH	<u> </u>							
	ช B <u></u> <u> </u>									
Standard C 16.46 PH										
DATE (yy/mm/dd)	TIME (hr:min)	STD (A, B, C)	STD VALUE	INSTRUMENT RESPONSE	% DEV	CALIBRATED (YES, NO)	TYPE (INIT, CONT)	SAMPLER SINITIALS		
0000420	1963	A	7.00	7.92>7\$€		YES	TUT	kie		
U	v	В	4.01	5.14 3		1	٠ ١	KR		
ε, .	u	C	100.00	14.04	6.04	رد	CONT	GR		
ι,	1647	A	7.00	7.03	6-63	4	ч	te.		
4	1222	B	4.01	4.09	0.08		৸	KO		
060421	1180	$\mathcal{C}$	10.00	10.04	0.04	l i	( <sub>1</sub>	40		
į, t	0905	A	7.05	7.05	0.05	ો	4	KR		
n	1034	R	4.01	4.04	0.03	el	પ્ય	KR		
				, 						
			l							
<b>}</b>	<del> </del>	<del> </del>		<del></del>						

Standar	d C							
DATE (yy/mm/dd)	TIME (hr.min)	STD (A, B, C)	STD VALUE	INSTRUMENT RESPONSE	% DEV	CALIBRATED (YES, NO)	TYRE (INIT, CONT)	SAMPLER INITIALS
\$6\$42\$	d943	A	1500 MS	15.40 W	NA	YES	TWIT	(de)
u	U	13	84. Øw	84.1 us	Ø.1	u	CONT	KR
Lr .	1000	A	15.44	1509	NB	ધ	cont	KR
v	1225	B	84.00	83.5	0.5	u	U C	ICR
060421	0812	A	15. 00mg	15.04	0.04	Ч	COUT	KR
( (	BABY	B	84.0	<b>୫</b> ଣି - ମ	0.02	٠,	પ	KR
٧١	1\$37	A	15.00d	1504	Ø. Ø +	11	(/	W.P.
						· ·		
		<u> </u>						
ļ								
		<u> </u>						
<u></u>								
	<b></b>							
-								
-								
ļ								
	-							
L	J	<u> </u>	L		l		1	



ITE AD SITE													
LOCATION: TEMP TAR M													
VELL NO:	<b>γγ</b> 17.33	)		SAMPLE	ID: MW		0 th/-		DATE: 2	\$ 11_ B	1.		
	·v				PURG	ING DA	TA		4	1 Tyn Y	y j		
VELIL Z		TUBING DIAMETER (in		DEPTH:	REEN INTER	9 feet	STATIC DE	R (feet): 8	PURGE PUMP OR BAILER:	TYPE APP	)		
	UME PURGE: if applicable) /	<b>.</b> .		,	= /		O WATER)	X WELL CAP	ACITY feet) X	na!	lons/loot =		
gallons	T VOLUME PUI	. biwe		2100	LINE + (DIB	<del>ļ</del>	8			. 6			
	if applicable)	NOL. TEQUIF	MICINI VOC		:UME + (106		TY X	TUBING LENG	1H) + FLOW CE feet) +		nallan.		
INSTIAL DIS	MP OR TUBING		FINAL PUMP			PURGIN		PURGIN		gailons =	gallons		
	WELL (feet):	12.24	DEPTH IN W	ELL (feet): '			ED AT: 113	ENDED		TOTAL VOLUM PURGED (galic			
TIME	VOLUME PURGED (gallons)	CUMUL. VOLUME PURGED (gallons)	PURGE RATE (gpm)	DEPTH TO WATER (feet)	pH (standard units)	TEMP.	COND. (µmhos/cm or µS/cm)	DISSOLVED OXYGEN (circle mg/L or % saturation)	TURBIDITY (NTUs)	COLOR (describe)	ODOR (describe)		
1 04	1.00	1.66		8.42	6.007	27.4	28 34	2.89	493	NA	NA		
147	2.25	1.25		8.42	5.91	27.3	145 us	_	400	NA	NA		
1150	.25	(.50		8-42	5.89	27-3	145 us	3.19	36	NA	WA		
1153	25	1,75		842	5.89	27,3	142 us	3. \$2	28	dito	art		
1154	.75	2.0		8.42	2.88	27.3	146 us	3.17/	23	NA	AW		
Anapli	<b>1</b>		<u> </u>		·	ļ			<del> </del> -				
<b>411440</b> 1159	.25	2.25	-	P. 188	6 67	27.3	19345	3.27	15	NA.	TACAP		
112				<u> </u>	4.4.4.1	6-1-5	1 1545		1	V IN	1011		
	PACITY (Gallon NSIDE DIA, CAP					6; 2" = 0.1 1/4" = 0.002					= 5.88 = 0.016		
		CEN MATON.		NADI EDIEN	SAMP	LING D	<b>ATA</b>						
SAMPLE	DBY (PRINT) / A	AFFILIA DON:	1	AMPLER(S) S	1ac	2.f	· · ·	SAMPLING INITIATED AT	SAMPLING ENDED ATIONS				
	RTUBING	124	S	NAME POWER	~	- Ch	<u> </u>	TUBING		1(/	10		
	N WELL (feet): ECONTAMINATI	ON: Y	) F	ELD-FILITER	- 11 / 1	FIL	TER SIZE:	MATERIAL CO	DUPLICATE:	Y (2)			
		CONTAINER	- ( T.	Itration Equip	<del></del>	APLE PRESE	RVATION		INTENDED	) SA	MPLING		
SAMPLE	EID #	IFICATION MATERIA	IL VOLUME	- 1	RVATIVE	TOTAL V	OL ]	FINAL	ANALYSIS ANI METHOD	D/OR EQ	UIPMENT CODE		
CODE	E CONTAIN	A 000	+.	HN	D <sub>2</sub>	DDED IN FIE		VG PH	5 9		P		
		N			>				9,1	5	·		
					·				·				
D. C.	DVC.					••			· .				
REMARKS: filtered sample													
MATER	RIAL CODES:	AG = Amb			ss;X_PE = F	Polyethylene;	PP = Poly	ypropylene; S =	Silicone; T=	Teflon; O = Oti	ner (Specify)		
,	LING/PURGING MENT CODES:		Peristaltic Purr erse Flow Peris			P = Bladder I raw Method (		SP = Electric Sub ty Drain); VT		PP = Perista O = Other (			
1	EQUIPMENT CODES: RFPP = Reverse Flow Peristaltic Pump; SM = Straw Method (Tubing Gravity Drain); VT = Vecuum Trap; O = Other (Specify)  NOTES: 1. The above do not constitute all of the information required by Chapter 62-160, F.A.C.												

2. STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3) pH:  $\pm$  0.2 units Temperature:  $\pm$  0.2 °C Specific Conductance:  $\pm$  5% Dissolved Oxygen: all readings  $\leq$  20% saturation (see Table FS 2200-2); optionally,  $\pm$  0.2 mg/L or  $\pm$  10% (whichever is greater) Turbidity: all readings  $\leq$  20 NTU; optionally  $\pm$  5 NTU or  $\pm$  10% (whichever is greater)



SITE NAME: /	Vorman	udx to	WK		1	OCATION:	Jan	110	FL		
WELL NO:	MW-Z			SAMPLE	ID: MU	1-2	04210	T	DATE: 4/	21/06	
						ING DA	TA		·		
WELL DIAMETER (	(inches): 7	TUBING DIAMETER (in	nches): /4		REEN INTER	VAL feet	STATIC DE	/ // \	PURGE PUMP OR BAILER:	YPE,	
	ME PURGE:	WELL VOLU	ME = (TOTAL	WELL DEP	TH - STA	TIC DEPTH	O WATER)		CITY		
gallons	f applicable)	7= WC		32=10		9,00	eei - 7 <u>-</u>	94	feet) X	Q ·	lons/loot =
	T VOLUME PUF if applicable) 🕝	RGE: 1 EQUIP	MEN1 VOL. =						H) + FLOW CEL	-	
ANTIAL DID	7	1570	TONAL DUMO		illons + (	<del></del> _	ons/foot X	<del>, :</del>	et) +	gallons =	gallons
DEPTH IN V	MP OR TUBING WELL (feet):	10	FINAL PUMP DEPTH IN WE	ELL (feet):	10	PURGIN	ED AT:	S PURGING ENDED A	1:1027	TOTAL VOLUM PURGED (gallo	ns): 3. 2.5
TIME	VOLUME PURGED (gallons)	CUMUL. VOLUME PURGED (gallons)	PURGE RATE (gpm)	DEPTH TO WATER (feet)	pH (standard units)	TEMP.	COND. (µmhas/cm or µS/cm)	DISSOLVED OXYGEN (circle mg/L or % saturation)	TURBIDITY (NTUs)	COLOR (describe)	ODOR (describe)
1084	.50	,50	.68	7.95	5.94	26-4	28/us	,74	2.4	No	NO
1007	. 25	.75	.08	8-02	5.77	26-7	276us	.37	4.8		
1010	. 25	1,00	.08	7-62	5.76	16.8	21505	. 28	14	7	Fes
1013	1,25	7.50	108	1.63	5.11	16-8	158. lu		23	20	
102)	1. 2		1/5	J. /X	5.11	11.8	87.145	1/6	33	MALCX	
10 14	,50	3.00	1/4	7-06	(7)	2/ 9	84505	,/6	35		
1017 San	In - 1	3-43	.08	1-41	2. /4	de	8/1/2145	.15	35		
1038		<del> </del>		7.66	C 74	24-9	855 Sus	0/5	35	mi/107	YES
10 <u>3</u>	<del>                                     </del>	<del>  •</del>		riude	2, 11	700	02743	مدر تا	37	pa1 1101	<i>y</i> = <u></u>
WELL CAL	PACITY (Gallons NSIDE DIA, CAF	s Per Foot): 0.			1.25" = 0.0	6; 2° = 0.1 1/4° = 0.00					= 5.88
TOBINGIA	13IDE DIA CAP	ACIT (GBIST)	. 1.0 - 0.00	, a 10		LING D		- 0.004, 378 -	0.000, 172 -	0.010; 5/8*	= 0.016
1	BY (PRINT) / A	FFILIATION:			IGNATURE	3:		SAMPLING	2-	SAMPLING	200
PUMP OR	RETUBING			MPLE PUMP	Henr	41		INITIATED AT:	<u>[ 250 </u>	ENDED AT:	038
DEFTHIN	WELL (feet):	10		OW RATE (n	nL per minute ED:		TER SIZE: /	MATERIAL COL	<del></del>	3	
FIELD DE	CONTAMINATIO	CONTAINER		tration Equip					DUPLICATE:	Y	<del>}</del>
SAMPLE	SPEC	IFICATION MATERIA	·	DRESER	SAX VATIVE	IPLE PRESE		FINAL	INTENDED ANALYSIS AND	OR EQ	MPLING JIPMENT
CODE			VOLUME	US		DDED IN FIE		pH	METHOD		CODE
	/	J PP	250m		ros	NA	=	<del>-3-+</del>	5b,16	A	PP_
<b> </b>				-	<u>-  </u>				L. Hered		
	<del></del>		<del></del>						<del></del>		
				-		. <del></del>					
				-				<del></del>	<del></del>		<del> </del>
-				_							
REMAR	KS:		. /.	L: 5	- Vo/		F,1	fered z	13.2	Tu	
MATER	IAL CODES:	AG = Amb				Polyethylene;			Silicone; T = Te	flon, D = Oth	er (Specify)
1	ING/PURGING MENT CODES:		Peristaltic Pump erse Flow Peris			sP = Bladder I traw Method (	Pump; E Tubing Gravit	SP = Electric Subr y Drain); VT :	nersible Pump; = Vacuum Trap;	PP = Perista O = Other (	
L	1. The above	do not cons	titute all of th	ne informa	ion require	ad by Chan	ter 62-160	FAC		<del></del> -	

2. Stabilization Criteria FOR Range OF Variation OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3) pH:  $\pm$  0.2 units Temperature:  $\pm$  0.2 °C Specific Conductance:  $\pm$  5% Dissolved Oxygen: all readings  $\leq$  20% saturation (see Table FS 2200-2); optionally,  $\pm$  0.2 mg/L or  $\pm$  10% (whichever is greater) Turbidity: all readings  $\leq$  20 NTU; optionally  $\pm$  5 NTU or  $\pm$  10% (whichever is greater)

ITE IAME: NO	CMAMD.	y PAR				ITE OCATION:	A CALL	DAT HOP	MPA FL	_	,
	MW 5			SAMPLE	ID: MU	5-042	\$ 604		DATE: U	bilan	Do
					PURG	ING DA	ÍΑ				
DAWE LEK (I	inches):	DIAMETER (in		DEPTH:	REEN INTER	5 feet	STATIC DE	(feei): 6.95	PURGE PUMP T OR BAILER:	YPE PERT	
only fill out if	applicable)		ME = (TOTAL / = .4.		TH - STA			X WELL CAF	feet) X		ilons/loot =
QUIPMENT	= 3.05 VOLUME PUR	RGE: 1 EQUIPM	MENT VOL =	PUMP VOL	• ,	• 474	TY X	TUBING LENG	TH) + FLOW CEL	L VOLUME	
only fill out if	applicable)		=	= ga	llons + (	gallo	ons/foot X		feet) +	gallons =	gallons
INITIAL PUN DEPTH IN W	IP OR TUBING /ELL (feel):		FINAL PUMP DEPTH IN W		16 ft	PURGIN INITIATE	G ED AT: \Ø	PURGIN ENDED	AT: 1623	TOTAL VOLUM PURGED (gallo	ME ons): 2.0
TIME	VOLUME PURGED (gallons)	CUMUL. VOLUME PURGED (gallons)	PURGE RATE (gpm)	DEPTH TO WATER (feet)	pH (standard units)	TEMP.	COND. (µmhos/cm or µS/cm)	DISSOLVED OXYGEN (circle mg/L o % saturation)	TURBIDITY (NTUs)	COLOR (describe)	ODOR (describe)
\$17	\$.5	ø.5	. \$3	7.00	6.06	24.3	271K		2.2	NA	NA
107p	0.5	1.4	,170	7-00	5.99	21.3	275W		11.7	NB	AN
ø23	Ø.5°	1.5	. (0	7.00	598	24.3	273us	1.38	1.6	NA	NA
mpli											
\$26	\$ 5	2.0	.120	7.00	5.86	14.3	2-15us	1.36	1.4	NA	WA
									<u> </u>	}	
WELL CAP	PACITY (Gallon: ISIDE DIA. CAP	Per Foot): 0.7 PACITY (Gal./FL	): 1/8" = 0.02; ): 1/8" = 0.00	1" = 0.04; 006; 3/16"	1.25" = 0.0 = 0.0014;		•			•	= 5.88 = 0.016
						LING DA	ATA				
SAMPLED	BY (PRINT) / A	FFILIATION:	He	MPLER(S) S	au Ra	Aon		SAMPLING INITIATED AT	: r\$26	SAMPLING ENDED AT:	(Ø2 <b>g</b>
		BAST	:\s7	MPLE PUMI OW RATE (r	$\gamma \sim \mathcal{V} \gamma$	e):		TUBING MATERIAL CO	DDE: PP		
1	CONTAMINATIO	//	\ F	ELD-FILTERI Itration Equip	D: Y		TER SIZE:	hw	DUPLICATE:	Y (N	$\overline{)}$
	SPECI	CONTAINER FICATION				IPLE PRESE			INTENDED ANALYSIS AND		MPLING UIPMENT
SAMPLE CODE			.VOLUME	PRESER US	ED A	TOTAL VI DDED IN FIE		FINAL pH	METHOD		CODE
		PP	2570m	1 HVX	3		- 2	2.ø	SE COM	<u> </u>	186
	<del>-   ·</del>										
				_		<del></del>				<del>-  </del>	
			1						· .		
REMAR	KS:	<del></del>	·.		· · · · · · · · · · · · · · · · · · ·		, ::-				
<del></del>	IAL CODES:	AG = Ambe	er Glass: CC		<del></del>	Polyethylene; SP = Bladder I			= Silicone; T = T	efion: O = Oil	ner (Specify)
EQUIPM	MENT CODES:		rse Row Peris	staltic Pump;	·		Tubing Gravit	<u> </u>	T = Vacuum Trap;	O = Other	(Specify)

2. STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3)

SITE NO	MAND	1 PAR	<u> </u>			SITE OCATION:	O. TF	MRE 7	pe a	L	
	Mw-7	, ,	_	SAMPLE	10: Mu)*	7A04	12/10	<u> </u>	DATE: 21	April 6	6
					PURC	SING DA	TA			- W-5-1-F	£
WELL 2 DIAMETER (I		TUBING DIAMETER (in		DEPTH:	REEN INTER	13 feet		R (feet): 7.00		PP	
only fill out if gallons	applicable)				= (	<b>f</b>	eet ~ .	X WELL CAP	PACITY feet) X	gal	lons/loot =
EQUIPMENT		RGE: 1 EQUIP						TUBING LENG	TH) + FLOW CE	L VOLUME	.17
		.522	うじく =	00 Pg	ailons + ( •	00\000	ons/foot X	16	feet)+	gallons =	gallons
DEPTH IN W	IP OR TUBING /ELL (feet):	16	FINAL PUMP DEPTH IN WI	ELL (feet):	16	PURGIN	ED ATT		AT0845	TOTAL VOLUM PURGED (gallo	
TIME	VOLUME PURGED (gallons)	CUMUL. VOLUME PURGED (gallons)	PURGE RATE (gpm)	DEPTH TO WATER (feet)	pH (standard units)	TEMP.	COND. (µmhos/cm or µS/cm)	DISSOLVED OXYGEN (circle mg/L o % saturation)	TURBIDITY r (NTUs)	COLOR (describe)	ODOR (describe)
1836	1.0	1.4	70.05	7.12	435	23.9	572us	3.44	Ø.85	NA	NA
Ø839	225	1.25	200	9.12	63	23.9	503vs	3.74	Ø 65		NA
2842	.25	1:5	Ø.08.	9.12	6.41	23 9	488 ùs	3.44	0.60	, NA	NA.
sample									<del></del>		
WORK -	25	175	100	9.12	6.42	53.9	494	3.48	0 d. 4d	ALA	NA
y copo	_, w	1113	4.40			,			Ψ. 17	04	
									<del></del>	·	
WELL CAF	PACITY (Gailon	s Per Foot): 0.	75" = 0.02;		1.25" = 0.0			- ,		6" = 1.47; 12"	= 5.88
TUBING IN	ISIDE DIA. CA	PACITY (Gal./FI	L): 1/8" = 0.00	006; 3/16	= 0.0014; SAME	1/4" = 0.00 PLING D		= 0.004; 3/8*	= 0.006; 1/2"	= 0.010; 5/8*	'=0.016
SAMPLED	BY (PRINT) / /	AFFILIATION:	SA	WPLER(S)	SIGNATURE			SAMPLING	9 1	SAMPLING	- (0
PUMP OR	TURING				PON		oc_	INITIATED AT	892	ENDED AT:	399
DEPTHIN	WELL (feet):	No'	( FL		ml per minu		TER SIZE:	MATERIAL CO	· · ·		· · · · · · · · · · · · · · · · · · ·
FIELD DE	CONTAMINATI	CONTAINER	) [Fil	ltration Equip					DUPLICATE:	Y (N	<i>)</i> .
SAMPLE	SPEC	IFICATION MATERIA			RVATIVE	MPLE PRESE TOTAL V	OL	FINAL	INTENDED ANALYSIS ANI METHOD	D/OR   EQ	MPLING UIPMENT CODE
CODE	CONTAIL	NERS CODE	<del></del>			ODED IN FIE	LD (mL)	рн 42	PG 51		<del>2</del> β
		11	230	W- tro	3				10, 21	e F	·
		<u> </u>									
								<del></del>			<del></del>
						<u></u> -		·		, 22	
<u> </u>				_					<u> </u>	رنهر مني -	
REMAR	KS:		<u>·</u>				7 ::-	<del></del> _	J	· · · · · · · · · · · · · · · · · · ·	
	_		<u>:</u>		· 			· · · · · · · · · · · · · · · · · · ·	·	<u>.</u>	<del></del>
	IAL CODES:	AG = Amb			<del></del>	Polyethylene;		<del></del>	= Sillcone; T=		ner (Specify)
EQUIP	ING/PURGING MENT CODES:	RFPP = Rev	Peristaltic Pum erse Flow Peris	staltic Pump;	SM = 9	BP = Bladder Straw Method	Tubing Gravit	ty Drain);	ibmersible Pump; T = Vacuum Trap;	PP = Perista O = Other	
NOTES:	1. The abov	e do not cons	titute all of t	he informa	ition requi	red by Chap	ter 62-160,	F.A.C.			

2. STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3) pH:  $\pm$  0.2 units Temperature:  $\pm$  0.2 °C Specific Conductance:  $\pm$  5% Dissolved Oxygen: all readings  $\leq$  20% saturation (see Table FS 2200-2); optionally,  $\pm$  0.2 mg/L or  $\pm$  10% (whichever is greater) Turbidity: all readings  $\leq$  20 NTU; optionally  $\pm$  5 NTU or  $\pm$  10% (whichever is greater)



SITE NAME: /	1/2/11	undy	Parl	 '/		SITE LOCATION:	-	MA.	C1		
	MW-/		1011	SAMPLE		1-10	043	2006	DATE: 4/	20/06	
	7 100 77	C/			PURC	SING DA		<u>ov</u>	7.1	10/6/4	
WELL DIAMETER	(inches)- 2	TUBING DIAMETER (in	nches):		REEN INTE	RVAL feet	STATIC DE	PTH 9.57	PURGE PUMP OR BAILER:	/ . ~	
WELL VOLU						TIC DEPTH		X WELL CAP			llons/loot =
EQUIPMEN	T VOLUME PUR	RGE: 1 EQUIP		= PUMP VOL	UME + (TUE	BING CAPAC	X YTI	TUBING LENG	TH) + FLOW CEL	LVOLUME	17
		.5ic 3				90 24 gall		15	(eet)+ , / 3	gallons =	gallons
DEPTH IN V	MP OR TUBING WELL (feet):	15		JP OR TUBINO WELL (feet):	15	PURGIN INITIAT	NG ED AT: 135	PURGING ENDED		TOTAL VOLUM PURGED (gallo	ns): /- 25
TIME	VOLUME PURGED (gallons)	CUMUL. VOLUME PURGED (gallons)	PURGE RATE (gpm)	DEPTH TO WATER (feet)	pH (standard units)	TEMP.	COND. (µmhos/cm or µS/cm)	DISSOLVED OXYGEN (circle mg/L or % saturation)	TURBIDITY (NTUs)	COLOR (describe)	ODOR (describe)
14c5	.50	.50	.68	9.66	C. 38	28.4	726us	.39	14	No	NO
1408	.25	.75	.08	19.6le	4.40	28.4	249us	. 43	8.4	٧ -	
1411	. 25	1.00	.08	7-66	4.44	28.4	254us	.44	5.7		
14/1	125	1.25	,08	7-64	4.48	28.4	257us	.40	3.8		
)a/	uple		ļ	917	1 25	20.11	2/1			ļ	
7917			<u> </u>	9.67	6.52	28.4	delus	. 3.9	3.5	No	NO
				1.			† <u>-</u>			<del></del>	
									,		
		s Per Foot): 0.7 PACITY (Gal./Ft			1.25" = 0.0 = 0.0014;						= 5.88 = 0.016
CANDICE	600000000	CTILATION	<del></del>	SAMPLER(S) S		LING D	ATA.				
SAMPLED	BY (PRINT) / A	FREATION:	) `	sampleds);	THE STATE	<b>5</b> .		SAMPLING INITIATED AT:	1417	SAMPLING ENDED AT:	1419
PUMP OR		15		SAMPLE PUM		e): 20,	8	TUBING	711/	` c	<u> </u>
	WELL (feel): CONTAMINATIO			FLCW RATE (r FIELD-FILTER	ED: Y	N) FIL	TER SIZE: _	MATERIAL CO	DUPLICATE:	Y (8	<del></del>
1100000		CONTAINER		Filtration Equip		ADI E DDECE	· ·		INTENDED		· · · · · · · · · · · · · · · · · · ·
SAMPLE	ID #	FICATION MATERIAL ERS CODE	L VOLÚM	AE PRESER	VATIVE	TOTAL V	OL	FINAL	ANALYSIS AND METHOD	VOR EQ	IMPLING UIPMENT CODE
CODE	CONTAIN	77	250 m		vo 3	- NA		J.	Sh Ph	A	PP
			<u> </u>								
						<del></del>					
						<del></del>			<del></del>		
REMAR	(S·								·		
, const			· · · · · · · · · · · · · · · · · · ·			·	, ,;,			<u> </u>	
<b></b>	AL CODES:	AG = Ambe		G = Clear Glas	<del></del>	<del></del>			Silicone: $T = T$		ner (Specify)
	NG/PURGING MENT CODES:	APP = After P RFPP = Rever				BP = Bladder F traw Method (	Pump; E Tubing Gravity	SP = Electric Sub y Drain);         VT	mersible Pump; = Vacuum Trap;	PP = Peristal O = Other (	
NOTES:	1. The above	do not consti	itute all of	the informa	tion requir	ed by Chap	ter 62-160, l	F.A.C.			

pH:  $\pm$  0.2 units Temperature:  $\pm$  0.2 °C Specific Conductance:  $\pm$  5% Dissolved Oxygen: all readings  $\leq$  20% saturation (see Table FS 2200-2); optionally,  $\pm$  0.2 mg/L or  $\pm$  10% (whichever is greater) Turbidity: all readings  $\leq$  20 NTU; optionally  $\pm$  5 NTU or  $\pm$  10% (whichever is greater)

<sup>2.</sup> STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3)



NAME: NOVMAY	ide Park			SITE LOCATION:	Tour	414	EL.		
NELL NO: MW-11			SAMPLE ID: MU		7200	1/2-	DATE: 4/	20/16	
				GING DA		,		7-10-	
DIAMETER (inches):	TUBING DIAMETER (inches):	190	VELL SCREEN INTI DEPTH: leet to	// leet	STATIC DE	(feet): (n. 20	PURGE PUMP OR BAILER:	PYPE .	
WELL VOLUME PURGE: 1 only fill out if applicable) gallons	WELL VOLUME =	(TOTAL WE	ELL DEPTH - ST = (	ATIC DEPTH 1	O WATER) eet -	X WELL CAP	ACITY feet) X	7	lions/loot =
EQUIPMENT VOLUME PUR (only fill out if applicable)							TH) + FLOW CEL	_	.16e
			oo 24 gallons + (			<del></del>	feet) + / 3		gallons
INITIAL PUMP OR TUBING DEPTH IN WELL (feet):	13 DEPT	PUMP OR	B 7	PURGIN	G ED AT: 1/3	PURGIN ENDED	AT: 1153	TOTAL VOLUM PURGED (gallo	ns)/. 25
TIME VOLUME PURGED (gallons)	PURGED RA	RGE W	TO pH (Standard (feet) units)	TEMP.	COND. (µmhos/cm or µS/cm)	DISSOLVED OXYGEN (circle mg/L or % saturation)	TURBIDITY (NTUs)	COLOR (describe)	ODOR (describe)
1144 .50			0.33 6.23	25.4	249 us	1.41	[]	NO	~0
1147 . 25		~/	· 33 ( - 21	15.3	237us	1-25	5.7		~-
1150 . 25			0.33 6.28	25.3	234us	1.19	3.5		· -
Sample	1. 23	80 10	123 4.40	0,5	24/4	1.01	1 A-CP	<del> </del>	
1154		/0	0.33 6.20	25.3	236us	1.10	1.4	10	NO
				<u> </u>				<del> </del>	
			<del></del>				<del>                                     </del>	-	
WELL CAPACITY (Gallons TUBING INSIDE DIA, CAP						37; 4" = 0.65;			= 5.88
TOBING INSIDE DIA. CAP	ACITI (GBIJEL). III		SAM	PLING DA		= 0.004; 3/8=	= 0.006; 1/2" :	= 0.010; 5/8**	= 0.016
SAMPLED BY (PRINT) / A	FFILIATION:	SAMP	LER(S) SIGNATUR	<b>\</b>		SAMPLING INITIATED AT:	. ای از	SAMPLING ENDED AT:	17.00
PUMP OR TUBING	17		LE PUMP		<del>\</del>	TUBING		- C	1,00
DEPTH IN WELL (feet): FIELD DECONTAMINATION	ON: 'Y	FIELD	RATE (mL per mini	FIL	O TER SIZE::	MATERIAL CC	DUPLICATE:	× 6	<u> </u>
SAMPLE	CONTAINER	Filtrage	on Equipment Type:	MPLE PRESE	RVATION		INTENDED		MPEING
SAMPLEID # CODE CONTAIN	FICATION  MATERIAL  ERS CODE V	OLÚME	PRESERVATIVE USED	TOTAL VI ADDED IN FIE		FINAL pH	ANALYSIS AND METHOD	VOR   EQI	DIPMENT CODE
7		SOML	HN03	·NA		2	Sb. Pb	AP	P .
								·	
		<u> </u>					<del></del>		
				·					
			<del></del>				<del></del>		
REMARKS:					1 (1)				
MATERIAL CODES:	AG = Amber Glas		Clear Glass PE :	= Polyethylene; BP = Bladder i		propylene: S = SP = Electric Sul	Silicone; T=To		er (Specify)
SAMPLING/PURGING EQUIPMENT CODES: NOTES: 1. The above	APP = After Perista RFPP = Reverse Fl	w Peristalii	c Pump; SM =	Straw Method (	Tubing Gravit	y Drain); Vi	= Vacuum Trap;	PP = Peristal O = Other (	

2. STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3) pH:  $\pm$  0.2 units Temperature:  $\pm$  0.2 °C Specific Conductance:  $\pm$  5% Dissolved Oxygen: all readings  $\leq$  20% saturation (see Table FS 2200-2); optionally,  $\pm$  0.2 mg/L or  $\pm$  10% (whichever is greater) Turbidity: all readings  $\leq$  20 NTU; optionally  $\pm$  5 NTU or  $\pm$  10% (whichever is greater)

SITE NAME:	19	news	vou F	NL		1	SITE OCATION:	TP	5MP 77	V.		
MEFF W	O:	MW12	َ ا د		SAMPLE	1D: M	D120	210	ر ما	DATE: 11	SAFE DE	
						PURC	SING DA	TA			16-10	
WELL DIAMET			TUBING DIAMETER (i		DEPTH:		<b>1 Ø</b> feet	STATIC DE	PTH R (feet): 1 8	PURGE PUMP OR BAILER:	TYPEO	
only fill	out if	ME PURGE:	1 WELL VOLU	IME = (TOTAL	WELL DEP	TH - STA	TIĆ DEPTH 1	O WATER) leet –	X WELL CAP	ACITY feet) X	16 ga	llons/loot =
EQUIPN	MENT	VOLUME PUI	RGE: 1 EQUIP	MENT VOL	PUMP VOL	UME + (TUE	ING CAPAC	X YT	TUBING LENG	TH) + FLOW CE		
(only fill	Out if	applicable)		=	= ga	allons + (	galio	ons/foot X	i	eet) +	gallons =	gallons
		P OR TUBING	3/	FINAL PUMP DEPTH IN W		131	PURGIN	IG ED AT	PURGING ENDED		TOTAL VOLUM PURGED (galic	ME ons (2) + # #
TIME		VOLUME PURGED (gallons)	CUMUL. VOLUME PURGED (gallons)	PURGE RATE (gpm)	DEPTH TO WATER (feet)	pH (standard units)	TEMP.	COND. (µmhos/cm or µS/cm)	DISSOLVED OXYGEN (circle mg/L or % saturation)	TURBIDITY (NTUs)		ODOR (describe)
1/1	2	1.5	1.5	\$. d	11.08	5.40	25.2	4880	,24	Ø	NA	NA
(Pl	5	.25	1.75	O B	11.98	5.43	25.2	487us	26	Ø	NA	NA
141	8	.25	2.00	6.60	11.98	5.44	25.2	489 us	.3'7	7	NA	CV Q
			-	V-00								
BAN	Pl			110	1.00					<u> </u>		
102	4	.25	2.15	P.D.O	N.98	6.49	25.2	489u	127	JØ_	NA	WA
					·					1		
WELL	CAD	ACITY (Gallon	s Per Font): N	75" = 0.02	1" = 0.04;	1.25" = 0.0	6; 2" = 0.1	6; 3" = 0.3	37; 4" = 0.65;	5" = 1.02;	6" = 1.47; 12"	'= 5.88
TUBIN	IG IN	SIDE DIA. CAL	PACITY (Gal./F	L): 1/8" = 0.0		= 0.0014;	1/4" = 0.002 LING D	26; 5/16"			•	= 0.016
SAMP	LED	BY (PRINT) / A	FFILIATION:	SA	MPLER(S)	IGNATURE:		^	SAMPLING		SAMPLING	
		TUBING	.2/			en se	TO CE	9(	INITIATED AT: TUBING	IPE!	ENDED AT:	1828
		WELL (feet): CONTAMINATI	ON: Y AN	FI	OW RATE ( ELD-FILTER Itration Equip		FIL	TER SIZE: _	MATERIAL CO	DE: 80 DUPLICATE:	Y (N	<u> </u>
			CONTAINER	. (1)	najen cyu)		APLE PRESE	RVATION		INTENDED	s <sub>A</sub>	MPLING
	APLE )		MATERL IERS CODE	VOLUME		RVATIVE ED A	TOTAL VI DDED IN FIE		FINAL pH	ANALYSIS AND METHOD		UIPMENT CODE
			PP	257	4 10	03			2	& B	A	P
-			<del>-  </del>		<del> </del>							
-		<del></del>	-	-			·					
-					-					·		
REA	MARK	is:		l	<u>l</u>	<u>_</u>	<del></del> -	, ,;,		<del> </del>	L <sub>-</sub>	
MA	TERL	AL CODES:	AG = Amb	er Glass; CC	S = Clear Gla	ssyd_PE = F	Polyethylene;	PP ≈ Poly	propylene; S =	Silicone: T = T	eflon; O = Oth	ner (Specify)
		NG/PURGING ENT CODES:		Peristallic Pum erse Flow Peris			P = Bladder F raw Method (	Pump; E Tubing Gravit	SP = Electric Sub y Drain); VT	mersible Pump; = Vacuum Trap;	PP = Perista O = Other (	

2. STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3)

pH:  $\pm$  0.2 units Temperature:  $\pm$  0.2 °C Specific Conductance:  $\pm$  5% Dissolved Oxygen: all readings  $\leq$  20% saturation (see Table FS 2200-2); optionally,  $\pm$  0.2 mg/L or  $\pm$  10% (whichever is greater) Turbidity: all readings  $\leq$  20 NTU; optionally  $\pm$  5 NTU or  $\pm$  10% (whichever is greater)

NAME: N	orma	nils	r fi	ark	-			SITE LOCATION:	Ta	m	10-	FL.		,	
WELL NO:						SAMPLE	ندر اسر <sup>:ID</sup>		9421	06		DATE:	4/21	/2/1	
	7		· · · · - <u> · ·</u>					SING DA		01		1	1101	04	
WELL DIAMETER (		TUBII	ETER (in	iches):	14	DEPTH: /	SEEN INTE	/ Difeet	STATIC TO WA	TER (fe	eet)/ 88	PURGE PUI OR BAILER			
only fill out if		1 WEL	r vorni	ME = (TC	TAL V	WELL DEP	= {	TIC DEPTH	TO WATE leet –	(R) X	WELL CAPA	feet) X	16	ga	e sooftanoil
EQUIPMENT (only fill out if							UME + (TÚI	BING CAPAC		TI	UBING LENGT	H) + FLOW	CELL VO	LUME	16
		<u>_</u>	-/-					oc 24 galls			<del></del>			gallons =	gallons
DEPTH IN W	MP OR TUBIN VELL (feet):	15		DEPTH II			13	PURGIN	IG ED AT	855		r:0%	7 TOT.	AL VOLUA GED (galle	ons); /. OO
TIME	VOLUME PURGED (gallons)	VOI PUI	MUL. LUME RGED Illons)	PURGI RATE (gpm)	1	DEPTH TO WATER (feet)	pH (standard units)	TEMP.	CONE (µmhosk or µS/cr	cm (	DISSOLVED OXYGEN circle mg/L or % saturation)	TURBID (NTUs	' '	COLOR describe)	ODOR (describe)
0%/	<u> </u>		.50	, 0		7.70	5.98	27-3	308m	_	.42	9.6	,	Tan	NO
0707 0907	.75 :25		:/5 (coc	.08		771	5-16 5-90	27.5	3040 303		37 33	5.7	7		
50 1	uPle	1		.00	<del>-   •</del>		1.17	167-3	2000	43		1 2.7			
2860						7-74	6.00	27.5	3000	ای	,33	5- 5	/ -	Ton	NO
					_			-	<u> </u>	-		ļ		·	
	<u>-</u>		<del></del>	-	$\dashv$			<del> </del>		+	<del></del>	ļ		·	
				<del>                                     </del>	$\dashv$		<del></del>	<del>                                     </del>	<u> </u>	_		<del> </del> -	_	<del>- ·</del> -	
WELL CAP TUBING IN	PACITY (Gallo ISIDE DIA, C	ons Per F	oot): 0.7 (Gal./Ft	75" = 0.02 .): 1/8" =	; 1 0.000		1.25" = 0.0 = 0.0014;	$2^{2} = 0.1$ $1/4^{2} = 0.00$		= 0.37; 16 = 0		5" = 1.02; 0.006;	6" = 1 1/2" = 0.01		" = 5.88 " = 0.016
CANAGE	DV (DDI) PO	. CO. 11	TON		CAL	ומו דמופי מ	SAM!	PLING DA	ATA				<del></del>		
QO	BY (PRINT) /	AFFILIA	. I ION.			3. M	L /	•		S	AMPLING NITIATED AT:	0910	SAI	MPLING DED AT:	09/3
PUMP OR	<del></del>		13			(PLE PUMP W RATE (n			8	<b>₹</b>	UBING MATERIAL COL	<del></del>	7.5		
	CONTAMINA	TION: "	Y (F)	)	FIEL	D-FILTERI			TER SIZE		m	DUPLICATE	Y		<b>5</b> · ·
		E CONT.					SA	MPLE PRESE	RVATION	ı		INTEN			AMPLING NUIPMENT
SAMPLE I CODE			MATERIA CODE	.VOL		บร	NATIVE ED 4	TOTAL V DDED IN FIE		· F	FINAL pH	METH			CODE
		/	PP	250	OML	H	NO3	NA			2	56,14	p	A	PP
			<del></del>			<del> </del>						<del></del>		<del> </del>	
	<del></del>					<del> </del>						<del></del>	<del></del>	<del> </del>	
	-														
						-									
REMARK	(5.		l			<u> </u>	l		<u> </u>			·		1	
I IVENIALO	<b></b> .								# 21*						
}	AL CODES:		3 = Ambe					Polyethylene;					T = Teflon;		ther (Specify)
EQUIPM	NG/PURGING	: RFP	P = Reve	enstaltic F	ensta	itic Pump;	SM = 5	BP = Bladder   Straw Method (	Tubing G	гаvi <b>ty</b> D		= Vacuum T		P = Perista O = Other	
NOTES:	<ol> <li>Ine abov</li> </ol>	re do no	ot const	itute all	of the	e informa	ion requi	red by Chap	ter 62-1	6U, F.A	۹.6.				

2. STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3) pH:  $\pm$  0.2 units Temperature:  $\pm$  0.2 °C Specific Conductance:  $\pm$  5% Dissolved Oxygen: all readings  $\leq$  20% saturation (see Table FS 2200-2); optionally,  $\pm$  0.2 mg/L or  $\pm$  10% (whichever is greater) Turbidity: all readings  $\leq$  20 NTU; optionally  $\pm$  5 NTU or  $\pm$  10% (whichever is greater)



SITE NAME: 1	101 man	1	Par K			ITE OCATION:		(4A)	F1		
WELL NO: M			ou p	SAMPLE			1 11	mpa	DATE: 4/	1.	
7	$\mathcal{U}$ $\mathcal{U}^{s}$	74 - 1			PURC	ニ <u>ルンナ</u> ING DA	7 092 TA	och	7/2	elol_	
WELL.		TUBING	1/11	WELL SCI	REEN INTER	RVAL	STATIC DE	PTH A -	PURGE PUMPA	YPE	·
DIAMETER (inc		DIAMETER (ii		DEPTH:	feet to	(Le feet	TO WATER	(feet): 7-	OR BAILER: 🆊		
well volum only fill out if a gallons		I WELL VOLU	ME= (101AL	. WELL DEP	1H - STAT = (		O WATER) eet –	X WELL CAPA	feet) X	J	llons/loot =
EQUIPMENT V (only fill out if a					•		TY X	TUBING LENGT	H) + FLOW CEL	L VOLUME	.18
	4	56= 3 E			llons + ( p)		ons/foot X	<u> </u>	eet)+ , / 3		gallons
DEPTH IN WE		CUMUL.	FINAL PUMP DEPTH IN W		21	PURGIN	D AT: 14	PURGING ENDED A DISSOLVED	T: 1455	TOTAL VOLUM PURGED (galk	ons): 125
	VOLUME PURGED (gallons)	VOLUME PURGED (gallons)	PURGE RATE (gpm)	TO WATER (feet)	pH (standard units)	TEMP. (°C)	COND. (µmhos/cm or µS/cm)	OXYGEN (circle mg/L or % saturation)	TURBIDITY (NTUs)	COLOR (describe)	ODOR (describe)
149	75	.75	.09	10.86	3.70	27.6	439us	23	.15	NO	NO
1452	.25	1.00	.08	10.91	3.71	27.8	43/ins	. 21	.10		·
14.55	.25	1.25	.08	10.92	3.73	27.7	43545	3/9	-10		7
	mple			- A.	7 7	~				ļ	
1458			-	10.91	3.75	27-8	434 us	.19	.15	100	20
					·				ļ		
				-				· <del> </del>	ļ		
			<del> </del>		·			! 	ļ <u>.</u>	<del> </del>	
						{			<del> </del>	<del> </del>	
WELL CAPAI	CITY / Gallons	Per Foot) 1	75" = 0.02;	4" = 0.04".	1.25" = 0.0	6; 2" = 0.1	6; 3" = 0.3	37; 4" = 0.65;	5" = 1.02; 6	5" = 1.47; 12'	° = 5.88
TUBING INSI	DE DIA. CAP	ACITY (Gal./F	L): 1/8" = 0.00	006; 3/16	= 0.0014;	1/4" = 0.002	6; 5/16			•	= 0.016
SAMPLED BY	Y (PRINT) / AI	FEILIATION:	I SA	MPLER(S) S	SAMP	LING DA	AJA.				
•	ORE			13.M	7/ 1			SAMPLING INITIATED AT:	1458	SAMPLING ENDED AT:	1501
PUMP OR TI	UBING	21-		MPLE PUMP			08	TUBING MATERIAL COI			. :
DEPTH IN W	ONTAMINATIC	ON: Y N	) . FI	D-FILTER	D: Y (	Z	ER SIZE:	. 1100	DUPLICATE.	Y (N	3
11225 5250		CONTAINER	Fil	tration Equip		IPLE PRESE	PIVATION.	<del></del>		—,— <u> </u>	
SAMPLEID	SPECIF	FICATION MATERIA	W. T	PRESER		TOTAL V		FINAL	ANALYSIS AND	!	MPLING UIPMENT
CODE	CONTAINE	RS CODE	.VOLUME	US	ED AI	DDED IN FIE	D (mL)	pΗ	METHOD		CODE
<u></u>		PP	250 m	1	No3	·NA	<u> </u>		56,16	A	PP
	<del></del>	<del></del> -	-	· .					<del></del>		
	+		<del></del>						<u>.                                    </u>		
	<del></del>		<del></del>	_		···					
							· -				<del></del>
									<del></del>		
REMARKS:	<u> </u>						<u></u>		·		
INDIVITION.	•						, :\-	•			
MATERIAL	CODES:	AG = Ambe	er Glass; CG	= Clear Glas	Syd—PE = F	olyethylene;	PP = Poly	propylene, S =	Silicone; T = To	eflon; O = Ot	ner (Specify)
	SPURGING		Peristaltic Pum		•	P = Bladder F		SP = Electric Sub		PP = Perista	
L	NT CODES:		erse Flow Peris		<del> </del>	<del></del>	Tubing Gravit		= Vacuum Trap;	O = Other	(Specify)

<sup>2.</sup> STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3)



SITE	11		1.	7)	10			SITE			~ /		
NAME:			andy	Porr	10-			LOCATION:	for	1per	FL	<del></del>	
WELL NO	MU	<u>1-05</u>	A-2			SAMPLE	ID: Mu	: DSA	-20	1200 li	DATE: Y	20/04	
					<b>γ</b>			GING DA	<del></del>	·			
WELL DIAMETE			TUBING DIAMETER (ii	•	91	DEPTH:		18 feet		R (feet): <b>ا</b> ن کر 🗗	OR BAILER:	er.	
WELL VO only fill or gallons			1 WELL VOLU	ME= (TO	TAL V	VELL DEP	TĤ - ST. = (		TO WATER) feet –	X WELL CAP	ACITY feet) X	· 9:	allons/foot =
EQUIPME (only fill or			RGE: 1 EQUIP	MENT VO	L = P √	O P ga	UME + (TU	BING CAPAC	ITY X ons/foot X	2-	TH) + FLOW CEL	L VOLUME  3 gallons =	. 19. gallons
INITIAL P			23	FINAL PL		R TUBING	73	PURGII	NG ED AT: 12	36 PURGIN	3 AT / 2 (1)	TOTAL VOLU PURGED (gal	
TIME	VOI PUI	LUME RGED	CUMUL VOLUME PURGED	PURGE RATE		DEPTH TO WATER	pH (standard units)	TEMP	COND. (µmhas/cm or µS/cm)	DISSOLVED OXYGEN (circle mg/L or	TURBIDITY	COLOR (describe)	ODOR (describe)
1245	(ge	75	(gallons) . 75	(gpm)	~ -	(feet) 3.18	3.96	25.3	277us	% saturation)	.70	Tan	NO
1248		, 75	1.00	.0	8 1	3.67	3.96	25.3	273us	.20	. 70		
1251	ni ,	25	1.25	, 01		3-89	3.97	25.4	274 vs	. 22	/4/		
Salu	Me			ļ	-∤-,		= 00	0 = 11	2	22		<del></del>	<del> </del>
1254			·	<del> </del>	/	4.14	3.99	25.4	275us	.73	,35	Ton	200
	+			<u> </u>	+						<del> </del>	<del> </del>	
	<u> </u>												
				7									
			s Per Foot): 0. PACITY (Gal./F				1.25" = 0. = 0.0014;			37; 4" = 0.65; = 0.004; 3/8"			2" = 5.88 3" = 0.016
						D. ED/01.0		PLING D	ATA	r	·	<del></del>	· 
	ED BY (F	· '	FFILIATION:				Hen	•	,	SAMPLING INITIATED AT:	1254	SAMPLING ENDED AT:	1258
PUMP (	OR TUBII	NG T	23		SAM	PLE PUM		26	)	TUBING MATERIAL CO	-	5	.,
		AMINATIO	ON: Y	> 1	FIEL	D-FILTER			TER SIZE: _	µm	DUPLICATE:	(C)	<b>J</b>
1.			CONTAINER				SA	MPLE PRESE	RVATION		INTENDED	. 1	AMPLING
SAMP		# CONTAIN	MATERU		IME	PRESER	VATIVE ED	TOTAL V ADDED IN FIE		FINAL pH	ANALYSIS AND METHOD	VOR   E	CODE
		Z	PP	250	mL	HA	103	-NF	-	×	ShiPb	1	PP
						·		<u> </u>			<u> </u>		
		·											
						<u> </u>					<del></del>		·
		<u> </u>			·					·	· <del></del>		
		<u> </u>				<u> </u>		<u> </u>					
REMA	.RKS:			1),./	je.	-/	her	e	1 250				
MATE	RIAL CO	DDES:	AG = Amb	er Glass,	CG =	Clear Glas	-//	Polyethylene:	PP = Pol	ypropylene; S =	Silicone: T = T	efion; O ≈ O	ther (Specify)
		URGING CODES:	APP = After				Bailer, SM = :	BP = Bladder Straw Method		SP = Electric Sul ty Drain); V1	omersible Pump; = Vacuum Trap;	PP = Perist O = Other	
			do not cons	tituto all c	F the	informa	tion requi	rad by Char	tor 62-160	FAC	<del></del>		<del></del> -

5: 1. The above do not constitute all of the information required by Chapter 62-160, F.A.C.

pH:  $\pm$  0.2 units Temperature:  $\pm$  0.2 °C Specific Conductance:  $\pm$  5% Dissolved Oxygen: all readings  $\leq$  20% saturation (see Table FS 2200-2); optionally,  $\pm$  0.2 mg/L or  $\pm$  10% (whichever is greater) Turbidity: all readings  $\leq$  20 NTU; optionally  $\pm$  5 NTU or  $\pm$  10% (whichever is greater)

<sup>2.</sup> STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3)



SITE NAME: /	Varmon	ndx 1	park		1	SITE LOCATION:	Town	noa	FL.		
	Mw-8			SAMPLE	ID: MU	v-8	24210	,6.	DATE: 4	121/06	•
					PURC	SING DA	ATA .			<u> </u>	
WELL DIAMETER	(inches): 2	TUBING DIAMETER (in	cheel 4	WELL SC	REEN INTE	RYAL feet	STATIC DE	PTH 9.07	PURGE PUMP OR BAILER:		
					TH - STA	TIC DEPTH	O WATER)	X WELL CAP	ACITY	£1/	
only fill out it	JME PURGE: f applicable)	92 we	. 78	EIVO		7. ec		.07	feet) - X	ر م	gallons/loot =
EQUIPMENT  (only fill out i	T VOLUME PUP	RGE: 1 EQUIPI	MENT VOL. =	PUMP VOL	UME + (TUE	BING CAPAC	TY X	TUBING LENG	TH) + FLOW CEL	LVOLUME	
				ga	illons + (	gallo	ons/foot X		feet) +	gallons :	= gallons
DEPTH IN V	MP OR TUBING WELL (feet):	12	FINAL PUMP DEPTH IN WI	ELL (feet):	12	PURGIN	IG ED AT: 07	YS PURGING ENDED	T:0887	TOTAL VOLU PURGED (ga	JME allons): 2, eco
TIME	VOLUME PURGED (gallons)	CUMUL. VOLUME PURGED (gallons)	PURGE RATE (gpm)	DEPTH TO WATER (feet)	pH (standard units)	TEMP.	COND. (µmhos/cm or µS/cm)	DISSOLVED OXYGEN (circle mg/L or % saturation)	TURBIDITY (NTUs)	COLOR (describe	
0757	1.00	1.00	.08	9.15	5.71	25.7	220 us	1.97	3.9	NO	0.0
0800	.25	1.25	.08	9.15	5.72	25.8	21745	2.12	3.7		۰
0803	- 25	1.50	.08	7.15	5.76	25-8	210 us	2-32	3.0		
0806	. 25	1.75	.08	9.15	5.82	25.8	208us	2.48	2.9		
0809	. 75	2.00	-08	9.15	5.82	25.8	203us	2.50	2.4		
Sar	rfle			<u> </u>	-	- 0/	-	0			
0812	<u> </u>			9-15	5.88	25.8	203us	2-54.	1.7	no	NO
						ļ			ļ	<u> </u>	
		 	<u> </u>			ļ			<del> </del>	ļ	
WELL CAR	PACITY (Collons	Per Foot): 0.7	'5" = 0.02:	t" = 0 04.	1.25" = 0.0	06; 2" = 0.1	16; 3" = 0.3	37; 4" = 0.65;	5" = 1.02; 6	5" = 1.47; 1	2" = 5.88
TUBING IN	ISIDE DIA. CAP	ACITY (Gal./Ft.	): 1/8" = 0.00		= 0.0014;	1/4" = 0.002	26; <b>5/16</b>				78" = 0.016
SAMPLED	BY (PRINT) / A	FFILIATION:	SA	MPLER(S) S	SAMI	PLING DA	AIA			<del></del>	<del></del>
۱ 🗻	RE		1	3. M	Hem	10		SAMPLING INITIATED AT:	0812	SAMPLING ENDED AT:	0814
PUMP OR		1.	_ / J SA	MPLEPUMI	nL per minut	~ (	3	TUBING MATERIAL CO	DE: 7 S	•	
	CONTAMINATIO	ON: 'Y	FIE	LD-FILTER	ED: Y	Z/A3	TER SIZE: _	hu	DUPLICATE:	Y (	
		CONTAINER		Toton Equip		MPLE PRESE	RVATION	<del></del> -	INTENDED		SAMPLING
SAMPLE	ID #	FICATION MATERIAL	VOLUME		WATIVE	TOTAL V		FINAL	ANALYSIS AND METHOD	VOR E	QUIPMENT CODE
CODE	CONTAIN	ERS CODE	250mL	US	103	DDED IN FIE		DH DH	86 06	A	PP
			1.32 ///-	1.72	-0-		<u> </u>		00/10		
						<del></del>					
	_		1			•					
<u> </u>										_	<del></del>
REMARK	S:				, .		y 25+				_
MATERI	AL CODES:	AG = Ambe	r Glass; CG	= Clear Glas	PE =	Polyethylene;	PP = Poly	propylene; S =	Silicone; T = T	eflon; O = (	Other (Specify)
	NG/PURGING SENT CODES:	APP = After P RFPP = Rever	eristaltic Pump se Flow Perist			BP = Bladder I traw Method (		SP = Electric Sub y Drain); V1	omersible Pump; = Vacuum Trap;		staltic Pump er (Specify)
NOTES	1 The shave	do not consti	tuto all of th	a informa	ion requir	ed by Chan	tor 62-160	FAC			<del></del>

The above do not constitute all of the information required by Chapter 62-160, P.A.C.
 Stabilization Criteria for range of variation of Last three consecutive readings (SEE FS 2212, SECTION 3)

pH: ± 0.2 units Temperature: ± 0.2 °C Specific Conductance: ± 5% Dissolved Oxygen: all readings ≤ 20% saturation (see Table FS 2200-2); optionally, ± 0.2 mg/L or ± 10% (whichever is greater) Turbidity: all readings ≤ 20 NTU; optionally ± 5 NTU or ± 10% (whichever is greater)




SITE NOT mandy POUTK	SITE	Toupler	FL.	
WELL NO: PZ-1	SAMPLE ID: P Z- /	042004	DATE: 6	20/04
	PURGING D	<del></del>		0704
WELL 7 TUBING 5	WELL SCREEN INTERVAL	STATIC DEPTH SU &	PURGE PUMP TY	PE I Las
DIAMETER (inches): / DIAMETER (inches): / WELL VOLUME PURGE: 1 WELL VOLUME = (To		HTO WATER) X WELL CA	PACITY	1444703
only fill out if applicable) gallons	= ( //0	feet -	feet) X	gallons/loot =
EQUIPMENT VOLUME PURGE: 1 EQUIPMENT V	DL = PUMP VOLUME + (TUBING CAP)	CITY X TUBING LENG	GTH) + FLOW CELL	VOLUME . 39
(only fill out if applicable)	= oo xle gallons + ( oo xle g	allons/foot X /60	feet)+ , / 3	gallons = gallons
	UMP OR TUBING / PURI IN WELL (feet): /OO INITI.	PURGING PURGINATED AT: / CC C ENDED	NG AT: 1014 P	OTAL VOLUME 3, 75
CUMUL.   VOLUME   PURC	DEPTH	COND DISSOLVED	TURBIDITY	COLOR ODOR
TIME PURGED PURGED RAT (gallons) (gallons) (gpm	E WATER (Standard (°C)	(µmhos/cm) (circle mg/L comps/cm) % saturation	or (NTUs)	(describe) (describe)
1008 1-25 1-25 6	2 55-32 7-20 26.	7 183.945 1.17	2-5	Tan No
1011 1.25 2.50 4	1 95.31 7-25 alc.	9/8/40s 196	2./	
1014 1.25 3.75 -4	1 55.33 7.28 24.	1 182.40s , 90	7-1	
Sauple				
1017	55.40 7-38 26.5	1/83 ous .40	7.9	Tan NO
			_	
		<u> </u>		
		_	_	
		<del>-   -</del>		<del></del>
WELL CAPACITY (Gallons Per Foot): 0.75" = 0.0	2° 1° = 0.04° 1.25° = 0.06° 2° =	0.16; 3" = 0.37; 4" = 0.65	5; 5° = 1.02; 6°	= 1.47; 12" = 5.88
TUBING INSIDE DIA. CAPACITY (Gal/FL): 1/8"	$= 0.0006;$ $3/16^{\circ} = 0.0014;$ $1/4^{\circ} = 0.0014;$	0026; 5/16" = 0.004; 3/8	= 0.006; 1/2" = (	
SAMPLED BY (PRINT) / AFFILIATION:	SAMPLING SAMPLER(S) SIGNATURES:		· · ·	
OARE	B. M. Win	SAMPLING INITIATED AT	r: 1017	SAMPLING ENDED AT: 16/7
PUMP OR TUBING DEPTH IN WELL (feet): /00	SAMPLE PUMP FLOW RATE (mL per minute):	TUBING MATERIAL C	DF	,,,,
FIELD DECONTAMINATION:   N	FIELD-FILTERED: Y	ILTER SIZE: µm	DUPLICATE:	Y (N)
SAMPLE CONTAINER	Filtration Equipment Type:	SERVATION	INTENDED	SAMPLING
SPECIFICATION  SAMPLE ID # MATERIAL VOI	PRESERVATIVE TOTAL	VOL FINAL	ANALYSIS AND/C	
CODE CONTAINERS CODE	OSED ADDED IN		0. 11	RCD
1 17 00	oml 4NO3 N	7	01,00	[V)
			<del> </del>	
			<del>                                     </del>	
			· ·	
REMARKS:		.1 :25		
MATERIAL CODES: AG = Amber Glass;	CG = Clear Glass PE = Polyethyle	ne; PP = Polypropylene; S	= Sillcone; T = Teff	lon; O = Other (Specify)
SAMPLING/PURGING APP = After Peristaltic	: Pump; B = Bailer, BP = Bladd	er Pump; ESP = Electric S	ubmersible Pump;	PP = Peristaltic Pump
EQUIPMENT CODES: RFPP = Reverse Flow	Peristaltic Pump; SM = Straw Metho	<u> </u>	/T = Vacuum Trap;	O = Other (Specify)

2. STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3)

pH:  $\pm$  0.2 units Temperature:  $\pm$  0.2 °C Specific Conductance:  $\pm$  5% Dissolved Oxygen: all readings  $\leq$  20% saturation (see Table FS 2200-2); optionally,  $\pm$  0.2 mg/L or  $\pm$  10% (whichever is greater) Turbidity: all readings  $\leq$  20 NTU; optionally  $\pm$  5 NTU or  $\pm$  10% (whichever is greater)


APPENDIX B
ANTIMONY CONCENTRATION VS WATER ELEVATION PLOTS

Well MW-1 **Antimony Concentration vs Water Elevation** 




-- 🖷 - - Water Level 


Well MW-2
Antimony Concentration vs Water Elevation




Well MW-5
Antimony Concentration vs Water Elevation




Well MW-7A
Antimony Concentration vs Water Elevation




Well MW-8
Antimony Concentration vs Water Elevation




Well MW-10
Antimony Concentration vs Water Elevation



Well MW-11
Antimony Concentration vs Water Elevation



Well MW-13
Antimony Concentration vs Water Elevation



-- - Water Level -- Anitmony

# APPENDIX B PUBLIC NOTICE

North Hillsborough Edition

Market

Hillsborough Market

FOR SALE

FREE SATE CHEET IVES NOTEM IN O EQUIPMENT TO BUT IF FEED IN SELECTION OF A ROOMS! FREE HOTS PACSIVETS FREE Digital Video Recorders that Record 100 Hours of Your Revolute Shows! CALL NOW: 1-877-998-DISH Extension 2 17545.

GOODBYE CABLET FREE! Movies

or 3 months, PREE, Receivers & DVR st.
Pades TV-Store 100 Hours) FREE Local
Channest FREE, Month of Service FREE
Installation 150 7 Asinets, \$19,99, tuly fed
time Offet IC Der NOW 1, 877,096, DISH
Eart, 198280, Godo A 2004 st. bur website; www.tl.sblecable.to/SAPA

MAKE & QUIL BOY EDSPARKS IFLY NGAIN Keep vour House Fires De single Seinstlonal, Remants Exwe sith Principle Anorthable Amplyersery Celebrators Beast Want to Wins a Great Loya Letter vi Isa's

Memorable Party? www.SweetLove Gifts.com.SAPA

A+ POOL HEATERS FEACTORY DI RECT Solar Heat R/Imp or Osse Complete do it yourself pool heater Rits. Phone quotes prestallation a wileble in most seres. Liseo 296.0951 a. 15 www.poetneogysuberMarketrom Lieu fc.WCo29239 in sures. Deater inquines welcome [2]

FURNITURE

HEALTH & EQUIPMENT

A POWERFUL WAY TO SAVE!

Solf-Employed, Under-Insured, Uninsured? Save up to SPX-or more on Healthcare Services

This is not insurance. 1.6 aons, start as low as \$10.99 per mont

For Information Call Carolo 813-433-6553

Call Me Now

and I-Will Help You

Weight and Health

First of the Year! Call Call

13 453 1386 IC

Back in Control

Get Your

after the

You may choose one market or more

Reach up to 12000 home and businesses

Phone: 909-2800 \* Fax: 909-7391

Email: classifieds@cnewspublications.com

POLICIES

### BUILDING MATERIALS

ALL STEEL BLDGS UP TO 50% OFFI! Engineered for Hurricane Coast! Ship Factory Direct for quick delivery: . 24x30 Up to 100x2001 Call Nowl. (800)499:6401 Eddlenf)

BUILDING SALET, Extended 31Wockh! 20/25 Now \$3340, 25/30, \$4790, 30/40, 17/340, 40/60, \$11,490 Factory Direct, 25/years, Many, Others, Endstaccessories optional. Pioneer (800)868-5422.(1)

whyour Norwood portablest and shawhile Log skildders allo available, www.norwoodindustries.com/Eres\_Information: (800)678-1363.ext300N (f)

STEEL BUILDINGS, Factory Clear ance. New, newer erected 30x40, 40x60, 50x100 and 60x100. Will Sell for balance Call Frank (800)803-7982 (f)

xy METAL ROOFING SAVE \$55 Buy Di-rectly from Manufacturer 20 chiefs in stock with all Accessories, Quick furn around! Delivery Available: foll Free (888)393-0335.

METAL: ROOFING, SIDING, Numerous Panel Polities for Besidential Commercial "Agricultural Street Stendard & Cus-4580 SAPA AND COMES AND SECONDS

CUMBERI? CIQUIDAAGAS HARD USEN SPECIAL WAS SENTED USES OF WOOD PLOORING from Selectifies of USEN \$ 199 From F Meyak (addelnie / Spracks) Bir Burglor (Mandias) (etc. Nam (etc.) Will all dessated a pasak addel anota a beliven evellas are all.

### COMPUTERS

NEW COMPUTER LBIDE Hippo Funding. guarantees your approval for a computer regardless of your credit. All you need is a checking account to be approved 1-800-507-4055. Callinow for free behalf. SAFA

### FOR SALE

NEW & UNPRECEDENTED ELECTION OF THE

World removered FULLIFIC BRUSH COmis officing a new cash generating bond business that includes this FREE Starter Kit - FREE Website PRE Training TREE Supervision For more information, please call

(813) 469-7092 or writesto: 14 and PO Box 83 • Crystal Springs, FL 33524 cmail: zbumperone@verizost.net

A BEST CHOICE BICYCLE Has a targe.
Dhiistmas Selection of Adult 3 Wheel Titkes, Recumbents, Cruisers, Big Fat Seats, Baskets 8 More at All Time Low-Prices (8622 Land O'Lakes Blvd. 813-996-1263 www.lerrycarbika.com

A+ POOL HEATERS - FACTORY DI-BECT Southfall Fundant Lat Complete do-thyourself pool heater kills, Prone

PDECORATIVE FRUIT ACCEPT PIECES SaldPopper, Very Pretty \$850 p. Call 813-654-8877 LARGE HEALTHY CHINESE PALM TREE

SPA EQUIPMENT

30' Tall \$50 OBO Call 813;828-2325

tanning and etc. Call 813-909-4711 or 813-390-0019

BRING THE BEST of New Orleans to your home. Specializing in Pewter and Cast for Fleur de Lis Home Decor. Shop online at www.FrenchQuarterMarket.com

DIRECTV 4000M18YSTEMETHEE\* In 2 The Lowest Brescription Price of t Citiling permistion St Delly W. Program ... III minut Astudias 529199 (all to the places) ... III Tout Cable hotayl cantor beauty of 560 years 1841290 or www.satellite-contact too.com SAPA

AND THE PARTY OF THE PARTY.

OXYGEN USERS: Enjoy more treedom to travell (Oxife's lightweight, Oxygen concentrators and off your car & in your home, 3.8-5 LPM U.S.A. made: Warranteed 1-806-760-2616 www.oxlifeinc.com

Automotive

Employment Monthly rains bely 14 Papers ... 179/1109

Classified liner rates.

Real Estate 33 Lines, up to 14 Papers .... \*99/\*129 Classified Ads Deadline is Friday @ Noon before publishing week

### HEALTH & EQUIPMENT

AFFORDABLE HEALTH PLAN as low

FAMILY HEALTHICARE

l Vision Pre-existing Condi-III. WCS 1,800-288-9214 Ext. NEW MOTORIZED FEATHERWEIGHT

LEVITHA VIAGRA Musicle Helaxerii Pain Heusti Viccer Ordina 1998 Proebusto x com opt 888 773-6230 FDA approved drug Sofra, transcol Carisob rodol, Fiolicet, Viagra, Levitra and morell US Licensed Physicians Pharmadis 2009

NEW MADIORIZED WHEELCHAIRS
NO COST MEIGIBLE SCOOLER TYPE
Hospinise CS Manual Chairs We accept Medicar A Private Insurance Fre
Delivery Helping Hands Medicar Eurip
ment Call, Toller see 1377 567 7066 pta
James Espanon CS 1444

### SHEDS / CARPORTS

Garattee, 'Barns + Capporass Carpolass standing See (12') of the call inized steel. 2. Styles +1.4 Colors to release steel. 2.

### ADULT CAREGIVER

Immediate Opening for Live-In Caregiver.

Also iP/T-Positions Available: Duties 8000 diliteiuse

Companion Care of Tampa Bay 866-907-2229

# DIRECT CARE Stout Homenist in Pares opineral to Disease is moved by Proposed by All Proposed by All Incina 0-1/2000 pp. 17 proposed by All Incina 0-1/2000 pp. 17 proposed by All Incina 0-1/2000 pp. 17 proposed by Pares at 170-1700 pp. 17 ADULT EDUCATION

ADULT HIGHTSCHOOL DIPLOMA IS

the own process of the second materials DEGREES/ONLINE ROMHOME

www.onlinetidewatertech.com, SAPA HIGH SCHOOL DIPLOMAN! Graduate in 4 weeks the Elbrochure CALL NOW, 1-880-532-6546 Ext 442 www.commentmacademy.com/SAPA4

### FINANCIAL

ROTHIRA OR THAD HONAL IRA Which the will a period and Call Mark to Multiply John 237 313-532 9700 ext. 237

ury Lawsuit Presidings Weense BC 1099, with its 48 hours Its suil Aeses apply in wear support 0.5588-83213 of a www.lew.Capthilli PA

SOLUTE BEST PRICE paid t CALL: 1.718-376-0894; SAPA

THE REPORT OF THE PARTY OF

### FINANCIAL

HAVE A WORRY FREE HOLIDAY Season with your personal fluid ross under control: Improve your cash flow reduce high interest rate payment gradin cardidebt. Poor credit welcome: Call 1-877-238-5157. SAPA

### **LEGAL SERVICES**

ARRESTEB - NEED A LAWYER? AN COMMON Defense Felanies Mes freezons 1801/17 Autoroblis Accident Domestic Violence Wrongfull Death Recent Your Alignes A-A Attorney Referral Service (888)733-5342 24HOURS 7 days a WEEK (I)

DIVORCES275-\$350 COVERS chi drens etd. Only one signature required (Excludes boyt, feest Call weekdays (800)462-2000, ext.600. (8am-7pm) Aha Divorce, LUC, Established 1977 (f)

### LEGAL, NON-ATTORNEY

BANKRUPTCY INCORPORATION DIVORCE

LOW REES - Payment Plan ✓ Missing Spouse Divorce \* MEICOME TO YOU :--Court Bocument Services 1-888-705:7221

**的问题是是自我的证明,不是就是由的** 

### PET SERVICES

CRITTER SITTER, UNLIMITED Reliable loving care for your pets in the comfort of their own, one or barnwhile you are away. Licensed. References. Patricia 813-995-0027

#### SERVICES OFFERED

Need Cash for your business?

We provide unlimited working capital without debt for most

growing businesses Government Contractors · Importers

Construction Subs CALL DAN AT

813-963-1642 dan@fundsinmotion.com



U.S. Environmentalle rotection Agency, Region 4 Announcestal ive - Year Review

for the Normandy Park Apartments Site. Temple Terrace, Hillsborough County, Florida The U.S. Environmental Projection Regardy (EPA) is conducting a Five Veter Royle wor the remedy for soil

and proceedings commingtion associated with the Normandy Park Apartments Size (the Size) in Temple Telephone Illaborough Goenty, Florida "The Site, which covers about 5.2, wores, then it, a mixed residential ming of Free of Temple Territor at 11110 N. 56\* Street

Configuration of the Configuration of Configuration of Configuration of the Configuration of Configuration o

teet of soil for in the southern confront uses. The expressed marginals were replaced with clean fill. Ground warm on the linear ways and research through the ball of confidence of

. The RAWAY completed in 2001 of the NAP requires that wind first of the land and an entire to the pit stances polarant for commining remaining scripts be ployed by less an allow top inflatited use, and utilities a construction of several every low years to ensure protection of numerical library the onionis the Trix of these Rives rain Rawleys will be completed at 2009, each (2)

The content of the co to gatherpare it a community interview, are taked to overact. ME BE Delegation

Mt Bill Desman Profit in the second 61 Forsyth St. (11<sup>th</sup> Floor) U.S. EPA, Region 4 Affanta, GA 30303-8936

Patienation Basis

# APPENDIX C LISTING OF REPORTS REVIEWED

### **Listing of Reports Reviewed**

1. Focused Baseline Human Health Risk Assessment, Normandy Park Apartments, Temple Terrace, Florida

By: Hazardous Substance & Waste Management Research, Inc

Tallahassee, Florida Date: April, 1999

2. Streamlined Remedial Investigation, Normandy Park Apartments, 11110 North 56<sup>th</sup> Street, Temple Terrace, Florida

By: QORE Property Sciences 1211 Tech Boulevard, Suite 200

Tampa, Florida 33619 Date: June 30, 1999

3. Record of Decision, Summary of Remedial Alternative Selection for the Soil and Groundwater, Normandy Park Apartments, Temple Terrace, Hillsborough County, Florida By: United States Environmental Protection Agency

Date: March 11, 2000

4. Remedial Design/Remedial Action Work Plan, Normandy Park Apartments, Temple Terrace, Florida for Gulf Coast Recycling, Inc.

By: QORE Property Sciences 1211 Tech Boulevard, Suite 200

Tampa, Florida 33619 Date: February 13, 2001

5. Revised Sampling and Analysis Plan, Remedial Design Ground Water Sampling, Normandy Park Apartments, Tampa, Florida for Gulf Coast Recycling, Inc.

By: QORE Property Sciences 1211 Tech Boulevard, Suite 200

Tampa, Florida 33619 Date: February 13, 2001

6. Remedial Action Construction Report, Normandy Park Apartments, Temple Terrace, Florida for Gulf Coast Recycling, Inc.

By: QORE Property Sciences 1211 Tech Boulevard, Suite 200

Tampa, Florida 33619 Date: January 25, 2002

7. October 2005 Sampling Event, Remedial Action Ground Water Sampling, Normandy Park Apartments, Tampa, Florida for Gulf Coast Recycling, Inc.

By: QORE Property Sciences 1211 Tech Boulevard, Suite 200

Tampa, Florida 33619 Date: January 11, 2006

# APPENDIX D SITE INSPECTION FORM

Please note that "O&M" is referred to throughout this checklist. At sites where Long-Term Response Actions are in progress, O&M activities may be referred to as "system operations" since these sites are not considered to be in the O&M phase while being remediated under the Superfund program.

### **Five-Year Review Site Inspection Checklist (Template)**

(Working document for site inspection. Information may be completed by hand and attached to the Five-Year Review report as supporting documentation of site status. "N/A" refers to "not applicable.")

I. SITE INFORMATION	
Site name: NORMANDY PARK APARTMENTS	Date of inspection: 12/13/05
Location and Region: Temple Tremace, FL	EPA ID: FLS 984229773
Agency, office, or company leading the five-year review: EPA REGION 4	Weather/temperature:
Remedy Includes: (Check all that apply)  Landfill cover/containment Access controls Institutional controls Groundwater pump and treatment Surface water collection and treatment Other	
Attachments: Inspection team roster attached Site map attached	
II. INTERVIEWS (Check all that apply)	
Name     Interviewed at site at office by phone Phon     Problems, suggestions; Report attached	Title Date e no.
Name     Interviewed at site at office by phone Phon     Problems, suggestions; Report attached	Title Date e no

A				
Agency				
Name		Title	Date	Phone
Problems; suggestions;				
Agency				
Contact				
Name Problems; suggestions;		Title	Date	Phone
				<u> </u>
Agency		and the second second		
Name Problems; suggestions;		Title	Date	· Phone
			<del></del>	<del>-</del>
Agency				
ContactName		Title	Date	Phone
Problems; suggestions;	Report attached			
Other interviews (option	nal) Report attache	ed.	•	<del></del>
<del></del>				
				—————
·			· · · · · · · · · · · · · · · · · · ·	
		·		<del>.</del> .
	·			·
•			•	
	<del></del>			

	<del></del>				
	III. ON-SITE DOCUMENTS & REC	CORDS VERIFIED (	Check all that app	ly)	
	O&M Documents O&M manual As-built drawings Maintenance logs Remarks	Readily available Readily available Readily available	Up to date Up to date Up to date	N/A N/A N/A	-
	Site-Specific Health and Safety Plan Contingency plan/emergency response plan Remarks	Readily available Readily available		N/A N/A	-
	O&M and OSHA Training Records Remarks	Readily available	Up to date	N/A	<u>.</u>
	Permits and Service Agreements Air discharge permit Effluent discharge Waste disposal, POTW Other permits	Readily available Readily available Readily available Readily available	Up to date	NA NA NA	
.i.	Gas Generation Records Readily Remarks	available Up t	o date. N/A	)	
		Readily available	Up to date	N/A	
_	Groundwater Monitoring Records (Remarks Located at nearby le	Readily available	Library	N/A	
	Leachate Extraction Records Remarks	Readily available	Up to date	N/A	
	Discharge Compliance Records Air Water (effluent) Remarks	Readily available Readily available	Up to date Up to date	N/A N/A	. :
•	Daily Access/Security Logs Remarks	Readily available	Up to date	N/A	-

	·				IV. O&M COSTS		
1.	PRP Feder	in-house in-house ral Facili	ty in-ho		Contractor for State Contractor for PRP Contractor for Feder	ral Facility	
2.	Read Fund	Cost Recily availating mechanical	able nanism/a cost estin				
	From	Date Date	To To	Date Date	Total cost  Total cost	Breakdown attached Breakdown attached Breakdown attached	
		Date Date		Date Date Date	Total cost  Total cost	_ Breakdown attached _ Breakdown attached	
3.							
	<del></del>	V. ACC		ND INSTI	TUTIONAL CONTRO		
A. F	encing						
1.	Fencing Remark		ed	Locat	ion shown on site map	Gates secured	N/A
В. О	ther Acces	s Restric	ctions	-			
1.				y measure	es Location sh	own on site map N/A	

C. Inst	itutional Controls (ICs)			
1.	Implementation and enforcement Site conditions imply ICs not properly implemented Site conditions imply ICs not being fully enforced	Yes Yes	No No	N/A N/A
	Type of monitoring (e.g., self-reporting, drive by) Frequency			
	Responsible party/agency Contact			
	Name Title	Date		Phone no.
	Reporting is up-to-date Reports are verified by the lead agency	Yes Yes	No No	N/A N/A
	Specific requirements in deed or decision documents have been met Violations have been reported Other problems or suggestions: Report attached	Yes Yes	No No	N/A N/A
<u></u>				
2	Adequacy ICs are adequate ICs are inadequate Remarks			N/A
D Co-				
D. Gen		dalism ev	ident	)
2.	Land use changes on site N/A  Remarks			
3.	Land use changes off site N/A  Remarks Private School + City Public Wor  Mest of the Site.	ks c	0.5	fracted
	VI. GENERAL SITE CONDITIONS			
A. Roa	ds Applicable N/A			
1.	Roads damaged Location shown on site map Roads a Remarks_	dequate		N/A

B. Oth	ner Site Conditions
	Remarks
	VII. LANDFILL COVERS Applicable N/A
A. Lai	ndfill Surface
1.	Settlement (Low spots)  Areal extent  Remarks  Location shown on site map  Settlement not evident  Depth  Remarks
2.	Cracks Lengths Lengths  Widths Depths  Remarks  No 51 grift cart  Cracking not evident
	Erosion Location shown on site map Erosion not evident  Areal extent Depth  Remarks
4.	Holes  Location shown on site map  Areal extent  Remarks  Depth  Remarks
5.	Vegetative Cover Grass Cover properly established No signs of stress Trees/Shrubs (indicate size and locations on a diagram) Remarks
6.	Alternative Cover (armored rock, concrete, etc.)  Remarks
7.	Bulges Location shown on site map Bulges not evident Areal extent Height

8.	Wet Areas/Water Damage Wet areas Ponding Seeps Soft subgrade Remarks	Wet areas/water damage not Location shown on site map	Areal extent Areal extent Areal extent
9.	Slope Instability Slides Areal extent Remarks	Location shown on site map	No evidence of slope instability
B. Ben	(Horizontally constructed moun	N/A ds of earth placed across a steep land ty of surface runoff and intercept a	ndfill side slope to interrupt the slope and convey the runoff to a lined
1.	Flows Bypass Bench Remarks	Location shown on site map	N/A or okay
2	Bench Breached Lo Remarks	cation shown on site map	N/A or okay
3	Bench Overtopped Remarks	Location shown on site map	( ' '
		trol mats, riprap, grout bags, or gab allow the runoff water collected by	
1.	Settlement Lo Areal extent Remarks	Depth	o evidence of settlement
2.	Material Degradation Lo Material type Remarks	cation shown on site map N Areal extent	o evidence of degradation
3	Areal extent Remarks	cation shown on site map N Depth	o evidence of erosion

4.	Areal extentRemarks	Location shown on site map Depth		
5.	Obstructions Type_ Location shown on sit Size Remarks	e map	Areal extent	<u>·</u>
6.	Excessive Vegetative G No evidence of excess Vegetation in channel Location shown on sit Remarks	ive growth s does not obstruct flow e map	Areal extent	
D. Co	ver Penetrations App	licable N/A		
1.	Gas Vents  Properly secured/locke Evidence of leakage at N/A Remarks	ed Functioning R penetration	Needs N	ed Good condition Maintenance
	Gas Monitoring Probes Properly secured/locke Evidence of leakage at Remarks	ed Functioning R penetration		ed Good condition  Maintenance N/A
3.	Evidence of leakage at	ed Functioning R penetration	outinely sample Needs N	ed Good condition Maintenance N/A
4.	Leachate Extraction W Properly secured/locke Evidence of leakage at Remarks	ed Functioning R penetration	outinely sample Needs N	ed Good condition Maintenance N/A
5.	Settlement Monuments Remarks			ly surveyed N/A

E. Gas	Collection and Treatment	Applicable	N/A)		
1.	Gas Treatment Facilities Flaring Good condition Remarks	Thermal destruction Needs Maintenance	Collection for r	euse	<del>- \                                   </del>
2.	Gas Collection Wells, Mar Good condition Remarks	Needs Maintenance			
3.	Gas Monitoring Facilities Good condition Remarks	Needs Maintenance	N/A	uildings)	
F. Cov	er Drainage Layer	Applicable	N/A)		
1.	Outlet Pipes Inspected Remarks	Functioning	N/A		
2.	Outlet Rock Inspected Remarks	Functioning	N/A		
G. Det	ention/Sedimentation Ponds	s Applicable	,N/A	)	
1.3	Siltation Areal extent Siltation not evident Remarks	•		N/A	
2.	Erosion Areal exte Erosion not evident Remarks	ntDo	•	· · · · · · · · · · · · · · · · · · ·	
3.	Outlet Works Remarks	Functioning N/A			
4.	Dam Remarks	Functioning N/A	Loine		

H. Retain	ning Walls	Applicable (	V/A	
I- R	Deformations Horizontal displacement Rotational displacement Remarks	Ven	tical displacem	Deformation not evident ent
	Degradation Cemarks		ı site map	Degradation not evident
I. Perime	ter Ditches/Off-Site Disch	arge /	Applicable	(N/A
A	iltation Location	Depth		t evident
A	Vegetative Growth Vegetation does not impedareal extent	le flow Type		N/A
A	real extent	Depth		Erosion not evident
	Pischarge Structure Lemarks		I/A	
	VIII. VERTIC	CAL BARRIER W	ALLS A	pplicable N/A
A	ettlement real extent emarks			Settlement not evident
F H	Performance Monitoring Ty Performance not monitored requency	d	-	ee of breaching

	IX. GROUNDWATER/SURFACE WATER REMEDIES	Applicable N/A
A. Gr	oundwater Extraction Wells, Pumps, and Pipelines	Applicable (N/A)
1.	Pumps, Wellhead Plumbing, and Electrical Good condition All required wells properly operating Remarks	Needs Maintenance N/A
2.	Extraction System Pipelines, Valves, Valve Boxes, and Other Ap Good condition Needs Maintenance Remarks	•
3.	Spare Parts and Equipment	le Needs to be provided
B. Su	rface Water Collection Structures, Pumps, and Pipelines Ap	plicable (N/A)
1	Collection Structures, Pumps, and Electrical Good condition Needs Maintenance Remarks	
2	Surface Water Collection System Pipelines, Valves, Valve Boxes Good condition Needs Maintenance Remarks	
3.	Spare Parts and Equipment Readily available Good condition Requires upgrade Remarks	e Needs to be provided

c.	reatment System Applicable NA	
1.	Treatment Train (Check components that apply)  Metals removal Oil/water separation Bioremediation  Air stripping Carbon adsorbers  Filters  Additive (e.g., chelation agent, flocculent)  Others  Good condition Needs Maintenance  Sampling ports properly marked and functional  Sampling/maintenance log displayed and up to date  Equipment properly identified  Quantity of groundwater treated annually  Quantity of surface water treated annually  Remarks	
2.	Electrical Enclosures and Panels (properly rated and functional)  N/A Good condition Needs Maintenance  Remarks	
3.	Tanks, Vaults, Storage Vessels  N/A Good condition Proper secondary containment Needs Maintenance Remarks	
4.	Discharge Structure and Appurtenances     N/A Good condition Needs Maintenance Remarks	
5.	Treatment Building(s)  N/A Good condition (esp. roof and doorways)  Chemicals and equipment properly stored  Remarks	
6.	Monitoring Wells (pump and treatment remedy) Properly secured/locked Functioning Routinely sampled Good condition All required wells located Needs Maintenance N/A Remarks	
D.	onitoring Data	
1.	Monitoring Data  Is routinely submitted on time  Is of acceptable quality	
2.	Monitoring data suggests:  Groundwater plume is effectively contained Contaminant concentrations are declining	

onitored Natural Attenuation
Monitoring Wells (natural attenuation remedy) Properly secured/locked Functioning Routinely sampled Good condition All required wells located Needs Maintenance N/A Remarks
X. OTHER REMEDIES
there are remedies applied at the site which are not covered above, attach an inspection sheet describing the physical nature and condition of any facility associated with the remedy. An example would be soil apor extraction.
XI. OVERALL OBSERVATIONS
Implementation of the Remedy
Describe issues and observations relating to whether the remedy is effective and functioning as designed. Begin with a brief statement of what the remedy is to accomplish (i.e., to contain contaminant plume, minimize infiltration and gas emission, etc.).
Adequacy of O&M
Describe issues and observations related to the implementation and scope of O&M procedures. In particular, discuss their relationship to the current and long-term protectiveness of the remedy.

# APPENDIX E INTERVIEW FORM

#### INTERVIEW FORM Apartment Resident #1

1. Are you aware of the former environmental issues at the Apartments and of the cleanup actions that took place?

Yes, she was a resident at that time.

2. What is your overall impression of the cleanup project?

Based on her knowledge of the project, she thought if was very good.

3. What effects have this Site had on the surrounding community, if any?

None that she was aware of.

4. Are you aware of any community concerns regarding the Site?

Not at this time. She came to Tampa in 1992 but, at first, did not live at the apartments due to the contamination. She later moved to Normandy Park about 8 years ago.

5. Do you feel well informed about the Site's activities and progress?

She felt well informed when the work was being done, but not since then.

6. Do you have any comments, suggestions, or recommendations regarding the cleanup work completed at the site and EPA's management of it?

None that she can think of.

### INTERVIEW FORM Apartment Resident #2

1. Are you aware of the former environmental issues at the Apartments and of the cleanup actions that took place?

She was aware when the excavation was ongoing. She worked a lot so she was not intimately aware of what was going on. Her son knew more about it than she did.

2. What is your overall impression of the cleanup project?

She thought the site looked fine.

3. What effects have this Site had on the surrounding community, if any?

None of which she was aware.

4. Are you aware of any community concerns regarding the Site?

None that she knows of; however, she doesn't get out much anymore to talk to very many other people.

5. Do you feel well informed about the Site's activities and progress?

She was not really aware of what was going on or why; however, her son had kept abreast of what was going on.

6. Do you have any comments, suggestions, or recommendations regarding the cleanup work completed at the site and EPA's management of it?

No, she thought every thing was fine.

#### **INTERVIEW FORM**

Diane Lee – President, DLG Management Services
Amy Flanagan – Property Manager (DLG) and Resident
(Interview was performed jointly)

1. Are you aware of the former environmental issues at the Apartments and of the cleanup actions that took place?

Yes, DLG was managing the facility at the time of the cleanup. Amy has been living at the complex for three years and was not aware that contaminated soils remained on site. She thought that the ground water monitoring that was being performed was to make certain that the contamination didn't come back. Neither was aware of the need to notify anyone if the soil under the buildings, parking lot and so forth, was exposed or needed to be excavated. They had been providing notices to new and potential tenants about the site history but had stopped several years ago; however, the complex has a very low turnover rate. Diane requested a write-up of what was done and the restrictions on site to provide to her maintenance personnel.

2. What is your overall impression of the cleanup project?

They thought it was very good.

3. What effects have this Site had on the surrounding community, if any?

They thought the work was a positive improvement.

4. Are you aware of any community concerns regarding the Site?

Not that they were aware of.

5. Do you feel well informed about the Site's activities and progress?

Somewhat – they knew of the ground water monitoring but not the purpose for it and, as noted above, they were unaware of the restrictions on the unexcavated soils; however, they had not ever had any inquiries other than one person who had found it on a website (see Joyce Morales-Caramella Interview Form).

6. Do you have any comments, suggestions, or recommendations regarding the cleanup work completed at the site and EPA's management of it?

They couldn't think of anything.

## INTERVIEW FORM Diana Colon – Leasing Agent (DLG) and Resident

1. Are you aware of the former environmental issues at the Apartments and of the cleanup actions that took place?

She has lived at the complex for only about one year. She had heard about the cleanup/environmental issues in a peripheral way but otherwise did not know what was done.

2. What is your overall impression of the cleanup project?

She thought it was adequate.

3. What effects have this Site had on the surrounding community, if any?

She was not aware of any.

4. Are you aware of any community concerns regarding the Site?

She had not heard of any concerns.

5. Do you feel well informed about the Site's activities and progress?

Yes, she felt well informed.

6. Do you have any comments, suggestions, or recommendations regarding the cleanup work completed at the site and EPA's management of it?

She was concerned about impacts to the water at the complex. Bill Denman explained that the complex was on City water and that the residents were not drinking or using contaminated water from the site. She was satisfied with this explanation.

#### INTERVIEW FORM

Frankie Acuna - Maintenance Man (DLG) Victor Claudio - Maintenance Man (DLG) (Interview was performed jointly)

1. Are you aware of the former environmental issues at the Apartments and of the cleanup actions that took place?

Neither was aware of what had gone on at the site. Frankie had worked at the site for only about 2 months and Victor had only been there a month. Neither was aware of the restrictions with respect to exposing or excavating the soil from under the sidewalks, pavement, buildings and so forth. Bill Denman and Joyce Morales-Caramella (GCR) explained what had occurred, what the restrictions were and why they were necessary. Both seemed to understand.

Due to their short timeframe at the site and lack of site history, none of the remaining were applicable (NA).

2. What is your overall impression of the cleanup project?

NA

3. What effects have this Site had on the surrounding community, if any?

NA

4. Are you aware of any community concerns regarding the Site?

NA

5. Do you feel well informed about the Site's activities and progress?

NA

6. Do you have any comments, suggestions, or recommendations regarding the cleanup work completed at the site and EPA's management of it?

The areas of contaminated soil should be identified and procedures set up to notify future maintenance workers of the restrictions at the site.

#### NORMANDY PARK APARTMENTS FIRST FIVE-YEAR REVIEW

EPA Questions Asked of Joyce Morales-Caramella – December 2005

#### 1. What is your overall impression of the project?

The remediation project went well and was finished in a timely manner with very few problems. EPA, Gulf Coast Recycling, Inc. (GCR) and GCR's consultants worked well together.

#### 2. How well do you believe the remedy is performing?

The remedy is performing as expected. Natural attenuation of groundwater is going to take more time.

3. Have all institutional controls contained in the Record of Decision been implemented? If not, please provide a schedule for implementation.

No, the restrictive covenant is not yet in place. According to Bill Taylor, Mr. Green, the property owner, signed the covenant several months ago (shortly after meeting with Ms. West in Atlanta). The document was supposedly notarized and it was assumed it was sent to Ms. West. When recently questioned, Mr. Taylor's paralegal assistant stated the notarized document was sent to the corporate office for Metalico, but no one can explain why. Metalico is looking for the document, but I'm not confident it will be found. I spoke with Mr. Taylor on Monday, December 12, 2005, and he stated that a new document would be signed, notarized and filed in Hillsborough County before the end of 2005.

4. Has the maintenance of the monitoring wells and hard surfaces such as parking lots and sidewalks been implemented as intended? Please describe your role in the O&M of the remedy.

The wells are maintained by QORE on behalf of GCR. There have been no problems noted with the flush-mount wells. The property owner maintains the sidewalks and other hard surfaces. QORE visits the property quarterly and I visit the property every three to four months.

5. Have you received any complaints or inquiries from residents of the Apartments since implementation of the remedial action, regarding environmental issues or the remedial action? If so, please explain.

Immediately upon completion of the remedial action complaints were received from residents of the complex regarding the elimination of the private decks in the southern complex.

There was a problem with stormwater ponding in the northern complex shortly after the remedy was completed. WRS Infrastructure and Environment corrected the drainage problem.

One other complaint was forwarded to me from Bill Denman and the Environmental Protection Commission of Hillsborough County (EPC) that a resident was complaining of battery chips in the complex. Bill Weston (the GCR Operations Manager) and I walked every inch of the site and found a couple battery chips near the roots of one of the big oak trees in the northern complex. I spoke with the complainant and she stated that she had never told anyone that she had seen battery chips, but rather she had reviewed historic data on line and was concerned about the battery chips. Her concerns were diminished by the time I spoke with her since she was moving or had just moved. I explained the remediation that was done at the site and why.

### 6. Have there been unexpected O&M difficulties or costs at the site since start-up or in the last five years? If so, please give details.

It just recently came to my attention that the paving stones surrounding one of the trees, west of the tennis courts, are being dislodged by some of the older children in the complex. I brought this to the attention of the apartment manager after the stones were put back in place. If this continues, GCR will consider cementing the stones in place or replacing the stones with a wooden deck.

## 7. Have there been opportunities to optimize O&M, or sampling efforts? Please describe changes and resultant or desired cost savings or improved efficiency.

There has been a reduction in the frequency of sampling and in the number of parameters being sampled. Although additional wells were installed to properly assess the groundwater at the western property boundary, the number of parameters being analyzed at several other wells has been reduced. Also, the sampling frequency of several wells was reduced from quarterly to semiannually. All changes were made after receiving EPA's approval.

#### 8. Do you have any comments, suggestions, or recommendations regarding the project?

If not already being done, persons leasing apartments at Normandy Park should be notified of the remedial action taken at the site and should be notified regarding precautions that should be taken, such as not digging on the property, reporting broken sidewalks, etc.

# APPENDIX F RESTRICTIVE COVENANT

#### MACFARLANE FERGUSON & McMullen

ATTORNEYS AND COUNSELORS AT LAW

1501 SOUTH FLORIDA AVENUE LAKELAND, FLORIDA 33803 (863) 680-9908 FAX (863) 683-2849 ONE TAMPA CITY CENTER. SUITE 2000 201 NORTH FRANKLIN STREET P.O. BOX 1531 (ZIP 33601) TAMPA, FLORIDA 33602 (813) 273-4200 FAX (813) 273-4396 625 COURT STREET
P O. BOX 1669 (ZIP 33757)
CLEARWATER, FLORIDA 33756
(727) 441-8966 FAX (727) 442-8470

www.mfmlegal.com

EMAIL: info@mfmlegal.com

IN REPLY REFER TO:

Tampa

February 27, 2006

Kathleen West, Esq. Associate Regional Counsel EPA Region 4 Atlanta Federal Center 61 Forsyth St., SW Atlanta, GA 30303

Re: Normandy Park Superfund Site; 11110 N. 56<sup>th</sup> Street, Temple Terrace, Florida Declaration of Restrictive and Affirmative Covenants

#### Dear Kathleen:

Enclosed please find a copy of the fully executed Declaration of Restrictive and Affirmative Covenants for the above referenced matter. I have, by copy of this letter, sent a fully executed copy to Kelsey A. Helton at the Florida Department of Environmental Protection as well.

Should you have any questions, please do not hesitate to call.

Sincerely,

William P. Tavi

WBTIV:kkb Enclosure

c: Kelsy A. Helton

Joyce Morales-Caramella

Steve Green

INSTR # 2006068283 O BK 16094 PG 0022

Pgs 0022 - 33; (12pgs)

RECORDED 02/08/2006 04:53:41 PM PAT FRANK CLERK OF COURT HILLSBOROUGH COUNTY DEPUTY CLERK Y Roche

This instrument prepared by: William B. Taylor IV, Esquire Macfarlane Ferguson & McMullen P.O. Box 1531 Tampa, Florida 33601

### DECLARATION OF RESTRICTIVE AND AFFIRMATIVE COVENANTS

1. This Declaration of Restrictive and Affirmative Covenants ("Declaration" or "thi	S
instrument") is given this 9th day of JANUARY , 2006, by NORMANDY PAI	ek holdings
a FL corporation, ("Grantor"), having an address of IIIO N. 56TH STREE	
to the State of Florida Department of Environmental Protection ("Grantee").	33617

#### WITNESSETH:

- 2. WHEREAS, Grantor is the sole fee simple owner of a parcel of land located in the county of Hillsborough, State of Florida, more particularly described on Exhibit A attached hereto and made a part hereof (the "Property"); and
- 3. WHEREAS, the Property is part of the Normandy Park Superfund Site ("Site"), which the U.S. Environmental Protection Agency ("EPA"), pursuant to Section 105 of the Comprehensive Environmental Response, Compensation and Liability Act ("CERCLA"), 42 U.S.C. § 9605, proposed for the National Priorities List, set forth at 40 C.F.R. Part 300, Appendix B, by publication in the Federal Register in February, 1995; and
- 4. WHEREAS, The Superfund Streamlined Remedial Investigation and Focused Feasibility Study confirmed that soil was contaminated with lead, antimony and arsenic, and that groundwater is contaminated with lead and antimony in concentrations that exceed standards or recommended exposure or ingestion levels; and

- 5. WHEREAS, in a Record of Decision dated May 11, 2000 (the "ROD"), the EPA Region 4 Regional Administrator selected a "remedial action" for the Site, which provides, in part, for the following actions:
- excavation of the top two feet of exposed soil around the apartment complex
- removal of wooden deck in the southern complex and excavation beneath
- treatment of excavated soil via stabilization and offsite disposal placement of clean fill in excavated areas
- monitored natural attenuation of groundwater
- placement of institutional controls in the form of deed restrictions/restrictive and affirmative covenants to limit future use of soil and groundwater, ensure maintenance of the engineered remedy, and authorize site access for certain purposes; and
- 6. WHEREAS, with the exception of continued monitored natural attenuation of the groundwater, the remedial action has been implemented at the Site; and
- 7. WHEREAS, the parties hereto have agreed 1) to impose on the Property use restrictions as covenants that will run with the land for the purpose of protecting human health and the environment; and 2) to grant an irrevocable right of access over the Property to the Grantee and its agents or representatives for purposes of implementing, facilitating and monitoring the remedial action; and
- 8. WHEREAS, Grantor wishes to cooperate fully with EPA and the Grantee in the implementation of all response actions at the Site and Grantor deems it desirable and in the best interest of all present and future owners of the Property that such remediation proceed and that the Property be held subject to certain irrevocable restrictions and licenses, all of which are more particularly hereinafter set forth;

#### NOW, THEREFORE:

- 9. <u>Grant:</u> Grantor, on behalf of itself, its successors and assigns, in consideration of the recitals above, the terms of the Consent Decree in the case of the <u>United States v. Gulf Coast Recycling, Inc.</u>, Civil Action # 8:01-CIV-1191-T-24TBM, and other good and valuable consideration, the adequacy and receipt of which is hereby acknowledged, does hereby covenant and declare that the Property shall be subject to the restrictions on use set forth below, and does give, grant and convey to the Grantee, and its assigns, with general warranties of title, 1) an irrevocable use restriction and site access covenant of the nature and character, and for the purposes hereinafter set forth and 2), the perpetual right to enforce said covenants and use restrictions, with respect to the Property.
- 10. <u>Purpose:</u> It is the purpose of this instrument to convey to the Grantee rights to

facilitate the remediation of past environmental contamination and to protect human health and the environment by reducing the risk of exposure to contaminants. The covenants, terms, conditions, restrictions and grants contained herein shall touch and concern the Property; shall run with the land; shall apply to and be binding upon and inure to the benefit of Grantor and Grantee, their successors and assigns; and shall continue as a servitude running in perpetuity with the Property and with title to the Property.

11. <u>Restrictions on use:</u> The following covenants, conditions, and restrictions apply to the use of the Property:

The owner of the property shall notify EPA and Grantee prior to the disturbance of any existing structures\_ more particularly described on Exhibit B attached hereto and made a part hereof. These structures include but are not limited to *concrete* building foundations and asphalt parking lots. With the notification, the property owner shall also submit a plan for EPA and Grantee approval which addresses the soil underneath these structures consistent with the requirements of the ROD for the Site. The existing structures shall not be disturbed until EPA and Grantee have provided written approval of a plan for addressing the potentially contaminated soil underneath.


The owner of the Property will not construct any groundwater wells on the Property or use the groundwater for any purpose without receiving written prior approval from EPA and Grantee.

The owner of the Property shall maintain all asphalt byways and parking lots so as to ensure their protective purpose as a capping remedial measure consistent with the requirements of the ROD for the Site.

- 12. <u>Irrevocable Covenant for Site Access:</u> Grantor hereby grants to the Grantee, its agents and representatives, an irrevocable, permanent and continuing right of access at all reasonable times to the Property for purposes of:
  - a) Implementing the response actions in the ROD;
  - b) Verifying any data or information submitted to EPA and Grantee;
  - Verifying that no action is being taken on the Property in violation of the terms of this instrument or of any federal or state environmental laws or regulations;
  - d) Monitoring response actions on the Site and conducting investigations relating to contamination on or near the Site, including, without limitation, sampling of air, water, sediments, soils, and specifically, without limitation, obtaining split or duplicate samples;

- e) Conducting periodic reviews of the remedial action, including but not limited to, reviews required by applicable statutes and/or regulations; and
- f) Implementing additional or new response actions if the Grantee, in its sole discretion, determines i) that such actions are necessary to protect the environment because either the original remedial action has proven to be ineffective or because new technology has been developed which will accomplish the purposes of the remedial action in a significantly more efficient or cost effective manner; and, ii) that the additional or new response actions will not impose any significantly greater burden on the Property or unduly interfere with the then existing uses of the Property.
- 13. <u>Modification:</u> The above restrictions and covenants may be modified, or terminated in whole or in part, in writing, by the Grantee, executed by Grantee in recordable form, and such writing shall be recorded by Grantor.
- 14. (a) Reserved rights of Grantor: Grantor hereby reserves unto itself, its successors, and assigns, all rights and privileges in and to the use of the Property which are not incompatible with the restrictions, rights and covenants granted herein.
- (b) Reserved Rights of EPA: Nothing in this document shall limit or otherwise affect EPA's rights of entry and access or EPA's authority to take response actions under CERCLA, the NCP, or other federal law.
- (c) Reserved Rights of Grantee: Nothing in this document shall limit or otherwise affect Grantee's rights of entry and access or authority to act under state or federal law.
- 15. <u>Liability.</u> Grantor shall take responsibility for any costs or liabilities related to the operation, upkeep or maintenance of the Property. Grantor will assume all liability for any injury or damage to the person or property of third parties which may occur on the Property arising from Grantor's ownership of the Property. Neither Grantor nor any person or entity claiming by or through Grantor shall hold Grantee liable for any damage or injury to person or personal property which may occur on the Property. Grantor shall pay any and all real property taxes and assessments levied by competent authority on the Property.
- 15. <u>No Public Access and Use:</u> No right of access or use by the general public to any portion of the Property is conveyed by this instrument.
- 17. <u>Notice requirement:</u> Grantor agrees to include in any instrument conveying any interest in any portion of the Property, including but not limited to deeds, leases and mortgages, a notice which is in substantially the following form:

NOTICE: THE INTEREST CONVEYED HEREBY IS



Within thirty (30) days of the date any such instrument of conveyance is executed, Grantor must provide Grantee with a certified true copy of said instrument and, if it has been recorded in the public land records, its recording reference.

- 18. <u>Administrative Jurisdiction:</u> The state agency having administrative jurisdiction over the interests acquired by the State of Florida by this instrument is the Grantee. EPA is a third party beneficiary to the interests acquired by the Grantee under this instrument.
- 19. <u>Enforcement:</u> The Grantee shall be entitled to enforce the terms of this instrument by resort to specific performance or legal process. All remedies available hereunder shall be in addition to any and all other remedies at law or in equity, including CERCLA. Enforcement of the terms of this instrument shall be at the discretion of the Grantee, and any forbearance, delay or omission to exercise its rights under this instrument in the event of a breach of any term of this instrument shall not be deemed to be a waiver by the Grantee of such term or of any subsequent breach of the same or any other term, or of any of the rights of the Grantee under this instrument.
- 20. <u>Damages:</u> Grantee shall be entitled to recover damages for violations of the terms of this instrument, or for any injury to the remedial action, to the public or to the environment protected by this instrument.
- 21. <u>Waiver of certain defenses:</u> Grantor hereby waives any defense of laches, estoppel, or prescription.
- 22. <u>Covenants:</u> Grantor hereby covenants to and with the Grantee, that the Grantor is lawfully seized in fee simple of the Property, that the Grantor has a good and lawful right and power to sell and convey it or any interest therein, that the Property is free and clear of encumbrances, except those noted on Exhibit C attached hereto, and that the Grantor will forever warrant and defend the title thereto and the quiet possession thereof.
- 23. <u>Notices:</u> Any notice, demand, request, consent, approval, or communication that either party desires or is required to give to the other shall be in writing and shall either be served personally or sent by first class mail, postage prepaid,\_ referencing the Site

name and Site ID # 04XB, and addressed as follows:

To Grantor:

To Grantee:

NORMANDY PARK HOLDINGS 11110 N.56TH STREET TAMPA, FL 33617 Bureau Chief, Waste Cleanup FDEP M.S. 4505 2600 Blair Stone Road Tallahassee, FL 32399

To EPA:

U.S. EPA, Region 4
Waste Management Division
Superfund Remedial and Technical Services Branch
Section Chief, Section D
61 Forsyth Street, SW
Atlanta, GA 30303

24. Recording in Land Records. Grantor shall record this Declaration of Restrictive and Affirmative Covenants in timely fashion in the Official Records of Hillsborough County, Florida, and shall rerecord it at any time Grantee may require to preserve its rights. Grantor shall pay all recording costs and taxes necessary to record this document in the public records.

#### 25. General provisions:

- a) <u>Controlling law:</u> The interpretation and performance of this instrument shall be governed by the laws of the United States or, if there are no applicable federal laws, by the law of the state where the Property is located.
- b) <u>Liberal construction:</u> Any general rule of construction to the contrary notwithstanding, this instrument shall be liberally construed in favor of the grant to effect the purpose of this instrument and the policy and purpose of CERCLA. If any provision of this instrument is found to be ambiguous, an interpretation consistent with the purpose of this instrument that would render the provision valid shall be favored over any interpretation that would render it invalid.
- c) <u>Severability:</u> If any provision of this instrument, or the application of it to any person or circumstance, is found to be invalid, the remainder of the provisions of this instrument, or the application of such provisions to persons or circumstances other than those to which it is found to be invalid, as the case may be, shall not be affected thereby.
- d) <u>Entire Agreement:</u> This instrument sets forth the entire agreement of the parties with respect to rights and restrictions created hereby, and supersedes all prior

discussions, negotiations, understandings, or agreements relating thereto, all of which are merged herein.

- e) <u>No Forfeiture:</u> Nothing contained herein will result in a forfeiture or reversion of Grantor's title in any respect.
- f) <u>Joint Obligation:</u> If there are two or more parties identified as Grantor herein, the obligations imposed by this instrument upon them shall be joint and several.
- g) <u>Successors:</u> The term "Grantor", wherever used herein, and any pronouns used in place thereof, shall include the persons and/or entities named at the beginning of this document, identified as "Grantor" and their personal representatives, heirs, successors, and assigns. The term "Grantee", wherever used herein, and any pronouns used in place thereof, shall include the persons and/or entities named at the beginning of this document, identified as "Grantee" and their personal representatives, heirs, successors, and assigns. The rights of the Grantee and Grantor under this instrument are freely assignable, subject to the notice provisions hereof.
- h) <u>Termination of Rights and Obligations:</u> A party's rights and obligations under this instrument terminate upon transfer of the party's interest in the Property, except that liability for acts or omissions occurring prior to transfer shall survive transfer.
- i) <u>Captions:</u> The captions in this instrument have been inserted solely for convenience of reference and are not a part of this instrument and shall have no effect upon construction or interpretation.
- j) <u>Counterparts:</u> The parties may execute this instrument in two or more counterparts, which shall, in the aggregate, be signed by both parties; each counterpart shall be deemed an original instrument as against any party who has signed it. In the event of any disparity between the counterparts produced, the recorded counterpart shall be controlling.
- k) Nothing contained in this agreement shall preclude or in any other way hinder the sale and/or conversion of the property to condominiums.

IN WITNESS WHEREOF, Grantor has caused this Agreement to be signed in its name.

Executed this qt day of January, 2006.

MANAGER

#### [full mailing address of Grantor]

the corporation that executed the foregoing instrument, and acknowledged the said instrument to be free and voluntary act and deed of said corporation, for the uses and purposes therein mentioned, and on oath stated that they are authorized to execute said instrument.

Witness my hand and official seal hereto affixed the day and year written above.

JOHN M. MURRAY Notary Public, State of New York No. 4618009 Qualified in Westchester County Commission Expires May 31, 2007	Notary Public in and for the State of
	My Commission Expires:

Signed,	sealed a	nd delivered	I in the presenc	æ of: <b>(two w</b>	itnesses required)
---------	----------	--------------	------------------	---------------------	--------------------

Mitness  Mitness	Emely Mynroe	1-9-06
Witness	Print Namé	Date
lown Monus	LouisMonago	1.9.00
Witness	Print Name	Date

This Declaration is accepted this

day of lanuary 2006.

STATE OF FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION

Attachments:

Exhibit A

Exhibit B

Exhibit C

Legal Description of the Property

Existing Structures on the Property

Existing Liens and Encumbrances on the

Property

Jan. 11 2006 03:30FM F2

FAX NO. :9084971097


FROM : METALICO

#### Exhibit A

All of Lots B, C, D, E, F, G, H and J Block 23, and Lots B, C, D and E, Block 24, Less the East 114 feet thereof for the right of way for State Road No. S-583 (5<sup>th</sup> Street) in Section 15, Township 28 South, Range 19 East, Temple Terrace Subdivision, as recorded in Plat Book 25, Page 62, of the public records of Hillsborough County, Florida.

9050431.1





PAGE 03/03

BULF COAST RECYCLING

#### MacFarlane Ferguson & McMullen 201 N. Franklin Street Suite 2000 One Tampa City Center Tampa FL 33602 (813) 273-4200 FAX: (813) 273-4396

#### Lawyers Title Insurance Corporation

#### OWNERSHIP AND ENCUMBRANCE REPORT

Order No: 40309797LA

Customer Reference No: 4352-6

This will serve to certify that Lawyers Title Insurance Corporation has caused to be made a search of the Public Records of Hillsborough County, Florida, ("Public Records") as contained in the office of the Clerk of the Circuit Court of said County, from December 21, 1999 through January 24, 2006, at 8:00 a.m., as to the following described real property lying and being in the aforesaid County, to-wit:

#### Parcel 1:

Lot J, Block 23 of Temple Terraces in Section 15, Township 28 South, Range 19 East, as per map or plat thereof, recorded in Plat Book 25, Page 62, of the Public Records of Hillsborough County, Florida.

#### Parcel 2:

All of Lots B, C, D, E, F, G and H, Block 23, and Lots B, C, D and E, Block 24, Less the East 114 feet thereof, for the right of way for State Road No. S0583 (56th Street) in Section 15, Township 28 South, Range 18 East, Temple Terraces, as per map or plat thereof, recorded in Plat Book 25, Page 62, of the Public Records of Hillsborough County, Florida.

As of the effective date of this Report the apparent record fee simple title owner(s) to the above described real property is/are:

Normandy Park Holdings, Inc., a Florida corporation, by virtue of Warranty Deed recorded in Official Records Book 9980, Page 411.

The following liens against the said real property recorded in the aforesaid Public Records have been found:

- 1. UCC Financing Statement recorded in Official Records Book 11353, Page 61, as assigned in Official Records Book 12021, Page 778. (as to Parcel 2)
- 2. Mortgage and Security Agreement recorded in Official Records Book 11387, Page 591, as assigned in Official Records Book 12525, Page 1279. (as to Parcel 2)
- 3. Assignment of Leases and Rents recorded in Official Records Book 11387, Page 653. (as to Parcel 2)
- 4. Mortgage and Security Agreement recorded in Official Records Book 11697, Page 1132, as modified in Official Records Book 12427, Page 1515 and assigned in Official Records Book 15683, Page 1659. (as to Parcel 2)
- 5. UCC Financing Statement recorded in Official Records Book 11697, Page 1144. (as to Parcel 2)
- 6. UCC Financing Statement recorded in Official Records Book 11697, Page 1148. (as to Parcel 2)
- 7. Exparte Default Judgment Against Defendent recorded in Official Records Book 14298, Page 939, as rerecorded and certified in Official Records Book 14348, Page 1767.

- 8. Claim of Lien recorded in Official Records Book 14051, Page 290.
- 9. Notice of Lis Pendens recorded in Official Records Book 14354, Page 1309.
- 10. Final Summary Judgment of Forclosure and Order Taxing Costs and Attorney's Fees recorded in Official Records Book 15480, Page 1605.
- 11. Order Cancelling Foreclosure Sale recorded in Official Records Book 15607, Page 57 and Official Records Book 15664, Page 745.

NOTE: The 2005 Ad Valorem Taxes under Folio Number 200711-0000 were EXEMPT. (as to Parcel 1)

NOTE: The 2005 Ad Valorem Taxes under Folio Number 200709-0000 were PAID and the 2004 Ad Valorem Taxes for said Folio remain UNPAID. (as to parcel 2)

Public Records shall be defined herein as those records currently established under the Florida Statutes for the purpose of imparting constructive notice of matters relating to real property to purchasers for value and without knowledge.


This Report shows only matters disclosed in the aforesaid Public Records, and it does not purport to insure or guarantee the validity or sufficiency of any documents noted herein; nor have the contents of any such documents been examined for references to other liens or encumbrances. This Report is not to be construed as an opinion, warranty, or guarantee of title, or as a title insurance policy; and its effective date shall be the date above specified through which the Public Records were searched. This Report is being provided for the use and benefit of the Certified Party only, and it may not be used or relied upon by any other party. This Report may not be used by a Lawyers Title Insurance Corporation agent for the purpose of issuing a Lawyers Title Insurance Corporation title insurance commitment or policy.

In accordance with Florida Statutes Section 627.7843 the liability Lawyers Title Insurance Corporation may sustain for providing incorrect information in this Report shall be the actual loss or damage of the Certified Party named above up to a maximum amount of \$1,000.00.

IN WITNESS WHEREOF, Lawyers Title Insurance Corporation has caused this Report to be issued in accordance with its By-Laws.

Lawyers Title Insurance Corporation

# APPENDIX G SOIL SAMPLING RESULTS TREE PRESERVATION AREAS




<u>EFGEND</u>

---- TREE PRESERVATION AREAS

SOIL REQUIRING TREATMENT

SOIL SAMPLE LOCATION

290 LEAD CONCENTRATION FROM 0-1 FOOT COMPOSITE SAMPLE (mg/kg)



NORMA	NDY PA	ARK AP	ARTME	NTS	<u>.</u>
	_	_		— Пі	Τ-

2/3/06


JOB NO. FLATE NO. 2148M 10


Q O R E

1211 Tech Blvd. Suite 200 Tampa, Florida 33519 (813) 523-6545

COMPOSITE SOIL SAMPLE LEAD CONCENTRATIONS TREE PRESERVATION AREAS NORTH COMPLEX TEMPLE TERRACE, FLORIDA

osibreport/LEQI-NC-R1





# APPENDIX H LEAD AND ANTIMONY CONCENTRATION CHARTS

Chart 1





Chart 2



# APPENDIX I SITE PHOTOGRAPHS TAKEN MARCH 2006



1. View of playground area near sales office.



2. View looking south between north pool and tennis courts.



#### SITE PHOTOGRAPHS



3. West view across central apartment complex.



4. Tree plaza - southwest corner of central apartment complex.



#### SITE PHOTOGRAPHS



5. Tree Plaza - west building of central apartment complex.



6. Tree Plaza - west side of courtyard of central apartment complex.



#### SITE PHOTOGRAPHS



7. Tree Plaza - West building of south apartment complex.



8. West side of south building in south apartment complex.



#### SITE PHOTOGRAPHS



9. Northeast view across south apartment complex courtyard.



Tree Plaza - east side of south apartment complex courtyard.



#### SITE PHOTOGRAPHS